

Table 1 Scope of Utility Work

PROPOSED UTILITY WORK ITEMS (a.)		PARTY RESPONSIBLE FOR UTILITY WORK	ESTIMATED COST OF UTILITY WORK			ACTUAL UTILITY WORK ITEMS		ACTUAL/FINAL UTILITY WORK SCHEDULE OF VALUES			PULL/SPLICE FIBER & CUT-OVER TIMEFRAME (CALENDAR DAYS)
			SCDOT SHARE	UTILITY SHARE				SCDOT SHARE	UTILITY SHARE		
			PRIOR RIGHTS	NON-PRIOR RIGHTS	BETTERMENT			PRIOR RIGHTS	NON-PRIOR RIGHTS	BETTERMENT	
Pay Item & Description	QTY/UNIT	The existing 10-in sanitary sewer effluent discharge line is to be abandoned and filled with flowable fill, including removal of any appurtenances, along I-20 from approximate Station 49+00 RT to approximate Station 94+00 RT.				Pay Item & Description	QTY/UNIT				
Flow fill one (1) 10-in sanitary sewer effluent discharge line	200 CY	SCDOT In-Contract Work	\$ 0.00	\$ 100,000.00	\$ 0.00			\$	\$	\$	
								\$	\$	\$	
								\$	\$	\$	
								\$	\$	\$	
								\$	\$	\$	
		Total	\$	\$ 100,000.00	\$ 0.00			\$	\$	\$	

* - Preliminary estimated cost of utility work based on the schematic design. Actual/Final work schedule of values will be based on the SCDOT’s Contractor’s final design.

Items of Work	Amount
PROPOSED UTILITY WORK ITEMS (a.)	\$ 100,000.00
TOTAL	\$ 100,000.00