

GEOTECHNICAL DATA SUMMARY REPORT

**S-12-77 OVER FISHING CREEK
LANCASTER COUNTY, SOUTH CAROLINA
S&ME PROJECT NO. 1611-10-292**

Prepared For:



STV / Ralph Whitehead Associates
4975 Lacross Road Suite 314
North Charleston, SC 29406-6531

Prepared By:



134 Suber Road
Columbia SC 29210

April 12, 2011



April 12, 2011

STV / Ralph Whitehead Associates
4975 Lacross Road Suite 314
North Charleston, SC 29406-6531

Attention: Mr. Dan Moses, P.E.

Reference: **GEOTECHNICAL DATA SUMMARY REPORT**
SC-12-77 Over Fishing Creek
Lancaster County, South Carolina
S&ME Project No. 1611-10-292

Dear Mr. Moses:

We have completed our Geotechnical Exploration for the replacement bridge over Cane Creek in Lancaster County, South Carolina. Our exploration was performed in general accordance with our Master Services Subconsultant Agreement dated May 9, 2007.

As requested, S&ME, Inc. personnel were present at the above referenced site on February 23, 2011 to conduct soil test borings. Borings were generally conducted at the proposed bridge locations provided to the SCDOT prior to the field exploration. Approximate boring and sounding locations are shown in Figure 2 – *Test Location Plan*. A summary of borings and soundings is presented in Table 1.

Table 1 – Test Borings and Soundings

BORING ID	DEPTH	STATION	OFFSET	TYPE	NOTE
B-1	44.1'	221+88	13'L	SPT	NORTH END BENT
B-2	51.8'	225+88	13'L	SPT	SOUTH END BENT
SW-1	n/a	n/a	n/a	MASW	SOUTH END BENT
SW-2	n/a	n/a	n/a	MASW	NORTH END BENT

Stationing and offsets are described on the individual attached boring logs. The borings were conducted to the SCDOT requested depths. Groundwater levels were not measured for the soil borings due to the rotary wash drilling method and the need for immediate backfilling of roadway borings on account of safety concerns.

SPT hammer energy measurements were previously obtained with a Pile Driving Analyzer (PDA) on the CME 550 drill rig used to perform the borings on this project. The N-values indicated on the logs are field values and have not been corrected for hammer efficiency which is noted on the logs.

Shear wave velocities were measured near the proposed bridge location around as shown on the Test Location Plan using Multi-Channel Analysis of Surface Waves (MASW) and Microtremor Array Method (MAM) with non-linear array geometry, combining the dispersion curves from both tests prior to the inversion process.

The logs of our soil test borings are attached. Test locations were initially located by S&ME personnel measuring from existing site features as noted on the drawing provided. Offsets to the existing alignment centerline were utilized as noted on the log. The borings were backfilled by S&ME, Inc. with sand and cuttings.

Soils were classified in general accordance with ASTM D 2488. These logs represent our interpretation of the subsurface conditions based on the test data. Stratification lines on the boring logs represent approximate boundaries between soil types; however, the actual transition may be gradual and the thicknesses of the strata will vary across the site. The soil samples will be retained at our laboratory until SCDOT requests them, until completion of the new bridge, or 365 days after drilling, whichever is least.


Environmental assessment of soils, water, wetlands, and endangered species was not included in our scope of services for this project. The boring log information is intended for SCDOT's engineering interpretation of the data collected.

This data report has been prepared in accordance with generally applicable standards of our practice in this geographic area at the time this report was prepared. No other warranty, express or implied, is made. The Geotechnical Engineer of Record for the project must review the data submitted in this report and develop their own interpretation of the testing results as they apply to design.


S&ME, Inc. appreciates this opportunity to work with STV/Ralph Whitehead Associates as your local geotechnical consultant on this project. If you have any questions or need any further information in regard to this letter, please do not hesitate to contact us at 803-561-9024.

Sincerely,

S&ME, Inc.



Matt Longshore, EIT
Staff Professional



Michael (Trapp) Harris, PE
Geotechnical Department Manager

ML/TH

APPENDIX

Site Vicinity Map (Figure 1)

Test Location Plan (Figure 2)

Soil Test Boring Logs

Generalized Subsurface Profile (Figure 3)

MASW Shear Wave Velocity Profile

Field Testing Procedures



SCALE:	NTS
DRAWN BY:	ML
CHECKED BY:	TH
DATE:	3/22/2011




SITE VICINITY MAP
 S-12-77 OVER FISHING CREEK
 CHESTER COUNTY, SOUTH CAROLINA

JOB NO: 1611-10-292

FIGURE NO.

1



SCALE:	AS SHOWN
DRAWN BY:	ML
CHECKED BY:	TH
DATE:	3/22/2011




TEST LOCATION PLAN S-12-77 OVER FISHING CREEK CHESTER COUNTY, SOUTH CAROLINA	
JOB NO:	1611-10-292

FIGURE NO.
2

SCDOT Soil Test Boring Log

File No.:		Project No. (PIN):		County:	Chester	Eng./Geo.:	K. Plummer
Site Description:	Hightower Road over Fishing Creek (S&ME Job No.: 1611-10-292)				Route:		
Boring No.:	B-1	Boring Location:	221+88	Offset:	13'L	Alignment:	Existing
Elev.:	0.0 ft	Latitude:	0	Longitude:	0	Date Started:	2/23/2011
Total Depth:	44.1 ft	Soil Depth:	44.1 ft	Core Depth:	N/A ft	Date Completed:	2/23/2011
Bore Hole Diameter (in):	6"	Sampler Configuration		Liner Required:	Y (N)	Liner Used:	Y (N)
Drill Machine:	CME 550X	Drill Method:	Mud Rotary	Hammer Type:	Automatic	Energy Ratio:	
Core Size:	N/A	Driller:	S&ME	Groundwater:	TOB	N/E	24HR N/E




LEGEND

SAMPLER TYPE		DRILLING METHOD	
SS - Split Spoon	NQ - Rock Core, 1-7/8"	HSA - Hollow Stem Auger	RW - Rotary Wash
ST - Shelby Tube	CU - Cuttings	CFA - Continuous Flight Augers	RC - Rock Core
AWG - Rock Core, 1-1/8"	CT - Continuous Tube	DC - Driving Casing	

SC_DOT 1611-10-292.GPJ SC_DOT.GDT 4/13/11

SCDOT Soil Test Boring Log

File No.:		Project No. (PIN):		County:	Chester	Eng./Geo.:	K. Plummer
Site Description:	Hightower Road over Fishing Creek (S&ME Job No.: 1611-10-292)				Route:		
Boring No.:	B-2	Boring Location:	225+88	Offset:	13'L	Alignment:	Existing
Elev.:	0.0 ft	Latitude:	0	Longitude:	10	Date Started:	2/23/2011
Total Depth:	51.8 ft	Soil Depth:	51.8 ft	Core Depth:	N/A ft	Date Completed:	2/23/2011
Bore Hole Diameter (in):	6"	Sampler Configuration		Liner Required:	Y (N)	Liner Used:	Y (N)
Drill Machine:	CME 550X	Drill Method:	Mud Rotary	Hammer Type:	Automatic	Energy Ratio:	
Core Size:	N/A	Driller:	S&ME	Groundwater:	TOB	N/E	24HR N/E



LEGEND


SAMPLER TYPE		DRILLING METHOD	
SS - Split Spoon	NQ - Rock Core, 1-7/8"	HSA - Hollow Stem Auger	RW - Rotary Wash
ST - Shelby Tube	CU - Cuttings	CFA - Continuous Flight Augers	RC - Rock Core
AWG - Rock Core, 1-1/8"	CT - Continuous Tube	DC - Driving Casing	

SC_DOT 1611-10-292.GPJ SC_DOT.GDT 4/13/11

B-1

Sta. 221+88


N



B-2


Sta. 225+88

N




NOTES:

1. N = STANDARD PENETRATION TEST RESISTANCE VALUE (BLOWS PER FOOT)
2. THE DEPICTED STRATIGRAPHY IS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY
3. THE ACTUAL SUBSURFACE CONDITIONS WILL VARY BETWEEN BORING LOCATIONS



FILL (Silty Sand, Elastic Silt, Clayey Sand)



ALLUVIUM (Silty Sand, Sandy Silt)



PARTIALLY WEATHERED ROCK



ENGINEERING • TESTING • ENVIRONMENTAL SERVICES

GENERALIZED SUBSURFACE PROFILE
SC-12-77 DIVER FISHING CREEK
CHESTER COUNTY, SOUTH CAROLINA

SCALE: 1" = 10' (V)
1" = 50' (H)

DRAWN BY: MBL

APPROVED BY: TH


PROJECT NO. 1611-10-292

DATE: 4/11/2011

FIGURE NO. 3




Shear Wave Velocity Profile SW-1
RBO Fishing Creek
Great Falls, South Carolina
1611-10-292





Shear Wave Velocity Profile SW-2
RBO Fishing Creek
Great Falls, South Carolina
1611-10-292



SUMMARY OF EXPLORATION PROCEDURES

Layout and Access to Boring Locations

Staking of Borings - S&ME laid out the borings by measuring distances from the ends of the bridges with a measuring wheel and by turning rough right angles from the existing alignment centerline. Boring locations were marked in the field with marking paint on the asphalt surface and roadway shoulders where needed. Boring locations indicated on the attached “Boring Location Plan” must be considered as approximate.

Boring and Sampling

Soil Test Boring with Rotary Wash - Soil sampling and penetration testing were performed in general accordance with ASTM D1586, “Standard Test Method for Penetration Test and Split Barrel Sampling of Soils. A rotary drilling process was used to advance the hole and a heavy drilling fluid was circulated in the bore holes to stabilize the sides and flush the cuttings. . At regular intervals, drilling tools were removed and soil samples were obtained with a standard 1.4 inch I. D., two-inch O. D., split barrel sampler. The sampler was first seated six inches to penetrate any loose cuttings, then driven an additional 12 inches with blows of a 140-pound hammer falling 30 inches. The number of hammer blows required to drive the sampler through the two final six inch increments was recorded as the penetration resistance (SPT N) value. The N-value, when properly interpreted by qualified professional staff, is an index of the soil strength and foundation support capability.

Borehole Closure – Following collection of relevant geotechnical data, boreholes were filled by slowly pouring auger cuttings into the open hole such that minimal “bridging” of the material occurred in the hole. Backfilling of the upper two feet of each hole was tamped as heavily as possible with a shovel handle or other hand held equipment.

Laboratory Testing

Examination of Recovered Soil Samples – Soil samples and field boring records were reviewed in the laboratory by the geotechnical engineer. Soils were classified in general accordance with the visual-manual method described in ASTM D 2488, “*Standard Practice for Description and Identification of Soils (Visual-Manual Method)*”. The geotechnical engineer also prepared the final boring records enclosed with this report.