



Geotechnical Subsurface Data Report (GSDR)
Route S-12-300 (2310) Bridge Replacement over Little Rocky
Branch (North)
Chester County, South Carolina
SCDOT Project ID P038061
S&ME Project No. 1361-20-048

PREPARED FOR:

**South Carolina Department of Transportation
955 Park Street
Columbia, South Carolina 29201**

PREPARED BY:

**S&ME, Inc.
134 Suber Road
Columbia, South Carolina 29210**

March 19, 2021



March 19, 2021

South Carolina Department of Transportation
955 Park Street
Columbia, South Carolina 29201

Attention: Mr. Trapp Harris, P.E.

Reference: **Closed and Load-Restricted Bridge Package 2021-1**
Geotechnical Subsurface Data Report (GSDR)
Route S-12-300 (2310) Bridge Replacement over Little Rocky Branch (North)
Chester County, South Carolina
SCDOT Project ID P038061
S&ME Project No. 1361-20-048

Dear Mr. Harris:

The purpose of this report is to convey geotechnical information to the South Carolina Department of Transportation (SCDOT) for use by a contractor and is typically used with traditional design-bid-build projects. Our services were performed in general accordance with the *Scope of Services* provided in the *On-Call Consultant Work Order Request* by SCDOT, dated September 23, 2020, and the SCDOT *Geotechnical Design Manual* (GDM), Version 2.0, dated January 2019.

S&ME appreciates this opportunity to work with you as your geotechnical engineering consultant on this project. Please contact us at (803) 561-9024 if you have any questions or need any additional information regarding this report.

Sincerely,

S&ME, Inc.

John P. Lewis, P.E.
Project Engineer

Robert C. Bruorton, P.E.
Senior Engineer



Matthew F. Cooke, P.G., P.E.
Project Manager





Table of Contents

1.0	Project Description	1
2.0	Objective	1
3.0	Scope of Work.....	1
4.0	Test Locations	2
5.0	Exploration Procedures	2
5.1	Encroachment	2
5.2	Traffic Control.....	2
5.3	Standard Penetration Test (SPT) Borings	2
5.3.1	Ground Water	3
5.4	SPT Energy Measurements	3
5.5	Wireline Rock Coring.....	4
6.0	Classification of Recovered Soil Samples.....	4
7.0	Classification of Recovered Rock Samples.....	4
8.0	Laboratory Physical Tests.....	5
9.0	Closing	5

List of Tables

Table 1-1 – Bridge Location Summary	1
Table 5-1 – Boring Summary	2
Table 5-2 – Ground Water Measurement Summary	3
Table 5-3 – S&ME Drilling Equipment Summary	3

Appendices

- Appendix I – Figures
- Appendix II – Tables
- Appendix III – Soil Test Boring Records



Appendix IV – Laboratory Test Results – Split-Spoon Samples

Appendix V – Laboratory Test Data Sheets – Corrosion Series Testing

Appendix VI – Laboratory Test Data Sheets – Rock Cores

Appendix VII – SPT Hammer Energy Measurements



1.0 Project Description

The proposed construction for this project includes replacement of the existing Rambo Road (S-12-300) bridge over Little Rocky Branch (North) located in Chester County, South Carolina, as shown in the *Site Location Plan*, attached as Figure 1 in Appendix I.

Table 1-1 – Bridge Location Summary

Project ID	Route	Route Name	Crossing	County	Latitude	Longitude
P038061	S-12-300 (2310)	Rambo Road	Little Rocky Branch (North)	Chester	34.58469	-81.15843

From our review of provided information, the existing bridge was built in 1956 and is 56 feet in length with two travel lanes. The proposed replacement bridge will be 70 feet in length. Additional information regarding the proposed replacement bridge has not been provided at this time.

2.0 Objective

The objective of this project was to explore the subsurface conditions along the proposed alignment as they pertain to the proposed improvements, and in conjunction with field and laboratory testing, to provide geotechnical data to be utilized for project design.

3.0 Scope of Work

As requested, representatives of S&ME were present for on-site field activities between October 15 and 16, 2020, to conduct the following testing:

- Two (2) Standard Penetration Test (SPT) borings (B-1 and B-2), with one boring near each proposed abutment location.

Testing was conducted at or near the requested locations provided in the *Scope of Services*, provided by SCDOT, dated September 10, 2020. Testing locations were modified as necessary due to utilities, terrain, to minimize traffic control impacts, and to facilitate safe working conditions.

Additionally, laboratory testing was performed on disturbed split-spoon and rock core samples collected in the field. The laboratory testing program is described in more detail in the following sections.



4.0 Test Locations

Testing locations for the proposed new bridge abutments were determined by subtracting the existing bridge length from the proposed new bridge length, dividing that distance by two, and measuring that divided distance from the existing abutments. As-built survey of the testing locations was performed by Glenn Associates Surveying, Inc. The approximate testing locations are shown on the *Boring Location Plan*, included as Figure 2 in Appendix I. A summary of testing locations, including coordinates, elevation and alignment are presented in Table 1, *Test Location Summary*, in Appendix II. Surveyed coordinates are tabulated in decimal degree latitude and longitude as well as South Carolina State Plan northing and easting coordinates.

5.0 Exploration Procedures

The subsurface exploration for this project to date has included SPT borings. The following sections summarize the general outline of each test. The field testing data are organized into appendices of this report as follows:

- ◆ Appendix III – Soil Test Boring Records

5.1 Encroachment

S&ME contacted the Resident Maintenance Engineer for Chester County to coordinate the field testing and traffic control along the SCDOT rights-of-way in-lieu of applying for an encroachment permit.

5.2 Traffic Control

Traffic control for the project was provided by Area Wide Protective (AWP) under subcontract to S&ME. Traffic control was performed in accordance with SCDOT requirements for *Flagging Operations Two-Lane Two-Way Roadways without Intersections* – SCDOT Standard Drawing 610-005-10.

5.3 Standard Penetration Test (SPT) Borings

Two (2) soil test borings with SPT sampling were performed between the dates of October 15 and 16, 2020 using an ATV-mounted CME 550X drill rig. Soil test borings with SPT sampling were performed using mud rotary drilling techniques. The borings were performed to drill bit refusal, followed by wireline rock coring to termination depths. A summary of the SPT borings performed is provided in the table below:

Table 5-1 – Boring Summary

Route	Bridge ID	Boring No.	Refusal Depth (ft)	Total Boring Depth (ft)	Pavement	Purpose
S-12-300 (2310)	1270030000100	B-1	53.5	63.5	Asphalt	Proposed Southwest Abutment
		B-2	31.6	50.5	Asphalt	Proposed Northeast Abutment



Soil sampling and penetration testing were performed in general accordance with ASTM D1586 *Standard Test Method for Penetration Test and Split Barrel Sampling of Soils*. SPT was performed in each boring continuously in the upper 10 feet, followed by approximate 5-foot centers, thereafter. The split-barrel sampler was opened at the drill site and sloughed material was identified and separated from the recovered sample. The recovered sample was visually described and classified by S&ME's rig engineer. A selected portion of the sample was placed in a glass jar with a moisture-proof lid. Where materials changed over the sample drive length, a sample of each material was retained. The sample jars were labeled, placed in cardboard boxes, and transported to the S&ME Columbia Office at the end of each workday.

5.3.1 Ground Water

Water level measurements were attempted immediately after completion of drilling and, where feasible, were repeated after a period of roughly 24 hours. We note that due to the use of drilling fluid additives in mud rotary borings, the water level readings recorded in the soil borings may not accurately reflect the ground water conditions at the site. Ground water readings were conducted in general accordance with ASTM D4750 *Standard Test Method for Determining Subsurface Liquid Levels in a Borehole or Monitoring Well (Observation Well)*. A summary of the measured ground water depths and rough elevations are provided in the table below:

Table 5-2 – Ground Water Measurement Summary

Boring No.	Existing Grade (ft.)	GW Depth at TOB (ft.)	GW Elevation at TOB (ft.)	24-hr GW Depth (ft.)	24-hr GW Elevation (ft.)
B-1	483.5	5.9	477.6	7.9	475.6
B-2	482.8	7.5	475.3	8.0	474.8

After ground water measurements were complete, the borings were backfilled with bentonite chips, auger cuttings, or clean fill to within 20 feet of the existing ground surface then abandoned with Portland cement/bentonite grout. The surface pavements at each boring location were patched with commercially available bagged asphalt cold patch materials.

5.4 SPT Energy Measurements

SPT hammer energy measurements with a Pile Driving Analyzer (PDA) were performed by S&ME at an off-site location for the drill rig used on the project in general accordance with ASTM D4633 *Standard Test Method for Energy Measurement for Dynamic Penetrometers*. The SPT energy test results are summarized below and provided in Appendix VII. The N-values indicated on the soil test boring records are field values and were not corrected for overburden stress, rod length, borehole diameter or hammer efficiency.

Table 5-3 – S&ME Drilling Equipment Summary

Rig Make/Model	Serial No.	Carrier Type	Average SPT Energy Transfer Ratio (ETR), %
CME 550X	290593	ATV	81.1



5.5 Wireline Rock Coring

Upon encountering refusal at the boring locations, wireline rock coring was performed to termination depths of 50.5 to 63.5 feet below the existing ground surface to explore the refusal materials in general accordance with ASTM D2113 *Standard Practice for Rock Core Drilling and Sampling of Rock for Site Exploration*. Rock coring was performed using an NQ-size core barrel and wireline retrieval system. The recovered rock cores were visually logged by the S&ME rig geologist or engineer. The rock core samples were placed in cardboard core boxes and the boxes were labeled. Photographs were taken of each completed core box prior to any core being removed for laboratory testing. Completed core boxes were transported to the S&ME Columbia Office at the end of each workday. The rock cores were preserved, handled, and transported in general accordance with ASTM D5079.

6.0 Classification of Recovered Soil Samples

Recovered split-spoon samples were initially classified in general accordance with ASTM D2488 *Standard Practice for Description and Identification of Soils (Visual-Manual Method)*. After laboratory testing was completed, provisional field classifications were revised as necessary to provide a soil description that generally follows the terminology given by ASTM D2487 *Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)* and AASHTO M145 *Recommended Practice for Classification of Soils and Soil-Aggregate Mixtures for Highway Construction Purposes*.

Interpreted subsurface conditions encountered by the SPT borings are shown on the boring records in Appendix III. These records represent our interpretation of the subsurface conditions based on the test data. Stratification lines on the boring records represent approximate boundaries between soil types; however, the actual transition may be gradual, and the thicknesses of the strata will vary across the site. The soil samples will be retained at our laboratory for a period of seven years, or until completion of substructure installation, whichever is earlier.

7.0 Classification of Recovered Rock Samples

Recovered rock core samples were reviewed and classified in general accordance with the SCDOT GDM Chapter 6, Section 6.3. Upon return to our laboratory, the rock core samples were reviewed by a Professional Geologist (PG). Recovered cores examined in the laboratory were assigned descriptive terms using Tables 6-15 through 6-22 of the GDM where applicable to the rock type. Rock lithologic descriptions, and applicable descriptive information are included on the Soil Test Boring Records in Appendix III. Discontinuities in the recovered cores were evaluated using the terminology in GDM Tables 6-23 through 6-29. The results of the discontinuity examination are tabulated in the *Rock Core Discontinuity Worksheets* for each cored borehole, included in Appendix III. After logging, selected sections of rock core were removed and prepared for laboratory compressive strength testing.

After laboratory testing was completed, the Rock Mass Rating (RMR) and Geological Strength Index (GSI) were computed in general accordance with Sections 6.3.12 and 6.3.11, respectively, of the GDM. A summary of the rock core is provided in Table 4 *Rock Core – Laboratory Testing Summary*, in Appendix II.



Interpreted subsurface conditions encountered during rock coring activities are shown on the records in Appendix III. These records represent our interpretation of the subsurface conditions based on the test data. Stratification lines on the boring records represent approximate boundaries between rock types; however, the actual transition may be gradual, and the thicknesses of the strata will vary across the site. The rock samples will be retained at our laboratory for a period of seven years, or until completion of substructure installation, whichever is earlier.

8.0 Laboratory Physical Tests

Laboratory testing consisting of index property testing, and corrosion series testing was performed on selected split-spoon samples, while unconfined compressive strength testing was performed on selected rock core samples. The testing was performed in general accordance with ASTM, AASHTO, or SC state test procedures as follows:

- Atterberg limits – ASTM D4318 / AASHTO T89/90
- Particle-size distribution – ASTM D422 / ASTM D6913 / AASHTO T88
- Percent-finer 200 sieve – ASTM D1140 / AASHTO T11
- Natural moisture content – ASTM D2216 / AASHTO T265
- Corrosion Series:
 - pH – ASTM G51 / AASHTO T289
 - Chloride – AASHTO T291
 - Sulfate – ASTM C1580 / AASHTO T290
 - Resistivity – AASHTO T288
- Unconfined Compression – ASTM D7012

Tables summarizing the laboratory test results are provided in Appendix II as follows:

- Table 2: Split Spoon Samples – Laboratory Classification Testing Summary
- Table 3: Split Spoon Samples – Corrosion Series Testing Summary
- Table 4: Rock Core Laboratory Testing Summary

The individual laboratory test data sheets are organized into appendices of this report as summarized below:

- Appendix IV: Laboratory Test Results – Split Spoon Samples
- Appendix V: Laboratory Test Data Sheets – Corrosion Series
- Appendix VI: Laboratory Test Data Sheets – Rock Cores

9.0 Closing

This data report has been prepared in general accordance with procedures in SCDOT GDM Chapter 21 and with generally applicable standards of our practice in this geographic area at the time this report was prepared. No other warranty, express or implied, is made. The Geotechnical Engineer of Record for the project must review the data submitted in this report and develop their own interpretation of the testing results as they apply to design.




We relied on project information given to us to develop our exploration program. If project information described in this report is not accurate, or if it changes during project development, we should be notified of the changes.

This report presents data from a limited field exploration program. Subsurface conditions will vary widely between explored areas. Some variations may not become evident until further exploration or construction. If conditions are encountered which appear different than those described in our report, we should be notified. This report should not be construed to represent subsurface conditions for the entire site.

Unless specifically noted otherwise, our field exploration program did not include an assessment of regulatory compliance, environmental conditions or pollutants or presence of any biological materials (mold, fungi, bacteria). If there is a concern about these items, other studies should be performed.

Appendices

Appendix I – Figures



SOURCE: Google Maps



SITE LOCATION PLAN: S-12-300 (2310)

JOB NAME: S-12-300 Bridge over Little Rocky Branch (2310)		FIGURE NO. 1
LOCATION: S-12-300 (Rambo Road)		
CITY, STATE: Blackstock, South Carolina		
JOB NO.: 1361-20-048		
SCALE: NTS	CHECKED BY: MFC	
DATE: 3/18/2021	DRAWN BY: AKS	



Legend:

SOURCE: Google Earth



Approximate Boring Location



BORING LOCATION PLAN: S-12-300 (2310)

JOB NAME: S-12-300 Bridge over Little Rocky Branch (2310)
LOCATION: S-12-300 (Rambo Road)
CITY, STATE: Blackstock, South Carolina
JOB NO.: 1361-20-048

FIGURE NO.

2

SCALE: NTS

CHECKED BY: MFC

DATE: 3/18/2021

DRAWN BY: AKS

Appendix II – Tables



Table 1: Test Location Summary

Bridge ID	Boring No.	Test/SampleType(s)						SC State Plane Northing (ft.)	SC State Plane Easting (ft.)	Latitude (degrees)	Longitude (degrees)	Elevation (ft-msl)	Alignment
		SPT	CPT	DMT	Seismic	Bulk	UD						
S-12-300 (2310)	B-1	X						1001425.6	1952731.7	34.58558	-81.15705	483.5	Existing
S-12-300 (2310)	B-2	X						1001471.4	1952789.5	34.58571	-81.15685	482.8	Existing



Table 2: Split Spoon Samples – Laboratory Classification Testing Summary

Route ID	Boring Number	Sample Number	Sample Depth (ft)	Natural Moisture (%)	Atterberg Limits			Percent Finer #10 (%)	Percent Finer #40 (%)	Percent Finer #200 (%)	Organic Content (%)	Soil Classification		
					LL	PL	PI					AASHTO	USCS	Strata
S-12-300(2310)	B-1	SS-1	0.0-2.0	11.4	15	11	4	85	54	32.0	-	A-2-4	SC-SM	FILL
	B-1	SS-2	2.0-4.0	21.6	35	23	12	-	-	37.9	-	-	SC	FILL
	B-1	SS-4	6.0-8.0	19.0	23	18	5	96	72	25.0	-	A-2-4	SC-SM	FILL
	B-1	SS-6	13.5-15.0	-	-	-	-	-	-	22.7	-	-	SM	ALLUVIUM
	B-2	SS-1	0.0-2.0	13.6	32	18	14	96	80	50.0	-	A-6	CL	FILL
	B-2	SS-3	4.0-6.0	16.6	21	18	13	-	-	53.3	-	-	CL	FILL
	B-2	SS-6	13.5-15.0	-	-	-	-	-	-	23.4	-	-	SM	ALLUVIUM

NT = Not Tested

NP = Non-plastic

Classification estimated based on test results and ASTM D2488 Visual Manual Procedure



Closed and Load-Restricted Bridge Package 2021-1
Route S-12-300 (2310) BRO Little Rocky Branch (North)

Chester County, SC
SCDOT Project ID P038061
Project No. 1361-20-048

Table 3: Split Spoon Samples - Corrosion Series Testing Summary

Route & Boring Number	Sample Depth (ft)	Sample Number	As-Rec'd Resistivity (Ohm-cm)	Minimum Resistivity (Ohm-cm)	Sulfates		Chlorides		pH
					(mg/kg)	(wt%)	(mg/kg)	(wt%)	
S-12-300 B-2 (2310)	6.0 - 10.0	SS-4	3,283	2,479	19.3	0.0019	103.7	0.0104	6.5
		SS-5							



Table 4: Rock Core - Laboratory Testing Summary

Route & Boring Number	Core Run No.	Core Run Top Depth	Core Run Bottom Depth	Recovery (%)	RQD	Sample Top Depth (ft)	Sample Bottom Depth (ft)	Unit Weight (pcf)	Unconfined Compressive Strength (psi)	RMR ⁽¹⁾	GSI ⁽²⁾ Range
S-12-300 North B-1	RC-1	53.5	55.5	85	0	-	-	-	-	-	40
	RC-2	55.5	60.5	90	28	59.95	60.05	183	9,880	26	50
	RC-3	60.5	63.5	77	0	-	-	-	-	-	40
S-12-300 North B-2	RC-1	31.6	35.5	70	0	-	-	-	-	-	40
	RC-2	35.5	40.5	54	0	-	-	-	-	-	40
	RC-3	40.5	45.5	54	0	-	-	-	-	-	40
	RC-4	45.5	50.5	60	12	-	-	-	-	-	40

Notes:

⁽¹⁾ RMR = Rock Mass Rating (Refer to SCDOT Geotechnical Design Manual, Chapter 6)

⁽²⁾ GSI = Geologic Strength Index (Refer to SCDOT Geotechnical Design Manual, Chapter 6)

Appendix III – Soil Test Boring Records

LEGEND TO SOIL CLASSIFICATION AND SYMBOLS

SOIL TYPES

(Shown in Graphic Log)



Fill



Asphalt



Concrete



Topsoil



Gravel



Sand



Silt



Clay



Organic



Silty Sand



Clayey Sand



Sandy Silt



Clayey Silt



Sandy Clay



Silty Clay



Partially Weathered Rock



Cored Rock

WATER LEVELS

(Shown in Water Level Column)

▽ = Water Level At Termination of Boring

▼ = Water Level Taken After 24 Hours

◀ = Loss of Drilling Water

HC = Hole Cave

CONSISTENCY OF COHESIVE SOILS

CONSISTENCY

Very Soft
Soft
Firm
Stiff
Very Stiff
Hard
Very Hard

STD. PENETRATION RESISTANCE BLOWS/FOOT

0 to 2
3 to 4
5 to 8
9 to 15
16 to 30
31 to 50
Over 50

RELATIVE DENSITY OF COHESIONLESS SOILS

RELATIVE DENSITY

Very Loose
Loose
Medium Dense
Dense
Very Dense

STD. PENETRATION RESISTANCE BLOWS/FOOT

0 to 4
5 to 10
11 to 30
31 to 50
Over 50

TERMS

Standard Penetration Resistance - The Number of Blows of 140 lb. Hammer Falling 30 in. Required to Drive 1.4 in. I.D. Split Spoon Sampler 1 Foot. As Specified in ASTM D-1586.

REC - Total Length of Rock Recovered in the Core Barrel Divided by the Total Length of the Core Run Times 100%.

RQD - Total Length of Sound Rock Segments Recovered that are Longer Than or Equal to 4" (mechanical breaks excluded) Divided by the Total Length of the Core Run Times 100%.



Soil Test Log Descriptors

k

Rock Type

Indicate type of rock encountered (i.e. granite, limestone, shale, slate, etc.)

l

Color

Describe the sample color while sample is still moist, using Munsell color chart.

m

Texture

Describe the nonfracture structural features. Stratification is the layering of sedimentary rock and foliation is the layering of metaphoric rock

Descriptive Term	Criteria
Very Thickly Bedded	> 1.0 m
Thickly Bedded	0.5 to 1.0 m
Thinly Bedded	50 to 500 mm
Very Thinly Bedded	10 to 50 mm
Laminated	2.5 to 10 mm
Thinly Laminated	< 2.5 mm

n

Grain Size and Shape

Describe the size and shape of all visible grains, typically used on sedimentary rock.

<u>Size</u>		<u>Sieve size</u>
<u>Descriptor</u>	<u>mm</u>	
Very coarse grained	> 4.75	Grain sizes greater than popcorn kernels
Coarse grained	2.00 – 4.75	Individual grains easy to distinguish by eye
Medium grained	0.425 – 2.00	Individual grains distinguished by eye
Fine grained	0.075 – 0.425	Individual grains distinguished with difficulty
Very Fine grained	< 0.075	Individual grains cannot be distinguished by unaided eye

<u>Shape</u>	
<u>Descriptive Term</u>	<u>Criteria</u>
Angular	Shows little wear; edges and corners are sharp
Subangular	Shows definite effects of wear; edges and corners are slightly rounded off
Subrounded	Shows considerable wear; edges and corners are rounded to smooth curves
Rounded	Shows extreme wear; edges and corners are smoother to broad curves
Well-rounded	Completely worn; edges and corners are not present

o

Weathering / Alteration

Weathering is the physical disintegration of the minerals by atmospheric processes. Alteration is disintegration of the minerals by geothermal processes.

<u>Description</u>	<u>Recognition</u>
Residual Soil	Original minerals of rock have been entirely decomposed to secondary minerals, and original rock fabric is not apparent; material can be easily broken by hand
Completely Weathered / Altered	Original minerals of rock have been almost entirely decomposed to secondary minerals, although the original fabric may be intact; material can be granulated by hand
Highly Weathered / Altered	More than half of the rock is decomposed; rock is weakened so that a minimum 1-7/8 inch diameter sample can be easily broken readily by hand across rock fabric
Moderately Weathered / Altered	Rock is discolored and noticeably weakened, but less than half is decomposed; a minimum 1-7/8 inch diameter sample cannot be broken readily by hand across rock fabric
Slightly Weathered / Altered	Rock is slightly discolored, but not noticeably lower in strength than fresh rock
Fresh	Rock shows no discoloration, loss of strength, or other effect of weathering / alteration

Figure 6-16, SCDOT Soil Test Log Descriptors – Rock

6-38

January 2019

SCDOT Soil Test Log Descriptors

p

Rock Strength

Provide a qualitative assessment of the rock strength using either a geologic hammer or knife.

Description	Recognition	Approximately Uniaxial Compressive Strength (psi)
Extremely Weak Rock	Can be indented by thumbnail	35 – 150
Very Weak Rock	Can be peeled by pocket knife	150 – 700
Weak Rock	Can be peeled with difficulty by pocket knife	700 – 3,500
Medium Strong Rock	Can be indented 3/16 inch with sharp end of pick	3,500 – 7,200
Strong Rock	Requires one hammer blow to fracture	7,200 – 14,500
Very Strong Rock	Requires many hammer blows to fracture	14,500 – 35,000
Extremely Strong Rock	Can only be chipped with hammer blows	> 35,000

q

Strike and Dip

Dip of fracture surface measured relative to horizontal with bearing and direction (i.e. N30°down, etc.)

r

Discontinuity Type

F - Fault
J - Joint
Sh - Shear
Fo - Foliation
V - Vein
B - Bedding

s

Discontinuity Width (millimeters)

W - Wide (12.5 – 50)
MW - Moderately Wide (2.5 – 12.5)
N - Narrow (1.25 – 2.5)
VN - Very Narrow (< 1.25)
T - Tight (0)

t

Amount of Infilling

Su - Surface Stain
Sp - Spotty
Pa - Partially Filled
Fi - Filled
No - None

u

Type of Infilling

Cl - Clay
Ca - Calcite
Ch - Chloride
Fe - Iron Oxide
Gy - Gypsum/Talc
H - Healed
No - None
Py - Pyrite
Qz - Quartz
Sd - Sand

v

Surface Shape of Joint

Wa - Wavy
Pl - Planar
St - Stepped
Ir - Irregular

w

Discontinuity Spacing (feet)

EW - Extremely Wide (> 65)
W - Wide (22 – 65)
M - Moderate (7.5 – 22)
C - Close (2 – 7.5)
VC - Very Close (< 2)

x


Roughness of Surface

Slk - Slickensided (surface has smooth, glassy finish with visual evidence of striations)
S - Smooth (surface appears smooth and feels so to the touch)
SR - Slightly Rough (asperities on the discontinuity surfaces are distinguishable and can be felt)
R - Rough (some ridges and side-angle steps are evident; asperities are clearly visible, and discontinuity surface feels very abrasive)
VR - Very Rough (near-vertical steps and ridges occur on the discontinuity surface)

Figure 6-17, SCDOT Soil Test Log Descriptors – Rock (con't)

SCDOT Soil Test Log

Project ID:	P038061	County:	Chester	Boring No.:	B-1
Site Description:	S-12-300 (2310) BRO Little Rocky Branch (BRIDGE ID 1270030000100)			Route:	S-12-300 (N)
Eng./Geo.:	BK	Boring Location:	7' S of SEB	Offset:	6' E of CL
Elev.:	483.5 ft	Latitude:	34.58558268	Longitude:	-81.157046235
Date Started:	10/15/2020				
Total Depth:	63.5 ft	Soil Depth:	53.5 ft	Core Depth:	10 ft
Date Completed:	10/15/2020				
Bore Hole Diameter (in):	3 7/8	Sampler Configuration	Liner Required: Y (N)		Liner Used: Y (N)
Drill Machine:	CME 550X	Drill Method:	RW / DC / RC	Hammer Type:	Automatic
Energy Ratio:	81.1%				
Core Size:	NQ	Driller:	J. Little	Groundwater:	TOB 5.9 ft
24HR:	7.9 ft				




LEGEND

Continued Next Page

SAMPLER TYPE		DRILLING METHOD	
SS - Split Spoon	NQ - Rock Core, 1-7/8"	HSA - Hollow Stem Auger	RW - Rotary Wash
UD - Undisturbed Sample	CU - Cuttings	CFA - Continuous Flight Augers	RC - Rock Core
AWG - Rock Core, 1-1/8"	CT - Continuous Tube	DC - Driving Casing	

SCDOT Soil Test Log

Project ID:	P038061	County:	Chester	Boring No.:	B-1
Site Description:	S-12-300 (2310) BRO Little Rocky Branch (BRIDGE ID 1270030000100)			Route:	S-12-300 (N)
Eng./Geo.:	BK	Boring Location:	7' S of SEB	Offset:	6' E of CL
Elev.:	483.5 ft	Latitude:	34.58558268	Longitude:	-81.157046235
Date Started:	10/15/2020				
Total Depth:	63.5 ft	Soil Depth:	53.5 ft	Core Depth:	10 ft
Date Completed:	10/15/2020				
Bore Hole Diameter (in):	3 7/8	Sampler Configuration		Liner Required:	Y (N)
Liner Used:	Y (N)				
Drill Machine:	CME 550X	Drill Method:	RW / DC / RC	Hammer Type:	Automatic
Energy Ratio:	81.1%				
Core Size:	NQ	Driller:	J. Little	Groundwater:	TOB 5.9 ft
24HR:	7.9 ft				



LEGEND

SAMPLER TYPE		DRILLING METHOD	
SS - Split Spoon	NQ - Rock Core, 1-7/8"	HSA - Hollow Stem Auger	RW - Rotary Wash
UD - Undisturbed Sample	CU - Cuttings	CFA - Continuous Flight Augers	RC - Rock Core
AWG - Rock Core, 1-1/8"	CT - Continuous Tube	DC - Driving Casing	

SC.DOT 1361-20-048 S-12-300 (2310) BORING LOGS.GPJ SCDOT_DATATEMPLATE.GDT 3/16/21



Rock Core Discontinuity Worksheet


Project Name: S-12-300 (2310)
 Project Number: 1361-20-048
 Driller (Company/Name): S&ME/Jay Little
 Logged By: BRK
 Date: 10/15/2020

Boring Number: B-1
 Core Barrel Type: NQ2
 Core Barrel Length: 5.0'
 Coring Technique: wireline
 Number of Core Boxes: 1

Depth (ft)	Disc. No.	Disc. Type	Dip Angle (deg)	Disc. Width (mm)	Infill Amount	Infill Type	Surface Shape	Surface Roughness	Notes
53.9	1	J	20	MW	Su	Sd	Pl	SR to R	
54.1	2	J	20	MW	Su	Sd	Pl	SR	
54.4	3	J	15	MW	Su	Sd	Pl	SR	
55.5	4	J	N/A	MW	Su to Pa	Sd/Cl	Pl	SR	highly fractured 54.4' to 55.5'
55.9	5	J	60	MW	Su	Sd	St	SR	
56.3	6	J	10	MW	Su	Sd	Pl	SR	
57.2	7	J	N/A	MW	Su to Pa	Sd/Cl	Pl	SR	highly fractured 56.3' to 57.2'
57.3	8	J	9	MW	Su	Sd/Cl	Pl	SR	
57.5	9	J	6	VN	Su	Sd/Cl	Pl	SR	
58	10	J	N/A	MW	Su to Pa	Sd/Cl	Pl	SR	highly fractured 57.5' to 58.0'
58.4	11	J	5	N	No	N/A	Pl	SR	
58.7	12	J	4	N	No	N/A	Pl	SR	
59.1	13	J	5	N	No	N/A	Pl	SR	
59.4	14	J	5	N	No	N/A	Pl	SR	
59.5	15	J	25	MW	No	N/A	Pl	SR	
60.2	16	J	45	VN	No	N/A	St	SR	
60.8	17	J	15	N	No	N/A	Pl	SR	
61.3	18	J	N/A	N to MW	No	N/A	Pl	SR	
61.5	19	J	5	N	No	N/A	Ir	SR	
61.8	20	J	25	MW	Su	Sd/Cl	Pl	SR	
63.5	21	J	N/A	MW to W	Su to Pa	Sd/Cl	Pl	SR	highly fractured 61.8' to 63.5'

SCDOT Soil Test Log

Project ID: P038061				County: Chester		Boring No.: B-2			
Site Description:		S-12-300 (2310) BRO Little Rocky Branch (BRIDGE ID 1270030000100)					Route: S-12-300 (N)		
Eng./Geo.: BK			Boring Location: 7' N of NEB			Offset: 6' E of CL		Alignment: Existing	
Elev.: 482.8 ft		Latitude: 34.585708689		Longitude: -81.156854422		Date Started:		10/16/2020	
Total Depth: 50.5 ft		Soil Depth: 31.6 ft		Core Depth: 18.9 ft		Date Completed:		10/16/2020	
Bore Hole Diameter (in): 3 7/8		Sampler Configuration			Liner Required: Y (N)		Liner Used: Y (N)		
Drill Machine: CME 550X		Drill Method: RW / DC / RC		Hammer Type: Automatic		Energy Ratio:		81.1%	
Core Size: NQ		Driller: J. Little		Groundwater: TOB 7.5 ft		24HR		8.0 ft	



LEGEND

Continued Next Page

SAMPLER TYPE		DRILLING METHOD	
SS - Split Spoon	NQ - Rock Core, 1-7/8"	HSA - Hollow Stem Auger	RW - Rotary Wash
UD - Undisturbed Sample	CU - Cuttings	CFA - Continuous Flight Augers	RC - Rock Core
AWG - Rock Core, 1-1/8"	CT - Continuous Tube	DC - Driving Casing	

SCDOT Soil Test Log

Project ID:	P038061	County:	Chester	Boring No.:	B-2
Site Description:	S-12-300 (2310) BRO Little Rocky Branch (BRIDGE ID 1270030000100)			Route:	S-12-300 (N)
Eng./Geo.:	BK	Boring Location:	7' N of NEB	Offset:	6' E of CL
Elev.:	482.8 ft	Latitude:	34.585708689	Longitude:	-81.156854422
Date Started:	10/16/2020				
Total Depth:	50.5 ft	Soil Depth:	31.6 ft	Core Depth:	18.9 ft
Date Completed:	10/16/2020				
Bore Hole Diameter (in):	3 7/8	Sampler Configuration	Liner Required: Y (N)		Liner Used: Y (N)
Drill Machine:	CME 550X	Drill Method:	RW / DC / RC	Hammer Type:	Automatic
Energy Ratio:	81.1%				
Core Size:	NQ	Driller:	J. Little	Groundwater:	TOB 7.5 ft
24HR	8.0 ft				

Elevation (ft)	Depth (ft)	MATERIAL DESCRIPTION	Graphic Log	Sample Depth (ft)	Sample No./Type	1st 6"	2nd 6"	3rd 6"	4th 6"	N Value	● SPT N VALUE ● PL X — MC — LL X ▲ FINES CONTENT (%) + RQD (%) ■ REC (%)
		Strata break based on rotary speed.		40.5							
437.8		PARTIALLY WEATHERED ROCK (PWR) - very dense, dry, brown, Silty SAND (SM), 7.5YR 4/3, mostly fine to coarse sands, little low plasticity fines.			RC-3						
		Auger Refusal at 31.6 feet. Install NW Casing to 31.6 feet for NQ wireline coring.		45.5							
432.8	50.5	METAMORPHIC BEDROCK - FELSIC GNEISS - brown [7.5YR 4/3] and black [2.5/N] and white [8/N], coarse grained, thickly foliated, highly to completely weathered, weak to extremely weak rock, LH-F, J (0-60° dip, VC-C, N-MW-W, Pl-Ir, Su-Pa-Fi-No)			RC-4						
427.8		RC-1: RQD = 0%, REC = 70%, GSI = 40, 1.6 min/ft									
		RC-2: RQD = 0%, REC = 54%, GSI = 40, 1.0 min/ft									
		RC-3: RQD = 0%, REC = 54%, GSI = 40, 1.2 min/ft									
		RC-4: RQD = 12%, REC = 60%, GSI = 40, 1.0 min/ft									
422.8		Boring Terminated at 50.5 feet.									
417.8											
412.8											
407.8											

LEGEND

SAMPLER TYPE		DRILLING METHOD	
SS - Split Spoon	NQ - Rock Core, 1-7/8"	HSA - Hollow Stem Auger	RW - Rotary Wash
UD - Undisturbed Sample	CU - Cuttings	CFA - Continuous Flight Augers	RC - Rock Core
AWG - Rock Core, 1-1/8"	CT - Continuous Tube	DC - Driving Casing	

SC.DOT 1361-20-048 S-12-300 (2310) BORING LOGS.GPJ SCDOT_DATATEMPLATE.GDT 3/16/21



Rock Core Discontinuity Worksheet

Project Name: S-12-300 (2310)
Project Number: 1361-20-048
Driller (Company/Name): S&ME/Jay Little
Logged By: BRK
Date: 10/16/2020

Boring Number: B-2
Core Barrel Type: NQ2
Core Barrel Length: 5.0'
Coring Technique: wireline
Number of Core Boxes: 2

Depth (ft)	Disc. No.	Disc. Type	Dip Angle (deg)	Disc. Width (mm)	Infill Amount	Infill Type	Surface Shape	Surface Roughness	Notes
49.4	1	J	N/A	N-MW-W	No-Pa-Fa-Su	Sd-Cl	Pl-Ir	S-SR-R	highly fractured 31.6' - 49.4'
49.7	2	J	60	N	Su	Sd	Pl	SR	
50.2	3	J	10	MW	Su	Sd	St	SR	
50.5	4	J	N/A	MW-W	Su	Sd	Pl	SR-R	highly fractured 50.2'-50.5'



Rock Core Photo Log

Boring: B-1	Box: 1 of 1	Date: 10/15/2020	Driller: J. Little	Geologist: B. Kebea
Run: RC-1	Length: 2.0	Depth Int: 53.5-55.5	Recovery: 85%	RQD: 0%
Run: RC-2	Length: 5.0	Depth Int: 55.5-60.5	Recovery: 90%	RQD: 28%
Run: RC-3	Length: 3.0	Depth Int: 60.5-63.5	Recovery: 77%	RQD: 0%



Rock Core Photo Log

Boring: B-2	Box: 1 of 2	Date: 10/16/2020	Driller: J. Little	Geologist: B. Kebea
Run: RC-1	Length: 3.9	Depth Int: 31.6-35.5	Recovery: 70%	RQD: 0%
Run: RC-2	Length: 5.0	Depth Int: 35.5-40.5	Recovery: 54%	RQD: 0%
Run: RC-3	Length: 5.0	Depth Int: 40.5-45.5	Recovery: 54%	RQD: 0%
Run: RC-4	Length: 5.0	Depth Int: 45.5-50.5	Recovery: 60%	RQD: 12%



Boring: B-2	Box: 2 of 2	Date: 10/16/2020	Driller: J. Little	Geologist: B. Kebea
Run: RC-4	Length: 5.0	Depth Int: 45.5-50.5	Recovery: 60%	RQD: 12%





Drill Rig Photo Log

Bridge: S-12-300

Boring: B-1

Date: 10/15/2020

Driller: J. Little

Geologist: B. Kebea





Drill Rig Photo Log

Bridge: S-12-300

Boring: B-2

Date: 10/15/2020

Driller: J. Little

Geologist: B. Kebea



Appendix IV – Laboratory Test Results – Split-Spoon Samples



INDEX PROPERTIES VERSUS DEPTH


PROJECT ID P038061

PROJECT NAME S-12-300 (2310) BRO Little Rocky Branch (BRIDGE ID 1270030000)

PROJECT COUNTY Chester

SURFACE ELEVATION: 483.5

BORING B-1



LEGEND	
●	Water Content
⊠	Plastic Limit
▲	Liquid Limit
★	Fines



INDEX PROPERTIES VERSUS DEPTH


PROJECT ID P038061

PROJECT NAME S-12-300 (2310) BRO Little Rocky Branch (BRIDGE ID 1270030000)

PROJECT COUNTY Chester

SURFACE ELEVATION: 482.8

BORING B-2




LEGEND	
●	Water Content
⊠	Plastic Limit
▲	Liquid Limit
★	Fines

ATTERBERG LIMITS' RESULTS

PROJECT ID P038061

PROJECT NAME S-12-300 (2310) BRO Little Rocky Branch (BRIDGE ID 1270030000

PROJECT COUNTY Chester

[illegible]




GRAIN SIZE DISTRIBUTION

PROJECT ID P038061

PROJECT NAME S-12-300 (2310) BRO Little Rocky Branch (BRIDGE ID 1270030000)

PROJECT COUNTY Chester



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

BOREHOLE	DEPTH	Classification					LL	PL	PI	Cc	Cu
● B-2	4.0	SANDY LEAN CLAY (CL)					31	18	13		
☒ B-2	13.5	SILTY SAND (SM)									
BOREHOLE	DEPTH	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
● B-2	4.0	0.075						53.3			
☒ B-2	13.5	0.075						23.4			

GRAIN SIZE 1361-20-048 S-12-300 (2310) BORING LOGS.GPJ SCDOT DATA TEMPLATE_01_30_2015.GDT 2/8/21

Appendix V – Laboratory Test Data Sheets – Corrosion Series Testing



Results Only Soil Testing for SCDOT Bridge Package 2021-01 DB Prep

December 8, 2020

**Prepared for:
Matthew F. Cooke
S&ME, Inc.
134 Suber Road
Columbia, SC 29210
mcooke@smeinc.com**

**Project X Job#: S201125D
Client Job or PO#: 1361-20-48**

Respectfully Submitted,

Eduardo Hernandez, M.Sc., P.E.
Sr. Corrosion Consultant
NACE Corrosion Technologist #16592
Professional Engineer
California No. M37102
ehernandez@projectxcorrosion.com





Soil Analysis Lab Results

Client: S&ME, Inc.
Job Name: SCDOT Bridge Package 2021-01 DB Prep
Client Job Number: 1361-20-48
Project X Job Number: S201125D
December 8, 2020

	Method	AASHTO T290		AASHTO T291		AASHTO T288		AASHTO T289
Bore# / Description	Depth	Sulfates SO ₄ ²⁻		Chlorides Cl ⁻		Resistivity As Rec'd Minimum		pH
	(ft)	(mg/kg)	(wt%)	(mg/kg)	(wt%)	(Ohm-cm)	(Ohm-cm)	
SS-7 B-2; S-11-97 Bridge	18.5-20.0	34.8	0.0035	8.2	0.0008	31,490	26,800	6.7
SS-6/SS-7 B-2; S-11-119 Bridge	8.2-14.4	8.7	0.0009	21.4	0.0021	13,400	8,710	6.7
SS-5 B-2; S-11-265 Bridge	8.5-10.0	35.6	0.0036	109.9	0.0110	2,881	2,345	6.4
SS-4 B-1; S-12-58 Bridge	6.0-8.0	31.1	0.0031	23.9	0.0024	25,460	18,760	6.4
SS-4/SS-5 B-2; S-12-300 (2310) Bridge	6.0-10.0	19.3	0.0019	103.7	0.0104	3,283	2,479	6.5
SS-6 B-1; S-12-300 (2490) Bridge	13.5-15.0	36.1	0.0036	21.0	0.0021	9,380	8,040	6.7
SS-7/SS-8 B-2; S-20-214 Bridge	18.5-25.0	9.9	0.0010	7.4	0.0007	49,580	23,450	7.1
SS-6 B-1; S-29-97 Bridge	13.4-14.90	4.6	0.0005	1.9	0.0002	10,050	6,700	7.1
SS-4/SS-5 B-2; S-44-87 Bridge	7.0-11.0	45.9	0.0046	15.3	0.0015	16,080	15,410	6.2

Cations and Anions, except Sulfide and Bicarbonate, tested with Ion Chromatography
mg/kg = milligrams per kilogram (parts per million) of dry soil weight
ND = 0 = Not Detected | NT = Not Tested | Unk = Unknown
Chemical Analysis performed on 1:3 Soil-To-Water extract



Ship Samples To: 29990 Technology Dr, Suite 13, Murrieta, CA 92563


[illegible]

Appendix VI – Laboratory Test Data Sheets – Rock Cores



Client:	S&ME, Inc.
Project Name:	SCDOT Bridge Package 2021-1
Project Location:	South Carolina
GTX #:	313047
Test Date:	1/18/2021
Tested By:	cmh
Checked By:	jsc
Boring ID:	S-11-300(2310), B-1
Sample ID:	RS-1
Depth, ft:	59.65-60.05
Sample Type:	rock core
Sample Description:	See photographs Discontinuity failure

Compressive Strength and Elastic Moduli of Rock by ASTM D7012 - Method D



Peak Compressive Stress: 9,880 psi

Poisson's Ratio within the third stress range could not be determined.

Stress Range, psi	Young's Modulus, psi	Poisson's Ratio
1000-3600	7,440,000	0.21
3600-6300	6,130,000	0.14
6300-8900	3,590,000	---

Notes: Test specimen tested at the approximate as-received moisture content and at standard laboratory temperature.
The axial load was applied continuously at a stress rate that produced failure in a test time between 2 and 15 minutes.
Young's Modulus and Poisson's Ratio calculated using the tangent to the line in the stress range listed.
Calculations assume samples are isotropic, which is not necessarily the case.





Client:	S&ME, Inc.	Test Date:	1/14/2021
Project Name:	SCDOT Bridge Package 2021-1	Tested By:	cmh
Project Location:	South Carolina	Checked By:	smd
GTX #:	313047		
Boring ID:	S-11-300(2310), B1		
Sample ID:	RS-1		
Depth:	59.65-60.05 ft		
Visual Description:	See photographs		



UNIT WEIGHT DETERMINATION AND DIMENSIONAL AND SHAPE TOLERANCES OF ROCK CORE SPECIMENS BY ASTM D4543

BULK DENSITY				DEVIATION FROM STRAIGHTNESS (Procedure S1)	
	1	2	Average	Maximum gap between side of core and reference surface plate: Is the maximum gap \leq 0.02 in.? YES	
Specimen Length, in:	4.24	4.24	4.24	Maximum difference must be $<$ 0.020 in. Straightness Tolerance Met? YES	
Specimen Diameter, in:	1.99	1.99	1.99		
Specimen Mass, g:	635.5				
Bulk Density, lb/ft ³	183				
Length to Diameter Ratio:	2.1				
		Minimum Diameter Tolerance Met?	YES		
		Length to Diameter Ratio Tolerance Met?	YES		

END FLATNESS AND PARALLELISM (Procedure FP1)															
END 1	-0.875	-0.750	-0.625	-0.500	-0.375	-0.250	-0.125	0.000	0.125	0.250	0.375	0.500	0.625	0.750	0.875
Diameter 1, in	-0.00040	-0.00030	-0.00030	-0.00020	-0.00020	-0.00020	-0.00010	0.00000	0.00010	0.00010	0.00030	0.00030	0.00040	0.00050	0.00050
Diameter 2, in (rotated 90°)	0.00020	0.00020	0.00020	0.00020	0.00010	0.00010	0.00010	0.00000	-0.00010	-0.00010	-0.00010	-0.00020	-0.00030	-0.00030	-0.00030
Difference between max and min readings, in: 0° = 0.00090 90° = 0.00050															
END 2	-0.875	-0.750	-0.625	-0.500	-0.375	-0.250	-0.125	0.000	0.125	0.250	0.375	0.500	0.625	0.750	0.875
Diameter 1, in	-0.00060	-0.00050	-0.00040	-0.00030	-0.00030	-0.00020	-0.00010	0.00000	0.00010	0.00010	0.00020	0.00030	0.00030	0.00030	0.00030
Diameter 2, in (rotated 90°)	0.00020	0.00020	0.00010	0.00010	0.00010	0.00010	0.00010	0.00000	-0.00010	-0.00010	-0.00010	-0.00020	-0.00030	-0.00030	-0.00040
Difference between max and min readings, in: 0° = 0.0009 90° = 0.0006 Maximum difference must be < 0.0020 in. Difference = ± 0.00045															
Flatness Tolerance Met? YES															



DIAMETER 1	
End 1:	
Slope of Best Fit Line	0.00054
Angle of Best Fit Line:	0.03094
End 2:	
Slope of Best Fit Line	0.00055
Angle of Best Fit Line:	0.03159
Maximum Angular Difference:	0.00065
Parallelism Tolerance Met?	YES
Spherically Seated	



DIAMETER 2	
End 1:	
Slope of Best Fit Line	0.00034
Angle of Best Fit Line:	0.01932
End 2:	
Slope of Best Fit Line	0.00033
Angle of Best Fit Line:	0.01899
Maximum Angular Difference:	0.00033
Parallelism Tolerance Met?	YES
Spherically Seated	

PERPENDICULARITY (Procedure P1)						(Calculated from End Flatness and Parallelism measurements above)	
END 1		Difference, Maximum and Minimum (in.)	Diameter (in.)	Slope	Angle°	Perpendicularity Tolerance Met?	Maximum angle of departure must be \leq 0.25°
Diameter 1, in		0.00090	1.990	0.00045	0.026	YES	
Diameter 2, in (rotated 90°)		0.00050	1.990	0.00025	0.014	YES	
Perpendicularity Tolerance Met? YES							
END 2							
Diameter 1, in		0.00090	1.990	0.00045	0.026	YES	
Diameter 2, in (rotated 90°)		0.00060	1.990	0.00030	0.017	YES	

Client:	S&ME, Inc.
Project Name:	SCDOT Bridge Package 2021-1
Project Location:	South Carolina
GTX #:	313047
Test Date:	1/18/2021
Tested By:	cmh
Checked By:	smd
Boring ID:	S-11-300(2310), B1
Sample ID:	RS-1
Depth, ft:	59.65-60.05



After cutting and grinding



After break

Appendix VII – SPT Hammer Energy Measurements



Report of SPT Energy Measurements
S&ME CME-550X ATV (Serial No. 290593)
Rutherfordton, North Carolina
S&ME Project No. 1535-20-200

PREPARED FOR:

**North Carolina Department of Transportation
Geotechnical Engineering Unit
1589 Mail Service Center
Raleigh, North Carolina 27699**

PREPARED BY:

**S&ME, Inc.
9751 Southern Pine Boulevard
Charlotte, North Carolina 28273**

June 4, 2020



June 4, 2020

North Carolina Department of Transportation
Geotechnical Engineering Unit
1589 Mail Service Center
Raleigh, North Carolina 27699

Attention: Dr. Shunyi (Chris) Chen, Ph.D., P.E.

Cc: Ms. Cheryl A. Youngblood, L.G.
Ms. Christina M. Bruinsma, L.G.

Reference: **Report of SPT Energy Measurements**
S&ME CME-550X ATV (Serial No. 290593)
Rutherfordton, North Carolina
S&ME Project No. 1535-20-200
NC PE Firm License No. F-0176

Dear Dr. Chen:

We have completed the Standard Penetration Test (SPT) energy measurements on the automatic hammer used with our CME-550X ATV-mounted drill rig (Serial No. 290593). This service was performed by Mr. Joseph Williamson, P.E. of our firm on May 5, 2020, in general accordance with ASTM D4633 and the most recent revision of the North Carolina Department of Transportation (NCDOT) Geotechnical Engineering Unit's requirements. Review of the data quality and analyses was performed by Mr. Gregory Canivan, P.E. of our firm. Copies of the Certificates of Proficiency issued by Pile Dynamics based on the Dynamic Measurement and Analysis Proficiency Test for Mr. Williamson and Mr. Canivan are included in Appendix I. The testing procedures, equipment used during testing, and detailed results are presented in this report.

1.0 Dynamic Testing Methodology

Testing was performed using a model PAX (Serial No. 3733L) Pile Driving Analyzer™ (PDA) manufactured by Pile Dynamics, Inc. The PDA was used to record and interpret data from two piezoresistive accelerometers (Serial Nos. K5641 and K10181) bolted to a 2.0-foot long AWJ drill rod (Serial No. 203) internally instrumented with two strain transducers. Calibration sheets for the accelerometers and the instrumented rod are included in Appendix II. The instrumented AWJ drill rod has a cross-sectional area of 1.19 square inches and an outside diameter of approximately 1.75 inches. Therefore, we calculate the inside diameter to be approximately 1.25 inches at the gauge location. The accelerometers and strain gauges, which are diametrically opposed near the middle of the instrumented rod, monitor acceleration and strain for each hammer blow. The analyzer converts the data to velocities and forces and computes the maximum transferred hammer energies with the "EFV" method described in ASTM D4633. Preliminary results are recorded and displayed in real time for each blow.



2.0 Testing and Observations

S&ME personnel were on site May 5, 2020, to observe and perform high-strain dynamic testing during SPT sampling on the CME-550X ATV-mounted drill rig operated by Fred Johnson of S&ME. The measurements were taken during drilling and sampling of a soil test boring for an NCDOT project (R-2233BA boring L3_121) in Rutherfordton, North Carolina. SPT energy measurements were recorded during six sampling intervals at depths of approximately 28.5, 33.5, 38.5, 43.5, 48.5 and 53.5 ft below the ground surface. The 48.5 and 53.5 ft sample intervals did not meet the NCDOT blow count requirements and were not included in the data analysis. The information presented in the tables below summarizes the equipment and tooling used during the SPT energy measurements. The SPT Energy Evaluation Form and Boring L3_121 Soil Boring Log are included in Appendix III.

Table 2-1: Drill Rig Information

Manufacturer	CME
Model	550X
Serial Number	290593
Operator	F. Johnson
Carrier	ATV

Table 2-2: Hammer Information

Model / Type	CME / Auto
Serial Number	290593
Anvil Height (inches)	12
Anvil Diameter (inches)	2.5
Typical Drop Height (inches)	30
Typical Ram Weight (pounds)	140
Ram Serial Number	N/A

Table 2-3: Drilling and Instrumented Rod Information

Drill Rod Type	AWJ
OD (inches)	1.75
ID (inches)	1.25
Cross-Sectional Area (in²)	1.19
Typical Lengths (feet)	5
Instrumented Rod Type	AWJ (Serial No. 203)
OD (inches)	1.75
ID (inches)	1.25
Cross-Sectional Area (in²)	1.19
Total Instrumented Rod Length (feet)	2.0
Length Below Gages (feet)	0.8
Split-Spoon Length (feet)	2.85



3.0 Dynamic Testing Results

The total rod length from the instrumentation to the tip of the split-spoon sampler was determined by adding 3.65 ft to the drill rod length at each sample depth. The SPT Energy Measurement Data Summary tables in Appendix IV present the test data from every hammer blow at each sampling interval, along with representative force and velocity traces for each test interval. Per ASTM D4633, only the blows from the final foot of each sample interval (i.e. the blows that determine the N-value) are considered when computing the average measurement values of each test interval.

The reported blow counts obtained by the drill rig personnel, a summary of the test data, and average computed hammer energy and transfer ratio values are provided in Table 3-1. Based on the test data, the automatic hammer on the CME-550X operated at an average rate of about 51 blows per minute (bpm) during dynamic testing. The measured average transferred hammer energy (EFV) of the four sample intervals tested ranged from 263 to 292 ft-lbs, which corresponds to Energy Transfer Ratio (ETR) values of 75.2 to 83.4%, respectively. Plots and tables of the following are also included in the Appendix and present the test data with depth for each test interval:

- Penetration vs. BLC¹
- Penetration vs. CSX⁴
- ETR vs. Rod Length
- Penetration vs. FMX²
- Penetration vs. VMX⁵
- Average ETR vs. Rod Length
- Penetration vs. EFV³
- Penetration vs. ETR⁶

Table 3-1: Summary of Dynamic Testing Results

Data Set ID	Sample Depth (ft)	Drill Rod Length (ft)	Instrumentation to Sampler Tip Length (ft)	Blows per 6" Increment / N-value	Soil Sample Description (Piedmont Residual)	Avg. BPM	Avg. EFV (ft-lbs)	Avg. ETR (%)
1	28.5 – 30.0	30.0	33.65	7-9-11 / 20	SILTY SAND	43.3	263	75.2
2	33.5 – 35.0	35.0	38.65	7-11-14 / 25	SILTY SAND	53.2	289	82.6
3	38.5 – 40.0	40.0	43.65	9-10-12 / 22	SILTY SAND	53.2	289	82.6
4	43.5 – 45.0	45.0	48.65	10-10-11 / 21	SILTY SAND	53.3	292	83.4
Overall Average						51.0	284	81.1

The overall average transferred hammer energy for the automatic hammer on the CME-550X ATV-mounted drill rig was 284 foot-pounds, with an average ETR of 81.1%.

¹ BLC - Blow Count per 6-in. increment

² FMX - Maximum Compressive Force

³ EFV - Maximum Transferred Energy

⁴ CSX - Maximum Compressive Stress

⁵ VMX - Maximum Velocity

⁶ ETR - Energy Transfer Ratio - Ratio of Calculated Energy to Theoretical Energy of 140 lb hammer falling 30 inches



4.0 Limitations of Report

This report has been prepared in accordance with generally accepted geotechnical engineering practice for specific application to this project. The conclusions contained in this report were based on the applicable standards of our profession in this geographic area at the time this report was prepared. No other warranty, express or implied, is made.

5.0 Closing

S&ME appreciates the opportunity to provide this report to the North Carolina Department of Transportation, Geotechnical Engineering Unit. Please let us know if you have any questions concerning this report.

Sincerely,

S&ME, Inc.

A handwritten signature in blue ink that reads "Joseph Williamson".

Joseph R. Williamson, P.E.
Geotechnical Group Leader



Gregory J. Canivan, P.E.
Technical Principal
N.C. Registration No. 028593

Appendices:

- Appendix I - Certificates of Proficiency
- Appendix II - Instrumented Rod and Accelerometer Calibration Sheets
- Appendix III - SPT Energy Evaluation Form (Field Log) & Boring L3_121 Soil Boring Log
- Appendix IV - CME-550X ATV (SN 290593) SPT Energy Measurements Summary Plots and Tables

Appendices

Appendices

Appendix I



This documents that

**Joseph Williamson
S&ME**

has on October 31, 2017 achieved the rank of


INTERMEDIATE

on the Dynamic Measurement and Analysis Proficiency Test.

The individual identified on this document demonstrated to the degree granted above an understanding of theory, data quality evaluation, interpretation and signal matching for high strain dynamic testing of deep foundations. ***It is recommended that Individuals at the Intermediate level seek Advanced, Master or Expert levels through additional study within four years of the date of this document.***

The ability of the individual named to provide appropriate knowledge and advice on a specific project is not implied or warranted by the Pile Driving Contractors Association or Pile Dynamics, Inc. The Pile Driving Contractors Association or Pile Dynamics, Inc. assumes no liability for foundation testing and analysis work performed by the bearer of this certificate. This certificate can be verified at www.PDAproficiencytest.com.


Steven A. Hall, Executive Director
Pile Driving Contractors Association


Garland Likins, Senior Partner
Pile Dynamics, Inc.

No. 2426





This documents that

**Greg Canivan
S&ME Inc.**

has on October 8, 2014 achieved the rank of


MASTER

on the Dynamic Measurement and Analysis Proficiency Test.

The individual identified on this document demonstrated to the degree granted above an understanding of theory, data quality evaluation, interpretation and signal matching for high strain dynamic testing of deep foundations. ***It is recommended that individuals at the Master level seek to attain Expert level through additional study within five years of the date of this document***

The ability of the individual named to provide appropriate knowledge and advice on a specific project is not implied or warranted by the Pile Driving Contractors Association or Pile Dynamics, Inc. The Pile Driving Contractors Association or Pile Dynamics, Inc. assumes no liability for foundation testing and analysis work performed by the bearer of this certificate. This certificate can be verified at www.PDAproficiencytest.com.


Steven A. Hall, Executive Director
Pile Driving Contractors Association




Garland Likins, President
Pile Dynamics, Inc


No. 721

Appendix II

203AWJ		Cycle 1		
Sample	Force (lb)	Strain (μ E)	Bridge 1 (V)	Bridge 2 (V)
1	0.00	0.00	0.00	0.00
2	1238.45	35.09	0.16	0.16
3	2101.82	59.39	0.28	0.28
4	3386.54	94.77	0.44	0.44
5	4235.08	119.35	0.56	0.56
6	5136.73	144.58	0.67	0.67
7	6021.00	168.91	0.79	0.79
8	7359.61	207.34	0.97	0.97
9	8298.94	232.84	1.09	1.09
10	9187.31	257.76	1.21	1.20
11	10120.00	284.12	1.33	1.33

Bridge 1		Bridge 2	
Force Calibration (lb/V)	7630.77	Force Calibration (lb/V)	7630.97
Offset	-7.83	Offset	-3.17
Correlation	1.000000	Correlation	0.999999
Strain Calibration (μ E/V)	213.97	Strain Calibration (μ E/V)	213.98
Offset	0.12	Offset	0.25
Correlation	0.999992	Correlation	0.999995


Force Strain Calibration	
EA (Kips)	35662.28
Offset	-12.17
Correlation	0.999993



203AWJ		Cycle 2		
Sample	Force (lb)	Strain (μE)	Bridge 1 (V)	Bridge 2 (V)
1	0.00	0.00	0.00	0.00
2	883.29	25.21	0.12	0.12
3	1765.61	49.65	0.23	0.23
4	3049.75	86.59	0.40	0.40
5	3958.42	112.20	0.52	0.52
6	4857.33	137.43	0.64	0.64
7	5743.75	162.78	0.76	0.76
8	7145.42	202.15	0.94	0.94
9	8044.14	227.44	1.06	1.06
10	8969.22	253.99	1.18	1.18
11	9924.95	280.34	1.30	1.30

Bridge 1		Bridge 2	
Force Calibration (lb/V)	7617.86	Force Calibration (lb/V)	7627.07
Offset	-11.91	Offset	-18.36
Correlation	0.999998	Correlation	1.000000
Strain Calibration ($\mu\text{E/V}$)	215.30	Strain Calibration ($\mu\text{E/V}$)	215.56
Offset	-0.14	Offset	-0.33
Correlation	0.999995	Correlation	0.999996


Force Strain Calibration	
EA (Kips)	35381.61
Offset	-6.76
Correlation	0.999996



203AWJ		Cycle 3		
Sample	Force (lb)	Strain (μE)	Bridge 1 (V)	Bridge 2 (V)
1	0.00	0.00	0.00	0.00
2	843.85	23.93	0.11	0.11
3	2145.36	61.00	0.28	0.28
4	3029.63	85.25	0.40	0.40
5	3880.71	109.47	0.51	0.51
6	5241.19	147.71	0.69	0.69
7	6147.33	172.47	0.81	0.81
8	7034.72	198.06	0.92	0.92
9	7979.71	224.33	1.05	1.05
10	8906.15	249.58	1.17	1.17
11	9817.56	275.86	1.29	1.29

Bridge 1		Bridge 2	
Force Calibration (lb/V)	7623.93	Force Calibration (lb/V)	7629.88
Offset	-3.49	Offset	-9.59
Correlation	0.999999	Correlation	0.999999
Strain Calibration ($\mu\text{E}/\text{V}$)	213.65	Strain Calibration ($\mu\text{E}/\text{V}$)	213.81
Offset	0.47	Offset	0.30
Correlation	0.999992	Correlation	0.999991

Force Strain Calibration	
EA (Kips)	35684.19
Offset	-20.08
Correlation	0.999992




Bridge Excitation (V) 5
Shunt Resistor (ohm) 60.4k

Calibration Factors	203AWJ		
Bridge 1 ($\mu\text{E/V}$)	214.31	Bridge 2 ($\mu\text{E/V}$)	214.45
EA Factor (Kips)	35576.02	Area (in^2)	1.19

Calibrated by:

Calibrated Date:


2/26/2019

Pile Dynamics Inc
30725 Aurora Rd
Solon, OH 44139

Traceable to N.I.S.T.

QBTA: ON [ALT-F1/BB=60]

File Dynamics, Inc.

TG F2 DPF

File Dynamics
2019-05-21 10:07FS —
10BN 3743
SL 1513/ 3440/ 2PJ:
PN: HOPBARA 4 -- US
F 2 3.3LE 17.0 ft
AR 1.7 in2
EM 30000 Ksi
SP 0.492 K/ft3
WS 16815 ft/s
WC 7312 ft/sJC 0.40
FM 1.00
UM 1.00EA/C 30.3 Ks/ft
UN KIPS*0.1
FR 20000 MB 90DL -42
UT -1 IP 0.00
PK 1 TM-PEAKF1/2 500/ 213
F3/4 213/ 213
A1/2 999/ 999
A3/4 999/ 378TS 12 E B PD: K5641 LP 0.00 ft
TB 8.0 T1 9.6 2L/C 4.7 UA 1000 UE 1024 LI 1.0

ACCEPT SQ-OFF FL-OFF PR-OFF

ACCEPT

UMX= 4.1 FMX= 65 AMX= 139
EMX= 0.2 MEX= 127 FVP= 1.00

ACCELEROMETER CALIBRATION N.I.S.T. Traceable

SERIAL NUMBER: K5641

CALIBRATION FACTOR: .0756 MV/g

PAK (*5000): 378 DATE: 21 MAY 19

PDA OPERATOR: [Signature]

<-AT:PIEZORESISTIVE

OP: LAINE [ver:5.011]

AT:PIEZOELECTRIC->

Smart Sensor

Programmed By: [Signature]

CRC Value F648

QBTA: ON [ALT-F1/BB=60]


Pile Dynamics, Inc.

TG F2 DPF

Pile Dynamics
2020-02-28 11:23FS —
10BN 5034/15033
SL 1255/ 3440/ 99PJ:
PN: HOPBARA 4 -- US
F 2 3.3LE 39.6 ft
AR 1.7 in2
EM 30000 Ksi
SP 0.492 K/ft3
WS 16815 ft/s
WC 16851 ft/sJC 0.40
FM 1.00
UM 1.00EA/C 30.3 Ks/ft
UN KIPS*0.1
FR 20000 MB 90DL -27
UT -1 IP 0.00
PK 1 TM-PEAKF1/2 500/ 213
F3/4 213/ 213
A1/2 999/ 999
A3/4 999/ 385TS 12
TB 8.0E B PD: K10181
T1 9.6 2L/C 4.7VA 1000 VE 1024 LP 0.00 ft
LI 1.0

ACCEPT SQ-OFF FL-OFF PR-OFF

ACCEPT

VMX= 4.1 FMX= 64 AMX= 149
EMX= 0.2 MEX= 125 FVP= 0.99

ACCELEROMETER CALIBRATION N.I.S.T. Traceable

SERIAL NUMBER: K10181

CALIBRATION FACTOR: .077 mV/g

PAK (*5000): 385

DATE: 28 Feb 20

PDA OPERATOR: [Signature]

<-AT:PIEZORESISTIVE

OP: LAINE [ver:5.01]

AT:PIEZOELECTRIC->

Smart Sensor

Programmed By: [Signature]

CRC Value 1108

Appendix III



SPT Energy Evaluation Form

Project: RUTHERFORDTON / US-221 RELOCATION
Project No.: 6235-20-004 / R-2233BA
Boring No.: L3_121

Date: 5/5/2020
Weather: CLEAR / 70s
Drill Rod Type: 5' LONG AWJ

On-site Personnel


Drilling Company: S&ME, INC.
Rig Operator: F. JOHNSON
Engr/Geologist: B. KEBEA
Client Rep.: N/A
Analyzer Oper.: J. WILLIAMSON

Rig/Hammer Info

Drill Rig Make/Model: CME-550X
Carrier Type: ATV
Rig Serial No.: 290593
Hammer Type/Model: CME-550X
Hammer Serial No.: N/A - BUILT IN
Hammer Drop System: AUTOMATIC
Lubrication Condition: PER MANUFACTURER
Manufacturer Recommended
Operation Rate (bpm): 50
Typical Drop Height (in.): 30
Typical Hammer Weight (lbs): 140
Anvil Dimension (in.): 12
Drilling Method: MUD ROTARY - 2-15/16" TRICONE

Rod Info

(A + E) Impact Surface to Gages Length: 1.2 ft
(B) Instr. Rod Length below Gages: 0.8 ft
(A) + (B) Instr. Rod Length: 2.0 ft
(D) Spoon Length: 2.85 ft
(E) Rod Length Above Instr. Rod (if applicable): N/A ft
Instr. Rod S/N: 203AWJ
Instr. Rod Outside Dia.: 1.75 in.
Instr. Rod Area: 1.19 in²
PDA Make/Model: PDI/PAX
PDA Serial No.: 3733L
Calib. Pulse Test (y/n): Y



Gage Info

Gage		Serial No.	Calibration No.
Accel.	A3	K5641	378.0
	A4	K10181	385.0
Strain	F3	203AWJ-1	214.31
	F4	203AWJ-2	214.45

Date of Test	Test Depth Increment (ft to ft)	Test Time Start / Stop (military)	Length of Drill String (ft) (C)	(LE) Length below Gages (ft) (B) + (C) + (D)	Avg. Meas. Hammer Rate (BPM)	SPT Blow Counts				Drop Height in Tolerance (y/n)	
						6"	12"	18"	N-Value		
5/5/2020	28.5 - 30.0	9:52	30	33.65	43	7	9	11	20	Y	A-2-4
	33.5 - 35.0	10:02	35	38.65	53	7	11	14	25	Y	A-2-4
	38.5 - 40.0	10:14	40	43.65	53	9	10	12	22	Y	A-2-4
	43.5 - 45.0	10:23	45	48.65	53	10	10	11	21	Y	A-2-4
	48.5 - 50.0	10:36	50	53.65	53	12	18	35	53	Y	A-2-4
	53.5 - 55.0	10:48	55	58.65	53	25	58	42/0.2'	100/0.7'	Y	WR

Notes:

NOTE: (1) Note any unusual hammer operating conditions that affect the hammer performance, or changes in operating conditions (e.g. veritcality, weather, or lubrication between trials). (2) Note any changes in rod diameter along drill string and record locations of short rod sections.

Joseph Williamson
Prepared By (print/signature)

5/5/2020
Date

SHEET 1


NC DOT BORE SINGLE L3_116 BORING LOG.GPJ NC_DOT.GDT 5/7/20

Appendix IV



CME-550X (SN 290593) - 28.5-30.0 FEET

L3_121




CME-550X (SN 290593)
JRW
L3_121

Annual Calibration
Test date: 5/5/2020

AR: 1.19 in²
LE: 33.65 ft
WS: 16807.9 ft/s

SP: 0.492 k/ft³
EM: 30000 ksi

Depth: (28.50 - 30.00 ft), displaying BN: 15



F1 : [203 AWJ-1] 214.31 PDICAL (1) FF1
F2 : [203 AWJ-2] 214.45 PDICAL (1) FF1

A1 (PR): [K5641] 378 mv/6.4v/5000g (1) VF1
A2 (PR): [K10181] 385 mv/6.4v/5000g (1) VF1

BPM: Blows/Minute

FMX: Maximum Force

VMX: Maximum Velocity

DMX: Maximum Displacement

CSX: Compression Stress Maximum

DFN: Final Displacement

EFV: Maximum Energy

ETR: Energy Transfer Ratio - Rated

BL#	LP ft	BC /6"	BPM bpm	FMX kips	VMX ft/s	DMX in	CSX ksi	DFN in	EFV ft-lb	ETR %
1	28.57	7	1.9	26	16.9	1.29	21.9	0.86	261	74.6
2	28.64	7	31.6	28	16.6	1.10	23.7	0.86	251	71.6
3	28.71	7	41.8	29	16.8	1.03	24.2	0.86	258	73.8
4	28.79	7	43.3	28	17.0	0.96	23.8	0.86	262	74.9
5	28.86	7	43.0	29	16.8	0.91	24.0	0.86	257	73.6
6	28.93	7	43.2	27	16.9	0.91	22.4	0.86	257	73.3
7	29.00	7	43.4	28	17.0	0.90	23.2	0.86	257	73.4
8	29.06	9	43.0	28	17.0	0.84	23.1	0.67	253	72.2
9	29.11	9	43.1	28	17.1	0.86	23.4	0.67	259	74.0
10	29.17	9	43.2	28	17.0	0.81	23.9	0.67	256	73.2
11	29.22	9	43.3	28	17.2	0.80	23.4	0.67	262	74.8
12	29.28	9	43.3	29	17.2	0.76	24.1	0.67	261	74.6
13	29.33	9	43.2	28	17.5	0.72	23.9	0.67	265	75.7
14	29.39	9	43.2	28	17.5	0.71	23.7	0.67	266	76.0
15	29.44	9	43.2	29	17.5	0.70	24.4	0.67	264	75.5
16	29.50	9	43.3	29	17.2	0.69	24.0	0.67	265	75.8
17	29.55	11	43.3	28	17.6	0.66	23.8	0.55	266	76.1
18	29.59	11	43.2	28	17.6	0.66	23.2	0.55	266	76.0
19	29.64	11	43.3	27	17.6	0.65	23.1	0.55	266	76.0
20	29.68	11	43.4	29	17.6	0.64	24.0	0.55	265	75.7
21	29.73	11	43.3	27	17.6	0.62	22.8	0.55	266	76.0
22	29.77	11	43.3	27	17.9	0.61	23.1	0.55	267	76.2
23	29.82	11	43.2	27	17.6	0.60	22.6	0.55	261	74.6
24	29.86	11	43.4	27	17.7	0.60	22.6	0.55	266	76.0
25	29.91	11	43.4	27	17.7	0.58	22.7	0.55	266	75.9
26	29.95	11	43.4	27	17.8	0.55	22.4	0.55	264	75.4
27	30.00	11	43.5	27	17.6	0.55	22.5	0.55	262	75.0

Average	43.3	28	17.5	0.68	23.3	0.60	263	75.2
Std Dev	0.1	1	0.3	0.09	0.6	0.06	4	1.0
Maximum	43.5	29	17.9	0.86	24.4	0.67	267	76.2
Minimum	43.0	27	17.0	0.55	22.4	0.55	253	72.2


N-value: 20

Sample Interval Time: 36.56 seconds.



CME-550X (SN 290593) - 33.5-35.0 FEET

L3_121




CME-550X (SN 290593)
JRW
L3_121

Annual Calibration
Test date: 5/5/2020

AR: 1.19 in²
LE: 38.65 ft
WS: 16807.9 ft/s

SP: 0.492 k/ft³
EM: 30000 ksi

Depth: (33.50 - 35.00 ft), displaying BN: 26



F1 : [203 AWJ-1] 214.31 PDICAL (1) FF1
F2 : [203 AWJ-2] 214.45 PDICAL (1) FF1

A1 (PR): [K5641] 378 mv/6.4v/5000g (1) VF1
A2 (PR): [K10181] 385 mv/6.4v/5000g (1) VF1

BL#	LP ft	BC /6"	BPM bpm	FMX kips	VMX ft/s	DMX in	CSX ksi	DFN in	EFV ft-lb	ETR %
1	33.57	7	1.9	29	18.4	1.07	24.2	0.86	279	79.8
2	33.64	7	52.6	26	18.0	1.00	22.1	0.86	287	81.9
3	33.71	7	52.9	27	18.2	0.91	22.4	0.86	286	81.7
4	33.79	7	53.4	27	18.0	0.90	22.5	0.86	293	83.8
5	33.86	7	53.4	27	18.2	0.92	22.8	0.86	296	84.7
6	33.93	7	53.2	27	18.3	0.91	22.6	0.86	296	84.5
7	34.00	7	53.3	27	18.2	0.86	22.4	0.86	288	82.3
8	34.05	11	53.3	26	17.9	0.74	21.9	0.54	273	78.0
9	34.09	11	53.1	25	18.1	0.70	21.3	0.54	274	78.3
10	34.14	11	53.1	26	18.1	0.69	21.4	0.54	281	80.3
11	34.18	11	53.4	25	18.1	0.69	21.3	0.54	284	81.2
12	34.23	11	53.0	24	18.3	0.68	20.5	0.54	292	83.4
13	34.27	11	53.4	25	18.2	0.59	21.0	0.54	289	82.5
14	34.32	11	53.4	25	18.6	0.55	20.8	0.54	293	83.8
15	34.36	11	53.3	24	18.1	0.54	20.2	0.54	289	82.5
16	34.41	11	53.0	24	18.7	0.54	20.5	0.54	293	83.7
17	34.45	11	53.4	25	18.6	0.54	20.6	0.54	294	84.0
18	34.50	11	53.2	25	18.3	0.54	20.7	0.54	289	82.4
19	34.54	14	53.4	25	18.5	0.52	20.7	0.43	290	82.8
20	34.57	14	53.1	24	18.2	0.51	20.5	0.43	281	80.1
21	34.61	14	53.1	24	18.8	0.53	20.4	0.43	295	84.3
22	34.64	14	53.2	25	18.6	0.51	20.7	0.43	285	81.5
23	34.68	14	53.3	24	18.5	0.55	20.5	0.43	294	84.1
24	34.71	14	53.1	24	18.7	0.51	20.5	0.43	289	82.5
25	34.75	14	53.1	25	18.7	0.51	21.0	0.42	292	83.3
26	34.79	14	53.3	26	18.3	0.50	21.8	0.43	289	82.6
27	34.82	14	53.1	25	18.6	0.50	20.8	0.43	286	81.7
28	34.86	14	53.1	25	18.8	0.50	21.0	0.43	291	83.1
29	34.89	14	53.5	25	18.7	0.50	21.0	0.43	292	83.4
30	34.93	14	52.8	25	18.8	0.51	21.0	0.43	297	84.8
31	34.96	14	53.3	25	18.7	0.50	21.3	0.43	295	84.3


32	35.00	14	52.7	26	18.8	0.50	21.5	0.43	298	85.1
		Average	53.2	25	18.5	0.56	20.9	0.48	289	82.6
		Std Dev	0.2	1	0.3	0.07	0.4	0.06	6	1.8
		Maximum	53.5	26	18.8	0.74	21.9	0.54	298	85.1
		Minimum	52.7	24	17.9	0.50	20.2	0.42	273	78.0
N-value: 25										

Sample Interval Time: 34.93 seconds.



CME-550X (SN 290593) - 38.5-40.0 FEET

L3_121




CME-550X (SN 290593)
JRW
L3_121

Annual Calibration
Test date: 5/5/2020

AR: 1.19 in²
LE: 43.65 ft
WS: 16807.9 ft/s

SP: 0.492 k/ft³
EM: 30000 ksi

Depth: (38.50 - 40.00 ft), displaying BN: 21



F1 : [203 AWJ-1] 214.31 PDICAL (1) FF1
F2 : [203 AWJ-2] 214.45 PDICAL (1) FF1

A1 (PR): [K5641] 378 mv/6.4v/5000g (1) VF1
A2 (PR): [K10181] 385 mv/6.4v/5000g (1) VF1

BL#	LP ft	BC /6"	BPM bpm	FMX kips	VMX ft/s	DMX in	CSX ksi	DFN in	EFV ft-lb	ETR %
1	38.56	9	1.9	29	18.5	1.03	24.6	0.67	301	85.9
2	38.61	9	52.8	26	18.2	0.78	21.7	0.67	300	85.6
3	38.67	9	52.7	27	18.6	0.72	22.8	0.67	311	88.8
4	38.72	9	53.2	27	18.8	0.74	23.0	0.67	310	88.6
5	38.78	9	53.1	27	18.6	0.72	23.1	0.67	301	86.0
6	38.83	9	53.2	28	18.4	0.70	23.3	0.67	291	83.1
7	38.89	9	53.2	27	18.6	0.78	22.9	0.67	301	86.1
8	38.94	9	53.5	28	18.7	0.75	23.1	0.67	296	84.5
9	39.00	9	53.0	27	18.5	0.75	22.7	0.66	290	82.7
10	39.05	10	53.5	27	18.9	0.74	22.3	0.60	297	84.9
11	39.10	10	53.2	28	18.9	0.72	23.7	0.60	292	83.4
12	39.15	10	53.2	26	18.7	0.85	21.6	0.60	306	87.4
13	39.20	10	53.4	26	18.4	0.74	21.5	0.60	287	81.9
14	39.25	10	53.0	26	18.6	0.71	22.3	0.60	291	83.2
15	39.30	10	53.2	27	18.5	0.63	22.5	0.60	285	81.5
16	39.35	10	53.1	26	18.7	0.62	21.9	0.60	294	83.9
17	39.40	10	53.0	26	18.3	0.61	22.0	0.60	287	81.9
18	39.45	10	53.4	27	18.7	0.64	22.4	0.60	303	86.6
19	39.50	10	53.2	27	18.6	0.60	22.8	0.60	294	83.9
20	39.54	12	53.3	26	18.7	0.58	22.1	0.50	291	83.1
21	39.58	12	53.2	27	18.6	0.58	22.6	0.50	288	82.4
22	39.63	12	52.9	27	18.2	0.69	22.5	0.50	292	83.4
23	39.67	12	53.3	26	18.3	0.57	22.0	0.50	280	80.0
24	39.71	12	53.2	26	18.1	0.57	22.0	0.50	278	79.5
25	39.75	12	53.1	26	18.1	0.56	22.1	0.50	281	80.2
26	39.79	12	53.1	26	18.2	0.56	22.3	0.50	281	80.4
27	39.83	12	53.1	27	17.9	0.58	22.5	0.50	291	83.0
28	39.88	12	53.1	26	17.8	0.64	22.1	0.50	291	83.1
29	39.92	12	53.5	27	17.9	0.56	22.6	0.50	286	81.6
30	39.96	12	53.0	28	17.9	0.56	23.2	0.50	286	81.6
31	40.00	12	52.9	26	17.9	0.58	22.2	0.50	285	81.5

Average	53.2	27	18.4	0.63	22.3	0.54	289	82.6
Std Dev	0.2	1	0.3	0.08	0.5	0.05	7	1.9
Maximum	53.5	28	18.9	0.85	23.7	0.60	306	87.4
Minimum	52.9	26	17.8	0.56	21.5	0.50	278	79.5


N-value: 22

Sample Interval Time: 33.81 seconds.



CME-550X (SN 290593) - 43.5-45.0 FEET

L3_121




CME-550X (SN 290593)
JRW
L3_121

Annual Calibration
Test date: 5/5/2020

AR: 1.19 in²
LE: 48.65 ft
WS: 16807.9 ft/s

SP: 0.492 k/ft³
EM: 30000 ksi



F1 : [203 AWJ-1] 214.31 PDICAL (1) FF1
F2 : [203 AWJ-2] 214.45 PDICAL (1) FF1

A1 (PR): [K5641] 378 mv/6.4v/5000g (1) VF1
A2 (PR): [K10181] 385 mv/6.4v/5000g (1) VF1

BL#	LP ft	BC /6"	BPM bpm	FMX kips	VMX ft/s	DMX in	CSX ksi	DFN in	EFV ft-lb	ETR %
1	43.55	10	1.9	28	18.7	0.78	23.3	0.60	284	81.1
2	43.60	10	52.3	27	18.8	0.63	22.8	0.60	277	79.2
3	43.65	10	54.0	27	18.6	0.63	22.8	0.60	284	81.0
4	43.70	10	52.9	27	18.9	0.64	23.0	0.60	286	81.6
5	43.75	10	53.5	27	19.2	0.64	22.7	0.60	291	83.2
6	43.80	10	53.5	27	19.3	0.66	23.1	0.60	294	84.1
7	43.85	10	53.2	27	19.1	0.68	22.3	0.60	284	81.2
8	43.90	10	53.4	27	19.2	0.69	22.6	0.60	284	81.2
9	43.95	10	53.3	27	19.2	0.70	22.5	0.60	283	81.0
10	44.00	10	53.5	26	19.3	0.70	22.1	0.60	283	80.9
11	44.05	10	53.1	27	19.3	0.70	22.4	0.60	284	81.2
12	44.10	10	53.3	27	19.5	0.71	22.8	0.60	293	83.7
13	44.15	10	53.5	26	19.3	0.72	21.9	0.60	285	81.4
14	44.20	10	53.5	26	19.3	0.74	22.0	0.60	287	82.0
15	44.25	10	53.3	26	19.5	0.75	22.0	0.60	291	83.2
16	44.30	10	53.3	26	19.9	0.74	22.0	0.60	296	84.6
17	44.35	10	53.3	27	19.9	0.70	22.5	0.60	296	84.6
18	44.40	10	53.2	27	19.8	0.69	22.6	0.60	298	85.3
19	44.45	10	53.5	26	19.5	0.68	21.5	0.60	284	81.1
20	44.50	10	53.0	26	19.9	0.68	21.8	0.60	296	84.5
21	44.55	11	53.2	26	19.6	0.64	22.0	0.54	290	82.9
22	44.59	11	53.1	25	19.9	0.64	20.9	0.54	295	84.1
23	44.64	11	53.2	26	19.6	0.61	21.5	0.54	294	84.1
24	44.68	11	53.1	25	19.2	0.61	20.9	0.54	289	82.6
25	44.73	11	53.5	25	19.7	0.61	20.8	0.54	294	84.0
26	44.77	11	53.3	25	19.8	0.57	21.0	0.54	288	82.3
27	44.82	11	53.2	25	19.7	0.59	20.8	0.54	296	84.5
28	44.86	11	53.2	24	19.3	0.58	20.1	0.54	289	82.5
29	44.91	11	53.2	24	19.5	0.56	20.0	0.54	293	83.8
30	44.95	11	53.4	23	18.9	0.58	19.6	0.54	295	84.3
31	45.00	11	53.2	24	19.4	0.58	20.2	0.54	298	85.2

Pile Dynamics, Inc.
SPT Analyzer Results

Page 2 of 2
PDA-S Ver. 2018.30 - Printed: 6/4/2020

Average	53.3	25	19.6	0.65	21.4	0.57	292	83.4
Std Dev	0.1	1	0.3	0.06	0.9	0.03	4	1.3
Maximum	53.5	27	19.9	0.75	22.8	0.60	298	85.3
Minimum	53.0	23	18.9	0.56	19.6	0.54	284	81.1
N-value: 21								

Sample Interval Time: 33.74 seconds.

Summary of SPT Test Results

Project: CME-550X (SN 290593), Test Date: 5/5/2020

BPM: Blows/Minute						CSX: Compression Stress Maximum							
FMX: Maximum Force						DFN: Final Displacement							
VMX: Maximum Velocity						EFV: Maximum Energy							
DMX: Maximum Displacement						ETR: Energy Transfer Ratio - Rated							
Instr. Length ft	Start Depth ft	Final Depth ft	Blows Applied /6"	N Value	N60 Value	Average BPM bpm	Average FMX kips	Average VMX ft/s	Average DMX in	Average CSX ksi	Average DFN in	Average EFV ft-lb	Average ETR %
33.65	28.50	30.00	7-9-11	20	27	43.3	28	17.5	0.68	23.3	0.60	263	75.2
38.65	33.50	35.00	7-11-14	25	33	53.2	25	18.5	0.56	20.9	0.48	289	82.6
43.65	38.50	40.00	9-10-12	22	29	53.2	27	18.4	0.63	22.3	0.54	289	82.6
48.65	43.50	45.00	10-10-11	21	28	53.3	25	19.6	0.65	21.4	0.57	292	83.4
Overall Average Values:						51.0	26	18.5	0.63	21.9	0.54	284	81.1
Standard Deviation:						4.2	1	0.8	0.09	1.1	0.07	13	3.6
Overall Maximum Value:						53.5	29	19.9	0.86	24.4	0.67	306	87.4
Overall Minimum Value:						43.0	23	17.0	0.50	19.6	0.42	253	72.2

