

Interim Condition Information

Anticipated Exhibit 3 Scope Language

Interim Condition

The Interim Condition is defined as full removal of toll facilities which impede free flow of traffic along Cross Island Parkway mainline and ramps as well as restriping of travel lanes through the affected areas to allow free flow of traffic. These impediments include the canopy, toll booths, crash attenuators, concrete bollards/barriers/curbs, stairwell openings, drainage features and other physical features that obstruct free flow of traffic. SCDOT desires to have these impediments removed in an expedited manner. The work also includes restriping ramps from two lanes to a single 16' wide ramp lane. The Interim Condition will be considered complete when all toll facilities have been removed and two mainline lanes of travel in each direction and single lane ramp ties have been provided as free flow movements.

Anticipated Exhibit 4z Language

1.2 Interim Condition Submittal

An Interim Condition phase, as defined in the Exhibit 3, is required for this project. The Interim Condition phase will require submittal of:

- Demolition plan in accordance with the Standard Specifications
- Traffic Control plans showing how traffic will be maintained/staged during demolition activities, including ramp traffic, and during lane reconfiguration operations
- Roadway plan sheets showing the final lane configuration, including ramps, for the Interim Condition

Plan submittals for the Interim Condition will follow the submittal process defined in Section 2 of this exhibit and will include preliminary, final and RFC plans.

Anticipated Agreement Language

CONTRACT TIME

Time to reach Interim Condition: The Project shall reach the Interim Condition within _____ calendar days from Notice to Proceed. The Notice to Proceed shall be no later than 45 days from the effective date of the Agreement. The PROPOSER must identify the time required to reach the Interim Condition for the construction time of the Project on the Cost Proposal Bid Form. In no case shall the time to reach Interim Completion be greater than 90 days from the notice to Proceed.

Liquidated Damages

CONTRACTOR shall pay liquidated damages to SCDOT in the amount of \$xx,xxx for each day for which the Interim Condition has not been completed and all travel lanes are not open to traffic in accordance with Article IV.

DRAFT