

Florence & Hutcheson  
501 Huger Street  
Columbia, SC 29201

Phone: (803)254-5800  
E-mail:

Fax: (803)929-0334

---

### Operational Analysis

---

Analyst: NJ  
Agency or Company: Florence & Hutcheson  
Date Performed: 3/31/2011  
Analysis Time Period: AM  
Freeway/Direction: I-385 SB  
From/To: End to Roper Mtn Rd  
Jurisdiction: Greenville, SC  
Analysis Year: 2015  
Description: I-85/I-385 No-Build

---

### Flow Inputs and Adjustments

---

Volume, V	3496	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	971	v
Trucks and buses	18	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	-	%
Segment length	-	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.917	
Driver population factor, fp	1.00	
Flow rate, vp	1411	pc/h/ln

---

### Speed Inputs and Adjustments

---

Lane width	-	ft
Right-side lateral clearance	-	ft
Total ramp density, TRD	-	ramps/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	55.0	mi/h
Lane width adjustment, fLW	-	mi/h
Lateral clearance adjustment, fLC	-	mi/h
TRD adjustment	-	mi/h
Free-flow speed, FFS	55.0	mi/h

---

### LOS and Performance Measures

---

Flow rate, vp	1411	pc/h/ln
Free-flow speed, FFS	55.0	mi/h
Average passenger-car speed, S	55.0	mi/h
Number of lanes, N	3	
Density, D	25.7	pc/mi/ln
Level of service, LOS	C	

Overall results are not computed when free-flow speed is less than 55 mph.