



South Carolina  
Department of Transportation

**INSTRUCTIONAL BULLETIN NO. 2006-10**

**SUBJECT:** Erosion Control Pay Items  
**EFFECTIVE DATE:** August 25, 2006  
**SUPERSEDES:** None  
**RE:** None


For projects having the pay item "Silt Fence", the following two additional pay items are required when the estimated quantity exceeds 2,000 linear feet:

<u>Item Number</u>	<u>Description</u>	<u>Unit</u>
8154050	Removal of Silt Retained by Silt Fence	LF
8153090	Replace/Repair Silt Fence	LF

The estimated quantities for these items will be as follows:

- a. "Removal of Silt Retained by Silt Fence" = 25% of the quantity for "Silt Fence".
- b. "Replace/Repair Silt Fence" = 10% of the quantity for "Silt Fence".

These items and quantities will be shown on the "General Construction Note Sheet" in the plans with the explanation, "For maintenance of Silt Fence".

Approved:   
E. S. Eargle  
Road Design Engineer

ESE:jhf

cc:

Mark C. Lester, Prog. Dev. Engineer West  
Charles Smoak, Hydraulic Engineer  
Matt Lifsey, Prog. Dev. Engineer East  
Jim Frick, Letting Preparation Facilitator

Mitchell Metts, Bridge Design Engineer  
Lindy Hallman, Road Construction Engineer  
Traffic Engineering

