

955 Park Street Post Office Box 191 Columbia, South Carolina 29202-0191 Office of the Director (803) 737-1302 • Fax (803) 737-2038

**Deputy Director of Engineering** (803) 737-1314 • Fax (803) 737-2038

Deputy Director of Finance and Administration (803) 737-1240 + Fax (803) 737-1719

Deputy Director of Mass Transit (803) 737-9720 + Fax (803) 737-9739

September 12, 1997

## **INSTRUCTIONAL BULLETIN NO. 97-9**

SUBJECT: Erosion Control Blanket

EFFECTIVE DATE: September 22, 1997

**SUPERSEDES:** None

RE: Instructional Bulletin 94-11 "Instructions for Sediment/Erosion Control Plans for South

Carolina Construction"

All bridge projects, regardless of size, will have the pay item "Erosion Control Blanket" included in the estimated quantities. The quantities will be calculated to include the entire fill slopes adjacent to the bridge back to the termini of the project or to a cut section. Areas to be rip rapped will not be include in the quantity for "Erosion Control Blanket". Where the roadway grade is 2.5% or greater, a quantity of "Erosion Control Blanket" will be computed to cover the roadway ditches to a minimum width of ten feet (5' each side of the bottom of the ditch) in the cut sections within the project limits. Quantities will be shown on the plans as described in Instructional Bulletin 94-11.

Approved:

E. S. Eargle

Road Design Engineer

ESE:adf

cc:

Federal Proj. Dev. Engr. Pratt "C" Proj. Dev. Engr. Kneece Director Right of Way Kelly