



SCDOT



ARMS

Access & Roadside Management Standards



This page intentionally left blank



ACCESS AND ROADSIDE MANAGEMENT STANDARDS

2008 Edition

Access and Roadside Management Standards (ARMS) Manual is published by the South Carolina Department of Transportation (SCDOT) Traffic Engineering Division. This manual is not intended to present all of the information that is needed by a permittee or designer; however, this document does provide a majority of the information needed for encroachments onto the right-of-way of the SCDOT. For specific projects or specific design elements, the permittee or designer may need to reference other SCDOT or national publications to perform a fully comprehensive analysis of the project.

As the need arises, this publication is revised, updated, and distributed within the Department. All parties are responsible for obtaining the most current edition.

South Carolina Department of Transportation
Traffic Engineering
955 Park Street, PO Box 191
Columbia, SC 29202-0191
www.scdot.org

Revision Date
April 25, 2008
June 20, 2008
July 28, 2008
August 18, 2008
November 13, 2009
August 18, 2011
Sept 26, 2012
April 27, 2015
Feb 3, 2020
May 15, 2020
Sep 3, 2021
July 8, 2025

This page intentionally left blank



ACCESS AND ROADSIDE MANAGEMENT STANDARDS 2008 EDITION

Summary of Significant Changes

In 1957, due to the enormous increase in the volume of traffic on the highway and the large number of accidents caused by unregulated entrances of highways, the South Carolina State Highway Department drafted *Standards for Driveway Entrances to Highways*. This publication was updated in 1976 and remained the standard until 1991 when the South Carolina Department of Transportation (SCDOT) published the *Access and Roadside Management Standards*, or ARMS Manual. It was updated in 1996 which is the edition that is currently being utilized. In 2004, Traffic Engineering identified the need for more comprehensive standards in step with current highway and land development practices in the region and nation. As a result, Traffic Engineering began a full scale update of the ARMS Manual. A committee was formed of representatives from Headquarters and District Traffic Engineering, Maintenance, Pre-Construction, and Hydrology to review the ARMS Manual and recommend changes to the current information and the addition of new concepts. The following items have been considered as the most significant changes to the manual.

1) Access Waivers (Chapter 1, Section 1E, Page 12): Recognizing that minimum criterion may not always be practical, a process has been established to approve exceptions to the access guidelines. If an applicant for an encroachment permit seeks a waiver, an access waiver request form (provided in Appendix C) shall be filled out and attached to the encroachment permit. The request should describe the undue hardship that will be placed on the applicant if a waiver is not granted. The Resident Maintenance Engineer (RME) should coordinate the waiver with the District Engineering Administrator and appropriate office at Headquarters. A waiver will only be granted if it is determined that:

1. Denial of the waiver will result in loss of reasonable access to the site.
2. The waiver is reasonably necessary for the convenience and welfare of the public.
3. All reasonable alternatives that meet the access requirements have been evaluated and determined to be infeasible.
4. Reasonable alternative access cannot be provided.
5. The waiver will not result in any violations of pedestrian accessibility in accordance with the ADAAG.

When a waiver is approved, the reasons for granting the waiver and any recommendations given by the Department shall be clearly stated and included in the Department files. Restrictions and conditions on the scope of the permit should be imposed as required in order to keep potential safety hazards to a minimum. The encroachment permit may contain specific terms and conditions providing for the expiration of the waiver if in the future the grounds for the waiver no longer exist. An Access Waiver should be included in the Appeal Process Request detailed in Section 2E.

2) Driveway Classification (Chapter 3, Section 3A-1, Page 20): A classification system for driveways has been developed based on the number of trips that will be generated by the land use that the driveway serves. This classification system, shown in Table 3-3 (page 19) will guide the design of driveway elements including width and radii.

3) Driveway Spacing and Location (Chapter 3, Section 3C, Page 26): Driveway spacing requirements (Figure 3-7, Page 26) were increased based on current recommended practice in Transportation Research Board's *Access Management Manual*. However, the old spacing requirements have been retained for driveways located on roadways with AADT<2000. Rather than measuring the spacing from the centerline of the driveways as in the 1996 ARMS, spacing will now be measured from the near edge of the driveways. This method will provide adequate spacing regardless of a drive's geometry. In the case of large developments with outparcels, access for outparcels should be provided only internally; however, shared or individual driveways may be permitted provided twice the normal spacing requirements are met.

4) Access Placement in Interchange Areas (Chapter 3, Section 3C-4, Page 30): Access connections to crossroads in the vicinity of freeway interchanges has been addressed (Figure 3-11, Page 30). Minimum spacing between the on and off ramp termini and the first access point is defined.

5) School Access Design (Chapter 4, Page 35): SCDOT Traffic Engineering's Guidelines for School Transportation Design has been added as a new chapter to the manual. On-site stacking length requirements have been increased.

6) Street Intersections (Chapter 5, Page 41): Various elements of intersection design from the SCDOT Highway Design Manual have been summarized and added as a new chapter. These elements include intersection spacing, design vehicle considerations, approach grade and side slope, auxiliary lane design, and parking considerations.

7) Auxiliary Lanes (Chapter 5, Section 5D, Page 47): When adding turn lanes, the road should be brought up to the latest standards requiring the addition of 2 foot paved shoulders.

8) Traffic Impact Studies (Chapter 6, Page 53): A Traffic Impact Study is a specialized engineering study that evaluates the effects of proposed development on traffic conditions in an area. A chapter has been added describing when a traffic study is required and the information that should be contained in the study.

9) Sight Distance (Chapter 7, Page 59): The intersection sight distance section from the SCDOT Highway Design Manual has been added as a new chapter to this manual. This chapter will replace the sight distance tables from the 1996 ARMS.

TABLE OF CONTENTS

CHAPTER 1 — INTRODUCTION	5
1A PURPOSE.....	5
1B AUTHORITY.....	7
1C SEVERABILITY	7
1D DEFINITIONS	7
1E DESIGN EXCEPTIONS AND ACCESS WAIVERS	11
CHAPTER 2 — ENCROACHMENT PERMITS	13
2A APPLICATION AND REQUIREMENTS	13
2B REVIEW AND APPROVAL.....	14
2C PERFORMANCE BONDS.....	15
2D CONDITIONS AND LIMITATIONS.....	16
2E ENCROACHMENT PERMIT APPEAL PROCESS REQUEST.....	18
CHAPTER 3 — DRIVEWAYS	19
3A GENERAL	19
3B DRIVEWAY DESIGN ELEMENTS	20
3C DRIVEWAY SPACING AND LOCATION	26
3D MEDIAN CROSSOVERS.....	32
3E TEMPORARY DRIVEWAYS	33
CHAPTER 4 – SCHOOL ACCESS DESIGN	34
4A GENERAL	35
4B ON-SITE STACKING.....	35
4C NUMBER OF SCHOOL DRIVEWAYS	36
4D DESIGN CONSIDERATIONS	37
4E ROADWAY WIDENING IMPROVEMENTS.....	39
4F MISCELLANEOUS RECOMMENDATIONS.....	39
CHAPTER 5 – STREET INTERSECTIONS	40
5A GENERAL	41
5B SPACING REQUIREMENTS	41
5C DESIGN CONSIDERATIONS.....	44
5D AUXILIARY LANES	47
CHAPTER 6 – TRAFFIC IMPACT STUDIES	53
6A GENERAL	53
6B STUDY REQUIREMENTS	55
CHAPTER 7 – SIGHT DISTANCE	58
7A GENERAL	59
7B BASIC CRITERIA.....	60
CHAPTER 8 –TRAFFIC CONTROL DEVICES.....	70
8A GENERAL	71
8B TRAFFIC SIGNALS.....	71
8C PAVEMENT MARKINGS	73
CHAPTER 9 –ROADSIDE ENCROACHMENTS	74

9A MAILBOXES.....	75
9B SIGNS	75
9C LIGHTS AND REFLECTIVE SURFACES.....	76
9D ROADWAY LIGHTING.....	76
9E GATEWAY MONUMENTS FOR INTERSTATE HIGHWAYS	76
9F UTILITIES.....	79
9G VISIBILITY ENHANCEMENT	79
9H HISTORICAL MARKERS AND BLUE STAR MEMORIAL HIGHWAY SIGNS	79
CHAPTER 10 — DRAINAGE	82
10A GENERAL REQUIREMENTS	83
10B DESIGN AND DISCHARGE.....	83
10C MAINTENANCE AND SAFETY CONSIDERATIONS	84
10D NPDES CONSIDERATIONS.....	84
10E PERMIT APPLICATION REQUIREMENTS	85
CHAPTER 11 — ENVIRONMENTAL.....	87
11A GENERAL REQUIREMENTS	87
11B PERMITTING REQUIREMENTS	87
CHAPTER 12 — BRIDGES, CULVERTS, AND RETAINING WALLS	88
12A GENERAL REQUIREMENTS	89
12B PRELIMINARY COORDINATION	90
CHAPTER 13 — CONSTRUCTION	91
13A GENERAL	91
13B INSPECTION AND APPROVAL.....	92
CHAPTER 14 — LANDSCAPING GUIDELINES.....	94
14A INTRODUCTION.....	94
14B POLICY.....	97
14B GUIDANCE.....	99
APPENDIX.....	104
APPENDIX A - TYPICAL DRAWINGS	
APPENDIX B - SCDOT PERSONNEL CONTACT INFORMATION	
APPENDIX C – ENCROACHMENT PERMIT INFORMATION	
APPENDIX D – ENGINEERING DIRECTIVES	
APPENDIX E – LANDSCAPING GUIDELINES	
APPENDIX F – ADDITIONAL TRIP GENERATION INFORMATION	

LIST OF FIGURES

Figure 3-1: Angle of Intersection	21
Figure 3-2: Critical Dimensions in Driveway Design	21
Figure 3-3: Inadequate Driveway Design.....	22
Figure 3-4: Medium Volume Driveway Approach Grade.....	23
Figure 3-5: Recommended Driveway Throat Lengths	24
Figure 3-6: Driveway Median Design	25
Figure 3-7: Minimum Driveway Spacing	27
Figure 3-8: Driveway Connections on Opposite Sides of the Roadway.....	28
Figure 3-9: Corner Clearances.....	29
Figure 3-10: Minimum Radius Offset Requirements	29
Figure 3-11: Minimum Spacing for Freeway Interchange Areas.....	30
Figure 3-12: Flag Lots and Alternative Access	31
Figure 3-13: Driveways with Median Crossovers	32
Figure 4-14: School Driveway Spacing	37
Figure 4-15: School Drive Width and Radii	38
Figure 5-16: Street Alignment	42
Figure 5-17: Traffic Signal Spacing.....	43
Figure 5-18: Roadway Angle of Intersection	45
Figure 5-19: Point of Tangency Offset	45
Figure 5-20: Offset Intersection Legs.....	46
Figure 5-21: Typical Auxiliary Lane Taper Lengths.....	50
Figure 5-22: Offset Left-turn Lanes	51
Figure 7-23: Sight Triangles.....	60
Figure 7-24: Sight Triangles on Divided Facilities.....	65
Figure 7-25: Sight Distance for a Stopped Vehicle Turning Left on a Major Road	68
Figure 7-26: Sight Distance at Skewed Intersection	69

LIST OF TABLES

Table 1-1: Summary of Effects of Access Management	6
Table 2-2: Review of Applications	15
Table 3-3: Driveway Classification	20
Table 3-4: Driveway Widths and Radii	22
Table 4-5: On-Site Stacking Length Requirements	36
Table 4-6: Recommended Number of Drives	36
Table 5-7: Turn Type Design Vehicles	44
Table 5-8: Right-Turn Lane Lengths	49
Table 5-9: Left Turn Lane Lengths	49
Table 6-10: Guidelines for Determining the Need for an Impact Study	54
Table 7-11: Gap Acceptance Times, Left Turns from Minor Road	63
Table 7-12: Intersection Sight Distance, Vehicles Approaching from the Left and For Vehicles Approaching from the Right on a Two-Lane Highway or Street Only	63
Table 7-13: Intersection Sight Distance For Vehicles Approaching from the Right on a Four-Lane Highway with a TWLTL Only	64
Table 7-14: Gap Acceptance Times for Crossing Maneuvers	66
Table 7-15: Two-Lane Intersection Sight Distances	66
Table 7-16: Gap Acceptance Times for Left Turns on a Major Road	69
Table 7-17: Intersection Sight Distances, Left Turns from Major Road	69
Table 14-1: Horizontal Clearances for Shrubs	101
Table 14-2: Horizontal Clearances for Small Trees	102
Table 14-3: Horizontal Clearances for Large Trees	103

CHAPTER 1 — INTRODUCTION



1A PURPOSE

These standards and guidelines have been developed to establish uniformity for encroachments upon roads in the South Carolina State Highway System so as to provide for the safe and efficient movement of traffic while allowing reasonable access to abutting property.

Access and Roadside Management Standards (ARMS) Manual is not intended to present all of the information that is needed by a permittee or designer; however, this document does provide a majority of the information needed for encroachments onto the State Highway System. For specific projects or specific design elements, the permittee or designer may need to reference other SCDOT or national publications to perform a fully comprehensive analysis of the project.

1A-1 History

Driveways have long been recognized as major sources of conflict for traffic on public highways. In order to reduce these conflicts and address the need for basic access, legislation was enacted in 1956 to establish a permitting process for driveways, and a handbook was developed to regulate the location, design, and construction of driveways adjoining highways.

Reasonable access means that a property owner must have access to the public highway system, rather than being guaranteed that potential patrons should have convenient access from a specific roadway to the owner's property.

1A-2 Need

The above-mentioned standard recognized that the efficiency and safety of a highway depend to a large extent upon roadside interference and its detrimental effect upon the movement of traffic. However, recent years have brought changes in land use and developmental impacts to our highways. With higher traffic volumes came

increased pressure to allow a variety of additional activities to occupy the roadside. The Department's desire to satisfy the public's need for efficient and safe traffic movement has to be weighed against property owners' needs for adequate access while taking into consideration significant changes in traffic and roadside characteristics. Since the primary purpose of highways is to provide for the safe and efficient movement of traffic, control of access points on the roadside is paramount. Previous standards became inadequate for regulating the location, design, construction, operation, and maintenance of points of access to the State Highway System and other activities within highway rights-of-way. This necessitated the development of this revision to the ARMS Manual which contains more comprehensive standards in step with current highway and land development practices in the region and nation.

1A-3 Effects of Specific Access Management Techniques

Studies of the effects of access management on traffic operations have indicated that the techniques help increase safety, maintain desired speed, and reduce delays. [Table 1-1](#) summarizes the general safety and operation effects of specific access management techniques based on research to date.

Table 1-1: Summary of Effects of Access Management

Treatment	Effects
Add continuous two-way left turn lane TWLTL	<ul style="list-style-type: none"> • 35% reduction in total crashes • 30% decrease in delay • 30% increase in capacity
Add nontraversable median	<ul style="list-style-type: none"> • $\geq 55\%$ reduction in total crashes • 30% decrease in delay • 30% increase in capacity
Replace TWLTL with a nontraversable median	<ul style="list-style-type: none"> • 15%-57% reduction in crashes on 4-lane • 25%-50% reduction in crashes on 6-lane
Add a left-turn bay	<ul style="list-style-type: none"> • 25%-50% reduction in crashes on 4-lane • Up to 75% reduction in total crashes at unsignalized access • 25% increase in capacity
Painted left turn improvement	<ul style="list-style-type: none"> • 32% reduction in total crashes
Separator/raised divider for left turn	<ul style="list-style-type: none"> • 67% reduction in total crashes
Add right-turn bay	<ul style="list-style-type: none"> • 20% reduction in total crashes • Limit right-turn interference with platooned flow, increased capacity
Increased driveway speed from 5 to 10 mph	<ul style="list-style-type: none"> • 50% reduction in delay per maneuver; less exposure time to following vehicles
Visual cue at driveways, illumination	<ul style="list-style-type: none"> • 42% reduction in crashes
Prohibition of on-street parking	<ul style="list-style-type: none"> • 30% increase in traffic flow • 20%-40% reduction in crashes
Long signal spacing with limited access	<ul style="list-style-type: none"> • 42% reduction in total vehicle-hours of travel • 59% reduction in delay

Source: Access Management Manual, Second Edition – Transportation Research Board, 2014

1B AUTHORITY

These standards are enacted pursuant to Sections 57-5-110 and 57-5-1080 and 1090 of the *Code of Laws of South Carolina* (1976 as amended through the 2006 Session of the General Assembly) and with the approval of the South Carolina Department of Transportation Commission.

The SCDOT reserves the right to deny or revoke any encroachment that is deemed detrimental to the state highway system or public safety.

1C SEVERABILITY

If, for any reason, any phrase, clause, sentence, paragraph, section, subsection, figure, table, or other part of this manual of standards and guidelines should be decided by a court of competent jurisdiction to be invalid or unconstitutional, such judgment shall not affect the validity of these standards and guidelines as a whole, or any part thereof, other than the part so held to be invalid.

1D DEFINITIONS

Access – Entrance to and/or exit from land fronting on the public highway system.

Access Point – A location on a property frontage at which access is allowed by the Department.

Applicant – The owner of a property or his or her agent applying for an encroachment permit.

ADA or Americans with Disabilities Act of 1990 – Federal law prohibiting discrimination against people with disabilities. Requires public entities and public accommodations to provide accessible accommodations for people with disabilities.

Americans with Disabilities Act Accessibility Guidelines (ADAAG) – Provides scoping and technical specifications for new construction and alterations undertaken by entities covered by the ADA.

Auxiliary Lane – The portion of the roadway adjoining the through traveled way for purposes supplementary to through traffic movement including parking, speed change, turning, storage for turning, weaving or truck climbing.

Average Annual Daily Traffic – The total volume of traffic passing a point or segment of a highway facility, in both directions, for one year, divided by the number of days in the year.

Average Daily Traffic – A general unit of measure for traffic expressed as the total volume during a given time period, greater than one day and less than one year, divided by the number of days in that time period.

Bicycle lane or bike lane – A portion of a roadway that has been designated for preferential or exclusive use by bicyclists by pavement markings and, if used, signs. It is intended for one-way travel, usually in the same direction as the adjacent traffic lane, unless designed as a contra-flow lane. (AASHTO *Guide for the Development of Bicycle Facilities*, 2012)

Collector Road – Functionally classified highway that is characterized by a roughly even distribution of their access and mobility functions.

Controlled-Access Highway – A highway over, from, or to which owners or occupants of abutting properties or others have no legal right of access except at such points and in such manner as determined by the Department.

Corner Clearance – The minimum distance, measured parallel to a highway, between the nearest curb, pavement or shoulder line of an intersecting public way and the nearest edge of a driveway excluding its radii.

Crossover – A paved or graded area in the highway median designed specifically for vehicles to cross the median of a divided highway.

Cross Slope – The slope measured perpendicular to the direction of (pedestrian) travel.

Crosswalk – (a) That part of a roadway at an intersection included within the connections of the lateral lines of the sidewalks on opposite sides of the highway measured from the curbs or in the absence of curbs, from the edges of the traversable roadway, and in the absence of a sidewalk on one side of the roadway, the part of a roadway included within the extension of the lateral lines of the sidewalk at right angles to the centerline; (b) any portion of a roadway at an intersection or elsewhere distinctly indicated as a pedestrian crossing by lines on the surface, which may be supplemented by contrasting pavement texture, style, or color.

Directional Median Opening – An opening in a restrictive median which provides for U-turns and or left-turn ingress and egress movements.

Divided Highway – A roadway that has separate traveled ways, usually with a depressed or CMB median, for traffic in opposite directions.

Department (SCDOT) – The South Carolina Department of Transportation.

Driveway – An access point that is not a public street, road, or highway.

Driveway Crossing – Extension of sidewalk across a driveway that meets the requirements of ADAAG.

Encroachment – Items placed within the existing right of way by persons other than the Department's staff or authorized agents.

Edge of Travel Way – Roadway location on the outside edge of the edge line pavement marking. If an edge line is not marked, this location would be the edge of pavement.

Flag Lot – A large lot not meeting minimum frontage requirements and where access to a public road is by a narrow, private right-of-way or driveway.

Freeway – The highest level of arterial. This facility is characterized by full control of access, high design speeds and a high level of driver comfort and safety.

Frontage – The length of that portion of a property which directly adjoins a highway.

Frontage Road – A roadway used to control access to an arterial, function as an access facility to adjoining property and to maintain circulation of traffic on each side of the arterial.

Full Median Opening – An opening in a restrictive median that allows all turning and through movements to be made.

Functional Area of an Intersection – The area beyond the physical intersection of two roadways that comprises decision and maneuvering distance, plus any required vehicle storage length. It includes the length of road upstream from an oncoming intersection needed by motorists to perceive the intersection and begin maneuvers to negotiate it. The upstream area consists of distance for travel during a perception-reaction time, travel for maneuvering and deceleration, and queue storage. The functional area also includes the length of road downstream from the intersection needed to reduce conflicts between through traffic and vehicles entering and exiting a property.

Highway, Street, or Road – A general term denoting a public way for purposes of vehicular travel, including the entire area within the right of way. (Recommended usage: in urban areas – highway or street, in rural areas - highway or road).

Intersection Sight Distance – The sight distance required within the corners of intersections to safely allow a variety of vehicular access or crossing maneuvers based on the type of traffic control at the intersection.

ITE – Institute of Transportation Engineers (www.ite.org)

Local Roads and Street – All public roads and streets classified below the collector level.

“May” – see “Shall,” “Should,” and “May.”

Median – The portion of a divided highway which separates opposing traffic flow.

Minor Arterial – A roadway that carries a mix of local and through traffic. It links Collectors, and sometimes Local Streets, with Principal Arterials.

MUTCD – Manual on Uniform Traffic Control Devices.

Outparcel – Any lot created from an overall tract wherein the remaining tract is larger than any single lot created and wherein the conditions and locations of access to such lot from a public highway or street may be restricted and/or provided through easements granted by the larger tract holder.

Offset – Related to displacement of a reference survey point; the horizontal distance between two other highway elements located at right angles (transverse) from the direction of travel.

Permit – A legal document in which the Department gives written permission for an encroachment by an applicant.

Permittee – The owner of a property or his or her agent to whom a permit is issued.

Principle Arterial – This functional class of street serves the major portion of through-traffic entering and leaving the urban area and is designed to carry the highest traffic volumes. Included in this class are fully controlled access facilities and partially controlled access facilities.

Right-of-Way – The land secured and reserved by the Department for the construction and maintenance of a highway and its appurtenances.

Road – See *Highway, Street, or Road*.

Roadway – The portion of a highway ordinarily used for vehicular travel, exclusive of the sidewalk, shoulder, or median.

“Shall,” “Should,” and “May”:

Shall – A mandatory condition. Where certain requirements in the design or application are described with the “shall” stipulation, it is mandatory when an installation is made that these requirements be met.

Should – An advisory condition. Where the word “should” is used, it is considered to be advisable usage, recommended but not mandatory.

May – A permissive condition. No requirement for design or application is intended.

Sidewalk – That portion of a street between the curb line, or the lateral line of a roadway, and the adjacent property line or on easements of private property that is paved or improved and intended for use by pedestrians.

Shared-Use Path – A path physically separated from motorized vehicular traffic by an open space or barrier and either within the highway right of way or within an independent right of way. Shared use paths may also be used by pedestrians, skaters, wheelchair users, joggers and other non-motorized users.

Sidepath – A shared use path located immediately adjacent and parallel to a roadway.

Sight Triangle – the area of visibility required on a corner to allow for the safe operation of vehicles, trains, pedestrians, and cyclists in the proximity of intersecting streets, rail lines, sidewalks, and bicycle paths.

Speed – Operating – Operating speed is the highest overall speed at which a driver can travel on a given highway under favorable weather conditions and under prevailing traffic conditions without at any time exceeding the safe speed as determined by the design speed on a section-by-section basis.

Design Speed - Design Speed is a selected speed used to determine various geometric design features of the highway. Generally, the design speed is 5 MPH greater than the posted speed limit of a roadway. See RDM Sections 3.5.1.1 and 3.5.2 for further guidance.

Posted Speed Limit - The posted speed corresponds to the value shown on regulatory signs as specified and described in the Manual on Uniform Traffic Control Devices. The posted speed is typically based on traffic and engineering investigations where statutory requirements do not apply. The selection of a posted speed is based on many factors including but not limited to: the 85th percentile speed, roadside development, curb and gutter, crash data, highway functional class, and median type.

Advisory Speed Limit – Speed advised to motorists for a comfortable speed to navigate a certain situation.

Street – See *Highway, Street, or Road*.

Traffic Control Device – A sign, signal, marking, or other device used to regulate, warn, or guide traffic, placed on, over, or adjacent to a street, highway, pedestrian facility, or shared-use path by authority of a public agency having jurisdiction

TRB – Transportation Research Board.

Two-Way, Left-Turn Lane (TWLTL) – A lane in the median area that extends continuously along a street or highway and is marked to provide a deceleration and storage area, out of the through traffic stream, for vehicles traveling in either direction to use in making left turns.

1E DESIGN EXCEPTIONS AND ACCESS WAIVERS

Recognizing that meeting the minimum criteria may not always be practical, the Department has established a process to identify and evaluate exceptions to geometric design criteria and access guidelines.

1E-1 Design Exceptions

An applicant can request a design exception when a proposed design does not meet AASHTO standards or the applicable criteria as given in the *SCDOT Roadway Design Manual* (SCRDM). The “controlling” design criteria are highway elements that are judged to be the most critical indicators of a highway’s overall safety and serviceability. The designer must seek a design exception or variance when the proposed design does not meet the Department or AASHTO standards for the following criteria:

- Design Speed
- Lane Width
- Shoulder Width
- Horizontal Curve Radius
- Superelevation Rate
- Horizontal Curve Radius
- Stopping Sight Distance (SSD)*
- Maximum Grade
- Vertical Clearance
- Design Loading Structural Capacity

*applies to horizontal alignments and vertical alignments except for sag vertical curves.

The standard form for Design Exception Requests can be downloaded from the SCDOT website at <http://www.scdot.org>.

1E-2 Access Waivers

If an applicant for an encroachment permit seeks a waiver from **access standards** provided in this manual, the request form contained in Appendix C shall be filled out and attached to the permit application. The access waiver shall be under the direct charge of and sealed by a registered South Carolina Professional Engineer with expertise in traffic engineering. The request should provide justification and describe the undue hardship that will be placed on the applicant if a waiver is not granted. The District Permit Engineer (DPE) should coordinate the waiver request with the District Engineering Administrator (DEA). A waiver will only be granted if it is determined that:

1. Denial of the waiver will result in loss of reasonable access to the site.
2. The waiver is reasonably necessary for the convenience and welfare of the public.
3. All reasonable alternatives that meet the access requirements have been evaluated and determined to be infeasible.
4. Reasonable alternative access cannot be provided.
5. The waiver will not result in any violations of pedestrian accessibility in accordance with the ADAAG

If a waiver is approved, the reasons for granting the waiver and any recommendations given by the Department shall be clearly stated and included in the Department files. Restrictions and conditions on the scope of the permit should be imposed as required in order to keep potential safety hazards to a minimum. The encroachment permit may contain specific terms and conditions providing for the expiration of the waiver if in the future the grounds for the waiver no longer exist. An Access Waiver should be included in the Appeal Process Request detailed in Section 2E.

CHAPTER 2 — ENCROACHMENT PERMITS



2A APPLICATION AND REQUIREMENTS

An encroachment permit must be obtained prior to any work on SCDOT right-of-way by an individual or agency other than the SCDOT or agent of the SCDOT. This includes non-routine maintenance of (see [subsection 2D-5](#)) and revisions to any existing encroachment. The applicant or his or her agent will be responsible for all requirements of the permit. Refer to Appendix C, page C-1 “Directions for Completion of Permit Application” and SCDOT Engineering Directive 17 (see Appendix D for instructions on accessing SCDOT’s Engineering Directives portal). The agent of the applicant shall be a person with actual or apparent authority conferred on him or her in writing by the applicant, who has been expressly granted the power to act in the place of and instead of the applicant, and upon whom the SCDOT may rely to do all acts within the scope of the encroachment permit.

2A-1 Application

Applications for encroachment permits must be submitted through SCDOT’s Encroachment Permit Processing System (EPPS).

2A-2 Preliminary Site Plan Concurrence

In cases such as large developments (e.g. industrial parks, shopping centers, large apartment complexes, or mixed use developments) where significant traffic volumes are expected, considerable time and effort often can be saved and the permitting time shortened when the Department and the local jurisdiction are involved in the early stages of development planning. In such cases, the Department recommends a preliminary site development plan and traffic impact study be submitted before the permitting process is begun. Preliminary plans and Traffic Impact Study should be submitted to the District Permit Engineer (DPE).

The Department may provide a document indicating concurrence with the preliminary site development plan. To receive the conceptual concurrence document, submit plans including: structure locations, access placement, internal traffic circulation, drainage requirements, and general grading. This document will expire one year from date of issuance and must be provided with the permit application. This concurrence will not indicate if threshold requirements for a Traffic Impact Study have been met as detailed in Chapter 6. Once submitted, the encroachment permit with all final requirements will be reviewed for approval.

2A-3 Coordination with Local Jurisdictions

In the event of a multi-county / jurisdiction encroachment, the county where the permit is submitted or where the majority of the work will be accomplished will be the lead county and will approve the permit after review by the Department in the other affected county or counties. Resident Maintenance Engineers (RMEs) are responsible for the inspection of work performed in their respective county. The encroachment permit shall reflect all work to be done on the right-of-way regardless of what entity requires the work to be done and copies of the approved permit will be sent to every county involved. The Department shall not issue a permit for an encroachment that meets local standards but violates the provisions of *Access and Roadside Management Standards* (ARMS) Manual. Similarly, the Department's issuing of an encroachment permit does not relieve the applicant of the need to comply with local requirements, even if more restrictive.

2B REVIEW AND APPROVAL

The review and approval of all encroachment permits shall follow the guidelines outlined in SCDOT Engineering Directive 17 and this manual. Early submittal of the Application for Encroachment Permit will allow for proper review and approval prior to completion of design so that any required revisions can be incorporated into the construction plans. The time involved in reviewing applications will depend upon the complexity of the application. The RME / DPE will review and give approval for all applications for permits, unless otherwise provided in writing by the DEA. During the review, the RME / DPE will review the application to determine what, if any impact, the encroachment will have on future widening, relocation, or new-location projects. If necessary, the DPE will coordinate the review with headquarters as shown in Engineering Directive 17. Prior to approval of a permit, the RME / DPE should obtain written recommendations from the appropriate SCDOT offices. When a recommendation is required from another SCDOT office prior to approval of a permit application, the RME / DPE shall promptly forward the information necessary for making the recommendation

to the appropriate office. All permits will be reviewed and returned as soon as practicable. Verbal approval will not be given to permit any work until an encroachment permit for the work has been issued. All extensions, amendments, or additions to existing permits must be in writing. The original application, with supporting documentation and the required recommendations and approval, shall be maintained at the issuing RME's office as required by the department's current records retention schedule.

2C PERFORMANCE BONDS

The Department may require a performance bond or letter of credit before issuance of an encroachment permit. Any such requirement shall be included in the special provisions of the permit, and evidence of the bond shall be attached to the permit. Coordination with the county or local government to determine the extent of their involvement may be necessary. The amount of the bond shall be equal to 1.5 times the estimated construction cost, or \$5,000, whichever is greater. If a bond in this amount has been secured as required by the county or local government, proof of such bond shall be provided with the permit and may satisfy the Department requirement. The purpose of such a bond is to ensure compliance with all terms of the permit by providing, in cases of noncompliance, for any and all damages and costs incurred in collecting damages through legal or other appropriate means. A bond shall be released only when the work described on the permit has been completed to the satisfaction of the Department.

2D CONDITIONS AND LIMITATIONS

2D-1 Traffic Safety and Operational Restraints

Safety, efficient traffic operations, and pedestrian accessibility are important considerations in the review of Application for Encroachment Permits. In some cases, it may be necessary to restrict access because of safety concerns or issues or operational restraints due to geometry, vertical grades, horizontal curves, or other conditions. Access at points within or near acceleration lanes or channelization may be restricted, limited, or prohibited. If operational or safety concerns exist, the application may be forwarded to the Director of Traffic Engineering for review.

2D-2 Land Use Changes and Redevelopment

When there is a change in land use and/or redevelopment, the Department reserves the right to require submission of a new Application for Encroachment Permit. For example, a residential lot may be rezoned to allow for a professional office that will generate commercial traffic. In this case, the Department may require the existing access to be revised to better accommodate the expected traffic even if no significant building renovations are planned. In some cases, the number and/or width of driveways allowed may change depending upon the land use change and the current standards. The Department shall require that driveway locations being retained be rebuilt if the existing driveway violates ADAAAG. The Department shall require that driveways taken out of service be removed as a condition of granting access for a new land use. This provision will also apply to existing accesses when a property is redeveloped with the same general land use.

2D-3 Subdividing Large Parcels

Access to future subdivided parcels shall be considered in the initial Application for Encroachment Permit's review process. The Department will not be obligated to allow direct access for any parcels that may be subdivided from a larger overall development at a later date.

2D-4 Setback

The site layout to which the driveway provides access shall be sufficient to provide for stopping, parking, and maneuvering of vehicles completely off the right-of-way without impacting the adjacent roadway. This may require the development to be sufficiently setback to provide adequate internal traffic circulation. The Department may require additional setback based on future roadway projects as detailed in the RDM. For specific driveway throat length requirements, see Section 3D-4.

2D-5 Maintenance Responsibilities

The owner shall be responsible for the maintenance of driveways and other access points, including any drainage structures, for areas within the rights-of-way of State maintained facilities. An encroachment permit is not required for routine maintenance such as mowing, patching potholes, clearing pipes and ditches, applying seal coating, and repairing minor erosion damage. The Department shall be responsible for the maintenance of permittee-provided crossovers, auxiliary lanes, and right-of-way.

2D-6 Retrofitting by the Department

The Department may require driveway accesses to be modified to conform to these standards. This may require that some driveways be narrowed, widened, restricted, relocated, or removed in order to correct safety and operational problems. Preferably, such actions should be considered during the preconstruction phase. When this is required as part of a road improvement project, it will be done by the Department as part of the construction contract.

2D-7 Private or Commercial Use of Right-of-Way

Pursuant to Sections 57-7-210 and 57-25-10 of the *Code of Laws of South Carolina* (1976 as amended), erecting fruit and vegetable stands on the right-of-way, displaying automobiles for sale on the right-of-way, or any other private or commercial uses of the right-of-way are prohibited. Some exceptions, such as placing banners across the roadway, for which encroachment permits or letters of authorization have been issued in accordance with these standards are allowed. Businesses seeking to operate on sidewalk areas (e.g. sidewalk cafes, etc.) shall demonstrate that sufficient space remains open to pedestrian traffic and that no compromise to accessibility for person with disabilities will result.

2D-8 Transfer of Responsibility and Liability

When, for any reason, there is a change in property ownership, all responsibilities and liabilities of the owner as it pertains to these standards shall become those of the owner's heirs, successors, or assignees upon the legal transfer of ownership.

2D-9 Stormwater Management and Sediment Control Plan

All applications for encroachment permits that includes changes to stormwater runoff or sediment shall include a drainage plan with supporting design computations and other requirements as described in [Chapter 10](#). This plan shall also include measures for controlling erosion on the site and restricting the release of sediment to the highway.

2D-10 Structures On, Over, or Under SCDOT Maintained Roadways

All encroachment applications for placing structures over or under a state maintained roadway shall be submitted a minimum of sixty (60) days prior to the proposed construction date. The DEA shall be the approving authority for permits of this type. Prior to approval of the permit, the DEA should obtain a written recommendation from the Preconstruction Office. All applications for placing structures on, over, or under a state maintained roadway shall include attachments as specified in Chapters 10 and 13 of this manual.

2D-11 Other Restrictions on Access

Owners of private property which is separated from the highway right-of-way by railroad or utility right-of-way must have the railroad or utility company's written approval prior to applying for the encroachment permit.

A controlled-access (full or partial) highway or frontage permits no legal right of access except at such points and in such manner as determined by the jurisdictional authority. On highways with partial control of access, points of access are restricted to driveways on a planned spacing in addition to normally provided interchanges and/or at-grade intersections. Access may be required to be from adjacent roads when direct access to the main highway is restricted or prohibited. This access is the responsibility of the applicant.

The median of a divided highway provides for safer, more efficient traffic movement by reducing accidents involving left-turn access maneuvers as well as head-on collisions. Access to adjacent property is provided by right-in and right-out maneuvers in conjunction with U-turn and crossing maneuvers at paved median crossovers. Crossovers are provided at a planned spacing and at intersections, and additional crossovers are not normally permitted at driveways. See [Section 3D](#) for more details on median crossovers.

2E ENCROACHMENT PERMIT APPEAL PROCESS REQUEST

An Application for Encroachment Permit that is not approved under Section 2B may be appealed to the Deputy Secretary for Engineering within 60 days from date of denial. A letter to the Deputy Secretary for Engineering from the applicant shall be submitted in writing to the RME or DPE. An Access Waiver should be included and note which standard the appeal is requesting to waive.

An Application for Encroachment Permit that is approved with conditions cannot be appealed.

The letter should also include the basis for the appeal such as:

- No other reasonable access can be provided.
- Applicant took all reasonable steps to meet ARMS standard.
- The ARMS standard is not interpreted to fit the site circumstances.
- Undue financial hardship imposed upon applicant.
- Denial is significantly inconsistent with the ARMS standard application within the locality or region.
- Appropriate SCDOT process was not followed.

The RME or DPE will transmit the appeal letter, the permit application number and additional supporting documentation to the Deputy Secretary for Engineering for processing. A Flowchart outlining the Permit Appeal Review Process can be found in Appendix C, page C-7. The Deputy Secretary for Engineering will advise the applicant, RME or DPE the results of his/her ruling on the appeal.

CHAPTER 3 — DRIVEWAYS



3A GENERAL

The AASHTO *A Policy on Geometric Design of Highways and Streets* (Green Book, 2011) states:

Driveways terminals are, in effect, low-volume intersections; thus, their design and location merit special consideration. The operational effects of driveways are directly related to the functional classification of the roadway which they provide access.

Ideally, driveways should not be located within the functional area of a roadway intersection or in the influence area of an adjacent driveway. The functional area extends both upstream and downstream from the physical intersection area and includes the longitudinal limits of auxiliary lanes. Appropriate engineering and safety factors should be considered in conjunction with these standards so that conditions unique to individual driveways are properly taken into account.

3A-1 Driveway Classification

The SCDOT classifies driveways according to the number of trips that will be generated by the land use that the driveway serves to help arrive at the appropriate design. [Table 3-3](#) provides information regarding the classifications including land uses that might be expected to generate the specified volumes. The expected number of trips can be estimated using the latest edition of ITE's *Trip Generation Manual*.

Table 3-3: Driveway Classification


Driveway Classification	Expected Trips	Example Land Use	Design Features
Low Volume	1-20 trips/day 1-5 trips/hour	Residential Drives (1-2 single family homes)	Typically designed with minimum requirements.
Medium Volume	21-600 trips/day 6-60 trips/hour	Small subdivisions with single family homes or apartments, small business or specialty shop	Typically designed with some higher volume features such as radial returns.
High Volume	601-4,000 trips/day 61-400 trips/hour	Convenience store, gas stations, or small shopping center	Typically designed with high volume features such as radial returns and turn lanes.
Major Volume	>4,000 trips/day >400 trips/hour	Large shopping center or regional mall	Designed with high volume features including radial returns, turn lanes, and medians.

3B DRIVEWAY DESIGN ELEMENTS

3B-1 Angle of Intersection

For safety and economy, driveways should generally be at or nearly at right angles to the main road. Driveways intersecting at acute angles need extensive turning roadway areas and tend to limit visibility, particularly for drivers of trucks. When a truck turns on an obtuse angle, the driver has blind areas on the right side of the vehicle. Acute-angle driveways increase the exposure time for the vehicles crossing the main traffic flow. The angle of a one-way and two-way driveway exiting a property shall not be less than 70 degrees and preferably should be 90 degrees as shown in [Figure 3-1](#).


Figure 3-1: Angle of Intersection



3B-2 Width and Radii


Driveway design is a critical component to the transportation system and essential to achieve efficient operations. Entry width, radius, and offset, as shown in Figure 3-2, are the key components to driveway design. The selected design vehicle should maintain a 2-foot clearance from the traveled way, curb line, or median during a right turn maneuver.

Figure 3-2: Critical Dimensions in Driveway Design



One important goal of driveway design is adequately serving the entering and exiting maneuvers without encroachment into an opposing lane. The entry width is the most critical because it has to serve right turning and left turning vehicles and should be sufficient to allow a vehicle to enter without having to slow down nearly to a stop and allow a vehicles to enter and exit simultaneously. Inadequate driveway design creates conflicts that can be detrimental to safety and operations on the mainline (see [Figure 3-3](#)).

Figure 3-3: Inadequate Driveway Design



The width of driveways, exclusive of any shoulder, should be based on various conditions including the type of highway facility, the driveway volumes, the driveway alignment angle, and the turning radii. Driveway radii should be designed to provide safety and ease of vehicle movement for the largest vehicle that will regularly use the driveway. [Table 3-4](#) indicates recommended driveway widths and minimum radii for various types of driveways based on the driveway class. For low to medium volume driveways in curb and gutter or sidewalk sections, drop curb driveways are typically used.

Table 3-4: Driveway Widths and Radii

Driveway Class	Driveway Width (feet)	Minimum Radius Returns (feet)
Low Volume	10 – 24	15
Medium Volume	24 – 40*	30 (40 Recommended)
High Volume	40**	**
Major Volume	**	**

* A 40 ft. driveway is usually marked with two exit lanes of 12 ft. width, with the balance of 16 ft. used for a single, wide entry lane. When a median divider is used, the throat width should be increased to maintain the same lane widths.

**Driveway widths, radii, and lane requirements are determined by a traffic study.

*** For one-way drives, use 14 to 18 feet depending on vehicle usage, width should not encourage two-way movement.

Without guidance, typical drivers will position themselves in the center of the drive, which causes conflicts with entering vehicles. The SCDOT recommends that all two-way driveways be marked to guide the driver to the correct portion of the drive, however; if the width of a driveway is 24 feet or larger pavement markings may be required at the Department's discretion. Driveways 36 feet or larger may require channelization.

Detailed design drawings for driveways with drop curb and for driveways with curb returns are given in *SCDOT Standard Drawings* Numbers 720-405-00, 720-410-00, and 720-415-00. These drawings can be accessed via the SCDOT website at the following address: <https://www.scdot.org/business/standard-drawings.aspx>


3B-3 Approach Grade and Side Slope for Low/Medium Volume Drives

Where a shoulder exists, the profile grade of the approach from the edge of the pavement shall slope at the same rate as the highway shoulder for the full width of the shoulder. As shown in

Figure 3-4, a difference in grade, not to exceed plus or minus 8 percent, shall be maintained from the edge of the shoulder for a minimum distance of 40 feet. Low-volume drives can have an additional grade change at this point not to exceed 14 percent total grade change from the shoulder grade. Also, driveways shall have a maximum side slope ratio of 4:1. These items should be clearly labeled on the driveway profile in the encroachment permit application.

High and major volume drives should be designed in accordance with Chapter 5 of this manual and Chapter 15 of the *SCHDM*.

Figure 3-4: Medium Volume Driveway Approach Grade




D = Maximum 6 percent grade change for low volume driveways. D for all other driveways should be 0 percent.

3B-4 Driveway Throat Lengths

Driveway throat length is the distance from the edge of the traveled way to the first conflict point. Sufficient driveway throat length that provides an uninterrupted area in advance of the initial conflict point is a key component for safe and efficient operation. The SCDOT has the authority and responsibility to require a sufficient throat length (beyond the right-of-way limits) to protect the needs of the adjacent roadway system. Driveways shall be designed to provide adequate queue storage and sufficient maneuvering distance. The larger the volume using the driveway, the more the driveway should be designed like a major roadway intersection. For unsignalized driveways, Figure 3-5 should be used as an estimate of the needed driveway throat length. For signalized driveways, the driveway throat length can be estimated using Figure 3-5, but should be verified through a traffic engineering study. If a development has a gated entrance or a check in station such as that of a military base, the throat length should contain the anticipated peak hour queue.

Figure 3-5: Recommended Driveway Throat Lengths



Signalized Access	Throat Length
4 exiting lanes including right-turn lane	≥350 ft, based on traffic engineering study
3 exiting lanes including right-turn lane	250 ft.
2 exiting lanes including right-turn lane	150 ft.

Unsignalized Access	Throat Length
1 entry lane, 2 exit lanes	50 ft.*
1 entry lane, 1 exit lane	30 ft.*

*In no case should the first access point be located within the radius returns of the driveway.


3B-5 Islands

Traffic islands are used to guide motorists into proper lanes and can be used for pedestrian access. They shall be used when the driveway characteristics or complexity is of such a nature that their use is needed to eliminate conflicts. They should be constructed with a mountable curb and should be offset from the traffic lanes. The minimum size of a raised concrete island is 100 square feet. Island used for pedestrian refuge should be at least 150 square feet. A diagram displaying the design requirement for triangular islands is given in [Figure A-7](#) in [Appendix A](#).

3B-6 Driveway Medians

When a median is used to separate opposing traffic on a driveway, the part of the median within the right-of-way shall have a minimum width of 4 feet and a maximum width of 12 feet. The median nose shall be offset a sufficient distance so that the median does not encroach into the normal shoulder width of the roadway. Landscape plants on the median and within 25 feet of the roadways should be limited to low growing plants not exceeding 2½ feet in height. These plants shall not negatively effect sight distance. When the median width is larger than 4 feet, the nose shall be defined with a 2-foot radius and the control turning radius. See [Figure 3-6](#) below.

Figure 3-6: Driveway Median Design



3B-7 Right-in, Right-out Driveways

Right-in, right-out driveways are necessary in some locations in accordance with Section 3C. A right-in, right-out driveway should incorporate a triangular (pork chop) raised concrete island no smaller than 100 square feet with sides a minimum of 12 feet in length after rounding of the corners. A recommended typical design is shown in [Figure A-7.1](#) in [Appendix A](#). To determine if this design is adequate based on the type of vehicles the drive will serve, refer to [Table 3-3](#), [Table 3-4](#), and [Figure 3-5](#) and adjust the design accordingly.

When a right-in, right-out driveway is implemented on an undivided roadway, the use of a restrictive median in concurrence with the “pork chop” island is preferred; however, adjacent impacts must be evaluated prior to implementing restrictive medians. A 4 foot wide raised concrete median is recommended. However, if a concrete median cannot be provided, consider the use of a Department-approved surface-mounted curbing system with flexible delineator posts as an alternative.

3C DRIVEWAY SPACING AND LOCATION

Driveways should be located to avoid undue interference with or hazard to traffic on the roadway. They should be located where there are no sharp curves or steep grades and where the provisions outlined in the following subsections are met. Driveways should not be located on auxiliary lanes or their tapers.

In the interest of public safety and convenience, the Department may restrict a point of access to a particular location along the frontage. On properties where driveways would not otherwise be clearly defined, a physical barrier such as curbing may be required along the frontage.


Generally, one driveway to a given property will be allowed, situated in a safe location and in accordance with the provisions of this manual. However, additional driveways may be allowed provided the spacing requirements in [Figure 3-7](#) are met. Driveways will be limited to the number needed to provide adequate and reasonable access to a property. Factors such as alignment with opposing driveways and minimum spacing requirements will have a bearing on the number of driveways approved. A residential property with a frontage of less than 50 feet or a commercial property with a frontage of less than 64 feet will be permitted a point of access only upon special consideration by the Department. A property with more than one frontage may have the frontages considered separately.

3C-1 Driveway Spacing

Separating driveways can reduce the potential for conflict and minimize collisions. [Figure 3-7](#) provides the minimum driveway spacing based on the speed and AADT of the adjacent roadway and is measured from near edge to near edge of adjacent driveways as shown in the figure. **Driveways generating more than 50 peak hour trips based on the most recent version of the *ITE Trip Generation Manual* shall use the larger of the two spacing requirements regardless of the adjacent roadway AADT.** Examples of facilities generating greater than 50 peak hour trips are provided in [Appendix F](#). Driveway spacing should reflect the future AADT if a significant change will result from the development as determined by the District Traffic Engineer. High and major volume driveways that act as local streets should align with driveways on the opposite side of the street or should be offset in the same manner as streets as governed by [Chapter 5](#) of this manual and the *SCHDM*. Minimum spacing will be increased if right-turn deceleration lanes are required and shall equal the length of the turning lane and taper plus 50 feet.

A pair of one-way driveways may be substituted only if the internal circulation on the site is compatible with the one-way driveways and wrong-way movements on the driveways are rendered impossible or extremely difficult for motorists. Nowhere shall a distance of less than 40 feet between edges of one-way driveways be permitted. (See [Figure A-1](#) in [Appendix A](#)).

Figure 3-7: Minimum Driveway Spacing



Posted Speed Limit (mph)	Minimum Driveway Spacing (ft) on roadways with AADT ≥ 2000 or Driveways Generating more than 50 Peak Hour Trips	Minimum Driveway Spacing (ft) on roadways with AADT < 2000
30	160	75
35	220	125
40	275	175
45	325	225
≥ 50	400	275


Exceptions to minimum driveway spacing include the following:

- The placement of residential (low volume) driveways. These drives should be placed in a reasonable location to avoid interference with adjacent drives as determined by the Resident Maintenance Engineer (RME).
- The replacement of a driveway to a property that may be lost or disrupted due to a SCDOT project.

In the case of large developments with outparcels, access for outparcels should be provided only internally; however, shared or individual driveways may be permitted provided that **twice the normal spacing** requirements are met. When direct access is approved, it may be limited to right-in, right out. Even when single or shared out-parcel driveways are allowed, additional access from the outparcels to the major development should be provided. Notation of access for outparcels shall be made on the plans for the development. Early coordination with the District Traffic Engineer is encouraged. For sample drawings of out-parcel access, see [Figures A-2 and A-3 in Appendix A](#).

Avoid closely spaced driveways on opposite sides of an undivided roadway or roadway with a two-way left-turn lane (TWLTL) as they can allow undesirable traffic movements and turning conflicts (See [Figure 3-8](#)). The spacing of these drives should also follow the requirements set forth in [Figure 3-7](#).

Figure 3-8: Driveway Connections on Opposite Sides of the Roadway



3C-2 Driveway Radius and Corner Clearances


Corner clearance is the distance between a roadway intersection and the nearest driveway. The purpose of corner clearance is to remove conflicting movements from the functional area of intersections and provide sufficient stacking space for queued vehicles at intersections so that the driveways are not blocked. These requirements may limit or exclude driveways on some corner lot frontages. The minimum corner clearance for full access unsignalized as well as signalized intersections is the standard spacing from [Figure 3-7](#). For right-in, right-out access, use a minimum of 150 feet or the value given in [Figure 3-7](#) if it is less than 150 feet.

Under no circumstances will a driveway connection be permitted within the corner radius of the intersection. In situations where large turn radii exist, the beginning of the radius of a driveway shall be at least 10 feet from the point of tangency of the intersecting roadway's radius.

In locations where left-turn lanes exist, these corner clearance distances may need to be increased as driveways should not be located where it is necessary for left turning vehicles to cross an intersection's left-turn lane. In situations where right turn

lanes exist at an intersection, driveways should not be located where exiting vehicles will enter the right turn lane.


Figure 3-9: Corner Clearances



3C-3 Driveway Radius Offset

With the exception of residential driveways, driveways shall have a minimum radius offset of 5 feet, as measured parallel to the driveway, from the intersection of the right-of-way and property lines (Shown in Figure 3-10). If this is not feasible and the radius encroaches into the adjacent property's frontage located along the roadway, then it will be necessary for the permit applicant to obtain a letter of permission from the adjacent property owner(s).


Figure 3-10: Minimum Radius Offset Requirements



3C-4 Access Placement in Interchange Areas

Adequate spacing and design of access points near freeway interchanges is important to avoid traffic queues and conflicts near interchange ramp terminals. When access points are too close to the ramp termini, heavy weaving volumes, complex traffic signal operations, frequent accidents, and recurrent congestion generally result. In no case shall a point of access be permitted on a freeway or expressway ramp or on a controlled-access highway unless illustrated on the original design plan for the controlled-access highway. The minimum spacing guidelines have been provided in Figure 3-11. Because of the complexity of freeway interchange areas, minimum spacing requirements may need to be increased at the discretion of the District Traffic Engineer (DTE).

Figure 3-11: Minimum Spacing for Freeway Interchange Areas



* Measured from the end of the lane taper if an acceleration lane exists for the off-ramp

** Measured from the beginning of the lane taper if a turn lane for the on-ramp exists

	Distance (ft)	Description
X	750	Distance from the closest interchange ramp to the first full access intersection
Y	325	Distance from the off-ramp to the first right in, right out access point
Z	325	Distance between the last right in, right out access connection and the on-ramp

3C-5 Coordination of Driveways and Sidewalks

Vehicles moving between the roadway and abutting property must pass through the portion of transportation system provided for pedestrians referred to as the sidewalk. Sidewalks should not be permitted for individual properties unless there is a logical and safe terminus. In the design of driveways and entrances/exits through this space where motorists and pedestrians must coexist, the right of way, which SC Code affords the pedestrian, must be basis for the design. In the design of all Low Volume and Medium Volume driveways, the concrete sidewalk, where present, should continue across the driveway with the features shown in the latest version of the *SCDOT Standard Drawings for Road Construction*.

Installation of driveways classified as Medium, High and Major Volume may result in the removal of the existing sidewalk. Where this occurs, care must be taken to minimize severe changes in the longitudinal grade and cross slope of the portion of the driveway within the pedestrian crossing area. The running slopes introduced by the proposed encroachment should not exceed the values provided in the *Americans with Disabilities Act Accessibility Guidelines* (ADAAG). The pedestrian crossing of driveways can be emphasized by the marking of standard six-foot (minimum) width crosswalks as shown in the MUTCD. This is especially important on wider radius-return (private street type) driveways where the crosswalk markings can emphasize to motorists that they must yield the right of way to pedestrians when crossing all driveways across sidewalks (SC Code 56-5-3250).


3C-6 Shared Driveways

Shared driveways requiring mutually executed easements are encouraged and, in some circumstances, may be required by the Department. The requirements of [subsection 3C-3](#) shall not apply to shared driveways.

3C-7 Flag Lots

Access problems often occur as the result of land development techniques that produce lots shaped like flags with long narrow access poles (see [Figure 3-12](#)). Landowners often stack flag lots when dividing a parcel to provide interior lots with direct access to the State Highway System, thereby avoiding the expense of providing a public or private road.

Figure 3-12: Flag Lots and Alternative Access




Access problems frequently occur when drives from stacked flag lots violate driveway spacing standards on the State Highway System. Inadequate spacing between these driveways increases safety hazards from vehicles turning on and off the high-speed roadway. To reduce the potential for access problems and improve safety, the construction of one drive per flag lot should be avoided. Instead, internal flag lots should be served by an internal street or road system that provides access to the State Highway System at one location. This access point should meet the design standards for a street or roadway and not those of a driveway. A residential property with a frontage of less than 50 feet will be permitted a point of access only upon special consideration by the Department.

3D MEDIAN CROSSOVERS

The initial placement of median crossovers along divided highways is determined by engineering design. Divided highways operate at higher levels of safety with a minimum number of median crossovers. Additional crossovers create more conflicts and can lead to higher accident experience and loss of the advantages of the divided highway. They, therefore, are not normally permitted at driveways, and the Department reserves the right to limit access to right-in, right-out. However, when additional median crossovers are warranted, in order to not compromise the operation of existing crossovers or the highway, the spacing of these additional median crossovers should follow a typical pattern for each roadway and shall be limited by the criteria set forth in this section. Applications for median crossovers which are difficult to reconcile shall be forwarded for review to the Director of Traffic Engineering. The design and construction of new median crossovers shall be the responsibility of the permittee and be accomplished at no additional expense to the Department.

Whenever applicable, driveways should align directly with existing median crossover. Those that do not align directly should be located according to the minimum driveway spacing in [Figure 3-7](#) so that conflicts with traffic using the crossover can be avoided. (See [Figure 3-13](#))

Figure 3-13: Driveways with Median Crossovers



3D-1 Requirements

A median crossover may be permitted when an engineering review by the Department indicates that all of the conditions listed below are met.

- The spacing to the nearest crossover is at least 500 feet in urban areas and 1,000 feet in rural areas (centerline to centerline).
- When needed as determined by the Department, a suitable left-turn lane and taper shall be included.
- Sight distance criteria are met (See [Chapter 7](#))
- Significant traffic volumes will be generated.
- The operation of the highway, other accesses, or crossovers will not be adversely affected.
- The maximum grade on the crossover should not exceed 5 percent.

The Department may approve the relocation of a median crossover if the new location meets the above requirements. A median crossover and any associated turn lanes are considered components of the driveway and are to be constructed by the permittee where approved.

3D-2 Design

The length of a median opening shall be based on the control radii accordance with [Figure A-4](#) in [Appendix A](#). For median crossovers provided for driveways, median ends should be of the bullet nose design following criteria established in [Figure A-5](#) in [Appendix A](#). The turning radius of the required design vehicle should determine the length of median crossovers for U-turns. The *SCHDM* offers more in-depth guidance on median design and provides minimum median widths for U-turn movements for various design vehicles. Pavement design shall equal or exceed that of the existing roadway. If auxiliary lanes are required, they shall be designed in accordance with [subsection 5D](#).

3E TEMPORARY DRIVEWAYS

Any driveway which is not for use by the general public and which will be closed after being used for only a limited time may be considered a temporary driveway. The limited time shall be specified on the permit and shall not exceed two years. The requirements for temporary driveways will be the same as for permanent driveways except that a stone surface may be used instead of pavement except where there are sidewalks and wide paved shoulders and different types of pipe are allowed. Temporary driveways shall not block existing drainage features. When the driveway is closed, all materials shall be removed and the site restored to its original condition by the permittee.

3E-1 Logging and Construction Driveways

Driveways to logging operations and construction sites can generally be considered temporary driveways with special consideration being given to ensure that mud and debris are not carried onto the highway.

For construction driveways, an area off the right-of-way for cleaning mud and debris off tires shall be required. Proper warning signs shall be provided, installed, and maintained by the permittee in accordance with the *Manual of Uniform Traffic Control Devices* (MUTCD).

For logging operations, refer to the guidelines attachments generated by the Encroachment Permit Processing System (EPPS) when applying for a temporary logging permit.

CHAPTER 4 – SCHOOL ACCESS DESIGN



4A GENERAL

The School Operations section of SCDOT was established in 1994 in response to the rapid rate at which new school construction was occurring. The section coordinates with the State Department of Education's Office of School Facilities, local school districts, the SCDOT Bike and Pedestrian Engineer, and SCDOT Safe Routes to School Coordinator to assure that roadway and operational improvements are made at the time of new school construction and as renovations are made to existing schools. This process includes the review of all new school site and/or renovation plans from the preliminary design phase through the final construction phase.

This chapter is primarily to be used as a reference for school districts and their architects/engineers doing school site transportation design related to the SCDOT review and approval of Encroachment Permits.

4B ON-SITE STACKING

Schools generate their highest peak traffic volume during morning arrival and afternoon dismissal times. Frequently, these periods coincide with times when traffic volumes are heaviest along roads adjacent to school sites, which further compounds congestion problems experienced at schools. Therefore, it is essential to design internal school driveways in a manner that will provide sufficient on-site stacking length for both vehicles and buses. Vehicle queues that extend into the adjacent roadway disrupt traffic flow, cause erratic maneuvers, and create safety issues with flowing traffic encountering stopped traffic. In some cases, it can lead to children exiting vehicles in the roadway.

On-site stacking capacity for automobile loops varies between 3,000 feet and 5,000 feet or longer based on student population and other factors. On-site stacking capacity will be determined during the preliminary planning and site development phase.

In addition, the presence of an all-day kindergarten program could create additional traffic flow problems in loops intended for parents dropping-off and picking-up elementary students. Therefore, if a large kindergarten student population is anticipated, it is recommended that a separate loop be constructed for this operation. Kindergarten students are more vulnerable, less visible, and require more supervision. A separate area provides for a safer environment. The loop's stacking capacity can be less than what is recommended for elementary students. If a kindergarten loop cannot be constructed, then a separate parking area for these parents should be considered.

4C NUMBER OF SCHOOL DRIVEWAYS

The number of school driveways is important in assuring proper distribution of traffic along a site's frontage. Typically, elementary and middle schools function best when they are served by two separate access drives. One driveway is needed to serve the bus loop, while the other is necessary to serve the parent drop-off/pick-up loop (Note: If a school has an all-day kindergarten program, another access drive may be necessary). High schools should have at least three access drives. The first drive would serve the bus loop, parents would use the second drive for dropping-off and picking-up students, and the third drive would provide access to the student parking areas. For a high school with a large volume of student drivers, additional driveways may be needed for the student parking areas. The recommended number of drives is summarized in [Table 4-6](#).

Consequently, there are circumstances when a new school has only one accessible driveway location. In these instances, it is essential that this access drive be designed to provide multiple lanes entering and exiting the site.

Table 4-6: Recommended Number of Drives


School Type	Number of Driveways
Elementary	2 – 3
Middle	2
High	3 – 4

4D DESIGN CONSIDERATIONS

4D-1 Driveway Spacing

The desirable distance between school driveways is 600 feet or greater as shown in [Figure 4-14](#). This spacing allows for adequate left-turn lane development along the roadway.

Figure 4-14: School Driveway Spacing




4D-2 Driveway Location

Although school driveway access locations are limited to points along a site's frontage where sight lines are optimum, there are other items that also dictate a driveway's location. School driveway locations should comply with the driveway location requirements as given [subsection 3B](#) of this manual. These include radius and corner clearances and radius offsets.

4D-3 Lane Widths and Corner Radii

Driveway corner radii should be designed to safely accommodate the turning movement of the largest vehicle that will regularly use the drive. The minimum corner radius for a school driveway to accommodate an automobile and a school bus is 30 feet and 40 feet, respectively. Also, a school driveway should have an 18-foot wide entrance lane to provide adequate pavement for vehicles entering the drive. This same treatment should be applied to the mainline roadway to accommodate buses exiting the school drive. See [Figure 4-15](#).

Figure 4-15: School Drive Width and Radii



4E ROADWAY WIDENING IMPROVEMENTS

Implementing roadway improvements at and adjacent to new schools is an essential part of the overall site design. Since schools generate high traffic volumes during take-in and dismissal times, they often create heavy congestion at their drives and adjacent intersections (especially when these times coincide with peak traffic demands of non-school traffic along the highway). Additionally, school driveways generate high volumes of turning traffic, which can interfere with the safe and efficient movement of traffic along a roadway. In most cases, the SCDOT recommends construction of turning lanes at new school sites on a statewide basis. Turn lane lengths and taper lengths used should be in accordance with [Figures A-9 and A-10 in Appendix A](#). Widening may also be recommended at adjacent intersections if the traffic introduced by a new school, or school addition, creates a more hazardous condition or is projected to cause a failure in the safe and efficient traffic operation of that intersection. When widening is necessary, the methods presented in [Figures A-9 and A-10 in Appendix A](#) should be used.

4F MISCELLANEOUS RECOMMENDATIONS

- The area where students are dropped-off and picked-up should be located separately from bus loading/unloading operations. This is accomplished by constructing loops and driveways that function separately.
- Automobile and bus loop traffic should circulate in a counterclockwise direction so that student loading and unloading occurs from a vehicle's passenger side next to the curb.
- Parking stalls placed along loop drives should be constructed in an angle type fashion to facilitate a one-way traffic flow pattern and discourage wrong way use.
- School buildings should be set back on a site a sufficient distance from the adjacent roadway to insure safe and adequate on-site storage for the stacking of loading and unloading vehicles.
- Pedestrians and bicyclists shall have a designated safe path between any road and the school building.
- The layout of the bus circulation and parking areas shall be designed to prohibit the backing-up of buses on a school site.
- Parking stalls for a full-size bus shall be a minimum of 15 feet wide. Smaller spaces may be provided for mini-buses and other specifically sized vehicles used to transport students.
- Student parking areas shall be separated from staff/visitor/bus parking and student loading/unloading areas.

THIS PAGE INTENTIONALLY LEFT BLANK

CHAPTER 5 – STREET INTERSECTIONS



5A GENERAL

Street intersections whether commercial or residential, public or private, shall be designed and constructed in conformance with the current editions of the *SCDOT Highway Design Manual* (SCHDM), the American Association of State Highway and Transportation Officials' *A Policy on Geometric Design of Highways and Streets* (AASHTO Green Book), AASHTO's *Guide for the Planning Design, and Operation of Pedestrian Facilities*, and AASHTO's *Guide for the Development of Bicycle Facilities*, the ADAAG, and the Department's *Standard Specifications for Highway Construction*. All intersections should be as simple as practical by minimizing confusion and demands on drivers to recognize and rapidly react to complex situations.

5B SPACING REQUIREMENTS


5B-1 Unsignalized Intersection Spacing

If practical, avoid short distances between intersections because they tend to impede traffic operations. For example, if two intersections are close together and require signalization, they may need to be considered as one intersection for signalization purposes. To operate safely, each leg of the intersection may require a separate green phase, thereby greatly reducing the capacity for both intersections. Short spacing between intersections may hinder or even restrict effective left-turn movements. Where practical, realign the roadways to form a single intersection.

To operate efficiently, urban intersections should be a minimum of 500 feet apart. For rural areas, provide a minimum spacing of $\frac{1}{4}$ mile (1320 feet) and, desirably, $\frac{1}{2}$ mile (2640 feet) apart. Generally, treat signalized and unsignalized intersections the same. Because of changing traffic patterns, development and crash concerns, unsignalized intersections may be converted to signalized intersections in the future. Conduct a capacity analysis to determine if free-flow can be obtained between the intersections.

In addition, avoid short gaps or offsets between opposing “T” intersections. Drivers tend to encroach into the opposing lanes (corner cutting) so that they can make their turning maneuvers in one movement. In general, all new intersections should preferably be at least 500 feet apart. However, intersections with a right hand offset should have a minimum spacing of 700 feet to properly develop left-turn lanes. (See Figure 5-16)


Figure 5-16: Street Alignment



5B-2 Signalized Intersection Spacing

Closely spaced traffic signals result in frequent vehicle stops and starts, unnecessary delay, and increased fuel consumption and emissions. Long and uniform signal spacing allow signal timing plans to efficiently accommodate varying traffic conditions including congested peak hours. Figure 5-17 shows the spacing requirements for signalized intersections. Less than minimum traffic signal spacing is only permitted if there is no reasonable alternative, and a weave and queue analysis show adequate spacing.

Figure 5-17: Traffic Signal Spacing



Functional Class	Traffic Signal Spacing (ft)
Major Arterial	2,640
Minor Arterial	1,320
Collector	1,320
Local	1,320

5C DESIGN CONSIDERATIONS

5C-1 Design Vehicles

Right-of-way for new streets should provide triangular areas sufficient to accommodate the intersection turn radii and provide for adequate intersection sight distance. The minimum radius for street intersections should comply with the recommended design vehicle based on the functional classification of the intersection's highway that the vehicle is turning from and onto. These design vehicles are listed in Table 5-7.

Table 5-7: Turn Type Design Vehicles

For Turn Made		Design Vehicle
From	Onto	
Freeway Ramp	Other Facilities	WB-62
Other Facilities	Freeway Ramp	WB-62
Arterial	Arterial	WB-62
	Collector	WB-62
	Local	WB-62
	Local (Residential)	SU/ S-BUS*
Collector	Arterial	WB-62
	Collector	WB-62
	Local	WB-62
	Local (Residential)	SU/ S-BUS*
Local	Arterial	WB-62
	Collector	WB-62
	Local	SU/ S-BUS*
	Local (Residential)	SU/ S-BUS
Local (Residential)	Arterial	SU/ S-BUS*
	Collector	SU/ S-BUS*
	Local	SU/ S-BUS
	Local (Residential)	SU/ S-BUS

* With encroachment, a WB-50 vehicle should physically be able to make the turn.


5C-2 Angle of Intersection

Highways should intersect at or nearly at right angles. Intersections at acute angles are undesirable because they:

- Restrict vehicular turning movements,
- Require additional pavement and channelization for large trucks,
- Increase the exposure time for vehicles and pedestrians crossing the main traffic flow, and
- Restrict the crossroad sight distance.


Preferably, the angle of intersection should be within 20 degrees of the perpendicular as shown in Figure 5-18. This amount of skew can often be tolerated because the impact on sight lines and turning movements is not significant. Where turning movements are significantly unbalanced, the intersections may be angled to favor the predominant movement.

Figure 5-18: Roadway Angle of Intersection



The minimum distance between the point of tangency (PT) of a curve and the beginning of a radius at the intersection is 25 feet, as shown in [Figure 5-19](#).

Figure 5-19: Point of Tangency Offset



5C-3 Offset Intersection Legs

In general, four-leg cross type intersections should be designed so that opposing approaches line up with each other (i.e., there is no offset between opposing approaches). However, this is not always practical. Figure 5-20 presents a diagram of an intersection with an offset between opposing approaches. Because of possible conflicts with overlapping turning vehicles, offset intersections should only be allowed to remain on low-volume approaches. The following criteria will apply for offset intersection approaches:

1. **Maximum Offset.** The maximum offset is determined from the application of a taper equal to V:1 applied to the intersection width, where V is the design speed in miles per hour; see Figure 5-20. V is selected as follows:


- V = 20 miles per hour for stop-controlled approaches.
- V = the roadway design speed for the free-flowing approaches at a stop-controlled intersection.
- V = the roadway design speed for the offset approaches at a signalized intersection.

2. **Turning Conflicts.** Evaluate the entire intersection for conflicts that may result from turning vehicles at an offset intersection. For example, offsets where the “jog” is to the left may result in significant interference between simultaneous left turning vehicles.

3. **Evaluation Factors.** In addition to potential vehicular conflicts, the designer should evaluate the following at existing or proposed offset intersections:

- Through and turning volumes,
- Type of traffic control,
- Impact on all turning maneuvers,
- Intersection geometrics (e.g., sight distance, curb/pavement edge radii), and
- Crash history at existing intersections.

Figure 5-20: Offset Intersection Legs



Design Speed (mph)	Allowable Offset (ft)	
	Crossing a 2-Lane Street*	Crossing a 5-Lane Street**
20***	3.7	7.2
25	3	5.7
30	2.5	4.8
35	2.1	4.1
40	1.9	3.6
45	1.6	3.2
50	1.5	2.9
55	1.3	2.6
60	1.2	2.4

Notes:

*Assumes a 25 ft. corner radius and 2-12 ft. lanes

**Assumes a 40 ft. corner radius, 4-12 ft. lanes, and a 15 ft. TWLTL

***Use the 20 mph design speed for all stopped approaches.

5C-4 Approach Grade and Side Slope

On streets or higher-volume driveways or when curb and gutter are present, the approach profile should be as flat as practical but consideration must be given to obtaining positive drainage. Intersection areas or landing areas in the range of 75 to 100 feet should be established for minor roads as shown in [Figure A-6](#) in [Appendix A](#). The landing area is the portion of intersecting highways, local roads, and public and private approaches that are used for the storage of stopped vehicles. This landing area should provide for minimum grade changes to provide adequate sight distance and minimize acceleration time for vehicles using the crossroads. Desirably, the landing area will slope away from the intersection on a gradient not to exceed 3 percent, downward or upward. However, an upward sloping landing area should be avoided if practical, because this will require the stopped motorist to apply brakes while waiting to cross or turn. Where the use of grades less than 3 percent may be cost prohibitive, the designer may, with corresponding adjustments to other intersection design elements, use an approach gradient up to 5 percent. See Chapter 15 of the *SCHDM* for more in-depth design criteria.

5D AUXILIARY LANES

On roadways with substantial traffic volumes and/or higher speeds, lanes for deceleration, or turn storage may be required by the Department or as the result of a traffic impact study. The design and construction of auxiliary lanes, as well as the acquisition of additional right-of-way where necessary, shall be the responsibility of the permittee and shall be accomplished at no expense to the Department.

When adding left-turn lanes, the entire roadway at the site shall be resurfaced to prevent differential settlement, to eliminate undesirable pavement contrast, and to provide proper pavement markings. When the through travel way shifts alignment to a new location, the entire roadway within the limits of the shift shall be resurfaced. However, when a right turn lane only is added, resurfacing of the entire area may not be required. In addition, the road should be brought up to the latest standards requiring the following:

- Minimum 2-foot paved shoulders, matching the paved shoulder width currently provided on the road, or the width called for in state or local bicycle/pedestrian plans.
- 10 foot shoulders on arterials, and 6-8 foot shoulders on collectors, and 4-6 foot shoulders local roads based on guidance in the *SCHDM*.
- All projects in which turn lanes are added shall have cross sections submitted with the permit application showing the pavement, shoulder width, cut and fill ditches, and the right-of-way. If additional right-of-way is needed, this shall be indicated on the plans, and the permittee shall be responsible for acquisition at no cost to the Department. Additional right-of-way shall be quit claimed to the Department for maintenance purposes and shall take place prior to approval of the permit.

5D-1 Right-turn Storage Lanes

The use of right-turn lanes at intersections can significantly improve operations. Consider exclusive right-turn lanes:

- At the free-flowing leg of any unsignalized intersection on a two-lane urban or rural highway;
- At the free-flowing leg of any unsignalized intersection on a high-speed, four-lane urban or rural highway;
- At any intersection where a capacity analysis determines a right-turn lane is necessary to meet the level-of-service criteria;
- As a general rule, at any signalized intersection where the projected right-turning volume is greater than 300 vehicles per hour and where there is greater than 300 vehicles per hour per lane on the mainline;
- For uniformity of intersection design along the highway if other intersections have right-turn lanes;
- At railroad crossings where the railroad is parallel to the facility and is located close to the intersection and where a right-turn lane would be desirable to store queued vehicles avoiding interference with the movement of through traffic; or
- At any intersection where the crash experience, existing traffic operations, sight distance restrictions (e.g., intersection beyond a crest vertical curve), or engineering judgment indicates a significant conflict related to right-turning vehicles.

5D-2 Left-Turn Storage Lanes

The accommodation of left turns is often the critical factor in proper intersection design. Left-turn lanes can significantly improve both the level of service and intersection safety. Always use an exclusive left-turn lane at all intersections with public roads on divided urban and rural highways with a median wide enough to accommodate a left-turn lane, regardless of traffic volumes. Consider using an exclusive left-turn lane for the following:

- At any signalized intersection. At locations where you have 300 vehicles per hour, consider a traffic study to determine if dual left-turn lanes are required;
- At all entrances to major residential, commercial and industrial developments;
- At all median crossovers;
- For uniformity of intersection design along the highway if other intersections have left-turn lanes (i.e., to satisfy driver expectancy); or
- At any intersection where the crash experience, traffic operations, sight distance restrictions (e.g., intersection beyond a crest vertical curve), or engineering judgment indicates a significant conflict related to left-turning vehicles.

5D-3 Multiple-Turn Lanes

At signalized intersections with high-turning volumes, dual left- and/or right-turn lanes may be considered. However, multiple turn lanes may cause problems with right of way, lane alignment, crossing pedestrians and lane confusion for approaching drivers. Consider dual right- and left-turn lanes where:

- Based on the capacity analysis, the necessary time for a protected left-turn phase becomes unattainable to meet the level-of-service criteria (average delay per vehicle); and/or
- There is insufficient space to provide the calculated length of a single-turn lane because of site restrictions (e.g., closely spaced intersections).

Dual right-turn lanes do not work as well as dual left-turn lanes because of the more restrictive space available for two-abreast right turns. If practical, the designer should find an alternative means to accommodate the high number of right-turning vehicles.

Triple left-turn lanes require more specific justification and detail in the design than dual left-turn lanes. Because triple left-turn lanes are not common in South Carolina, early coordination with the Traffic Engineering division is recommended.

5D-4 Auxiliary Lane Design

The length of a right-turn and left-turn lane at an intersection should allow for both safe vehicular deceleration and storage of turning vehicles outside of the through lanes. The length of auxiliary lanes will be determined by a combination of its taper length (Figure 5-21) and storage length (Table 5-8 and Table 5-9). When widening is necessary to accommodate a turn lane, the methods presented in Figure A-8 should be used.

Table 5-8: Right-Turn Lane Storage Lengths


Turning Volume (vph)	Percent of Trucks in Turning Volume				
	0% to 10%	20%	40%	60%	100%
50	Minimum length of 100 ft				
100					
150					
200	150 ft	175 ft	225 ft	225 ft	250 ft
250	200 ft	225 ft	275 ft	275 ft	325 ft
300	250 ft	275 ft	325 ft	350 ft	400 ft
350	300 ft	325 ft	375 ft	425 ft	475 ft
400	350 ft	375 ft	425 ft	500 ft	550 ft

Table 5-9: Left-Turn Lane Storage Lengths

Turning Volume (vph)	Percent of Trucks in Turning Volume				
	0% to 10%	20%	40%	60%	100%
50	Minimum length of 150 ft. in Urban Areas Minimum length of 200 ft. in Rural Areas				
100					
150			175 ft	175 ft	175 ft
200		175 ft	225 ft	225 ft	250 ft
250	200 ft	225 ft	275 ft	275 ft	325 ft
300	250 ft	275 ft	325 ft	350 ft	400 ft
350	300 ft	325 ft	375 ft	425 ft	475 ft
400	350 ft	375 ft	425 ft	500 ft	550 ft

NOTES: 1) SCDOT Traffic Engineering should review the design to determine if longer turn lane lengths are required. 2) Consider providing dual turn lanes if volumes are greater than 300 vph.

Figure 5-21: Typical Auxiliary Lane Taper Lengths



REVERSE CURVE TAPER				STRAIGHT TAPER		
Design Speed (mph)	Radius (ft)	Auxiliary Lane Widths		Design Speed (mph)	Auxiliary Lane Widths	
		W=11 ft	W=12 ft		W=11 ft	W=12 ft
$V \leq 30$	300	115	120	$V \leq 30$	115	120
31 - 40	480	145	152	31 - 40	145	150
41 - 50	670	171	179	41 - 50	170	180
$51 \leq V$	840	192	201	$51 \leq V$	200	200

Notes:

- 1) Create taper equivalent reverse curves.
- 2) Taper distance is approximately based on tangent alignment
- 3) W=width of turning lane
- 4) Where through road is on a curve, develop a uniform offset taper from the curved mainline.

In-depth design criteria for auxiliary lanes can be found in Section 15.5 of the SCHDM.


5D-5 Offset Left-Turn Lanes

On medians wider than 17 feet, it is desirable to align the left-turn lane so that it will reduce the width of the median nose to 1 to 6 feet. This alignment will place the vehicle waiting to make the turn as far to the left as practical, maximize the offset between the opposing left-turn lanes, and provide improved visibility to the opposing through traffic. The advantages of offsetting the left-turn lanes are:

- better visibility of opposing through traffic and decreased probability of a conflict between opposing left-turn movements within the intersection; and
- more left-turn vehicles can be served in a given period of time, especially at signalized intersections.

Offset designs may be either the parallel or taper design; see [Figure 5-22](#). The parallel design may be used at signalized and unsignalized intersections. However, the taper design is primarily only used at signalized intersections. Offset turn left-lanes should be separated from the adjacent through traveled way by painted or raised channelization.

Figure 5-22: Offset Left-turn Lanes



5E PARKING CONSIDERATIONS

Facilities and accommodations for parking on the State Highway System's right-of-way shall be permitted only when installed by local governments who maintain the responsibility for enforcing parking regulations within their jurisdiction. At no time shall any on-street parking be allowed on the right-of-way that is not in accordance with Section 56-5-2550 of the *Code of Laws of South Carolina* (1976 as amended). Only parallel parking is permitted on the State Highway System's right-of-way, unless the Department specifically permits otherwise. Parking other than parallel parking increases the accident potential due to vehicles backing into the roadway while under the restraint of limited sight distances created by vehicles in adjacent spaces. Standard angle and reverse angle parking, therefore, shall be permitted only on minor streets where there is sufficient width to allow maneuvering without interfering with the free movement of traffic. At no time shall 90° parking be permitted. Internal parking of a development or improvement will not be allowed to extend onto the State Highway System's rights-of-way.

Figure A-11 in Appendix A provides the layout criteria for parking stalls for various configurations. The figure also indicates the number of stalls which can be provided for each parking configuration for a given curb length. For angle parking, the roadway width allocated to parking will be the maneuvering space as shown in the figure exclusive of the through travel lane. The maneuvering space distance is that width needed by a parked vehicle to back onto the street when exiting the stall. However, in restricted areas a portion of the maneuvering dimension may be required for the through travel lane, thereby reducing the roadway width allocated to angle parking. The design must meet the accessibility design criteria discussed in Section 17.1 of the SCHDM.

For most sites, a parking occupancy turnover study and a sight distance evaluation must be conducted. In addition to State and local regulations, the following should be considered when locating parking spaces:

- A) Prohibit parking within 20 feet of any crosswalk.
- B) Prohibit parking at least 10 feet from the beginning of the curb radius at mid-block approaches (e.g., alleys, driveways).
- C) Prohibit parking within 50 feet of the nearest rail of a railroad/highway crossing.
- D) Prohibit parking from areas designated by local traffic and enforcement regulations (e.g., near school zones, fire hydrants). See local ordinances for additional information on parking restrictions.
- E) Prohibit parking near bus stops
- F) Prohibit parking within 30 feet on the approach leg to any intersection with flashing beacon, stop sign, or traffic signal.
- G) Prohibit parking on bridges or within a highway tunnel.
- H) Eliminate parking across from a T- intersection.
- I) Prohibit parking in the intersection sight triangle.

CHAPTER 6 – TRAFFIC IMPACT STUDIES




Image taken from Google Earth©

6A GENERAL

A traffic impact study (TIS) is a specialized engineering study that evaluates the effects of a proposed development on traffic conditions in an area. These studies help developers and government agencies identify the potential traffic impacts of a development and means to mitigate these impacts both on- and off-site. The District Traffic Engineer (DTE) will evaluate the study, therefore early contact with the Department by the developer is recommended. A TIS will be required for large developments such as major shopping centers, large planned-unit developments, industrial complexes, and other projects that would generate 100 or more trips during the peak hour of the traffic generator or the peak hour of the adjacent street. A change or expansion at an existing site that results in an expected increase of 100 or more trips or if the DTE determines that the proposed development will have a significant impact on the operations at the proposed access points even if the site generates fewer than 100 trips will also require a TIS. The estimate of the number of trips for the sites will be based on the latest edition of the Institute of Transportation Engineers (ITE) *Trip Generation Manual*. In [Table 6-10](#) are examples of land use size thresholds that might be expected to generate 100 peak hour trips that may be used to determine whether a study will be required (*based on 7th Edition of the ITE Trip Generation Manual*). In some instances, thresholds for rural areas and small cities may need to be lower than for urban areas.

Table 6-10: Guidelines for Determining the Need for an Impact Study

Land Use	100 Peak Hour Trips*
Single Family Home	90 units
Apartments	150 units
Condominiums/Townhouses	190 units
Mobile Home Park	170 units
Shopping Center – Gross Leasable Area (GLA)	6,000 sq. ft.
Fast Food Restaurant With drive-in – Gross Floor Area (GFA)	3,000 sq. ft.
Gas Station with Convenience Store	7 fueling positions
Banks w/drive-in (GFA)	2,000 sq. ft.
General Office	67,000 sq. ft.
Medical/Dental Office	29,000 sq. ft.
Research & Development	71,000 sq. ft.
Light Industrial / Warehousing (GFA)	185,000 sq. ft.
Manufacturing Plant (GFA)	144,000 sq. ft.

*Rates/Equations used to calculate above thresholds are for the P.M. Peak hour of the adjacent street.

A TIS shall be under the direct charge of and sealed by a registered South Carolina Professional Engineer with expertise in traffic engineering. An impact study shall analyze traffic conditions for the existing year conditions, build-out year background “no build” conditions, and build-out year “build” conditions. The study will be used to assess the need for changes in traffic control devices and roadway improvements necessary to accommodate the new development traffic. The study must also justify the proposed access plan and demonstrate the effects of the development on public roadways. The developer of a site will be responsible for making roadway improvements and installing traffic control devices that may be necessary due to the impacts of the new development. These include impacts through the influence area of the development and not limited to those in front of the development. The Department may also require road improvements by the developer without a TIS.

6B STUDY REQUIREMENTS

The DTE should be contacted before a TIS is begun to discuss the requirements and determine the scope of the study. The method used for analysis should be based on the 2006 edition of ITE's "Transportation Impact Analysis for Site Development." In general, the SCDOT requires the following information be contained in a TIS:

1. **Study Area** - Description of the study area including surrounding land uses and expected development in the vicinity that would influence future traffic conditions. The study area shall include the intersections immediately adjacent to the development and those identified by the DTE. These intersections may include those not immediately adjacent to the development if significant site traffic could be expected to impact the intersection. If intersections impacted by the development are within a coordinated traffic signal system, then the entire system shall be analyzed. If the signal system is very large, a portion of the system may be analyzed if approved by the DTE. A study area site map showing the site location is required.
2. **Proposed Land Use** - Description of the current and proposed land use including characteristics such as the number and type of dwelling units, gross and leasable floor area, number of employees, accompanied with a complete project site plan (with buildings identified as to proposed use). A schedule for construction of the development and proposed development stages should also be included.
3. **Existing Conditions** - Description of existing traffic conditions including existing peak-hour traffic volumes adjacent to the site and levels of service for intersections in the vicinity, which are expected to be impacted. Existing traffic signal timings should be used. In general, AM and PM peak hour counts should be used, but on occasion other peak periods may need to be counted to determine the effects of school or special event traffic. In some cases, pedestrian counts will be required. Data should be adjusted for daily and seasonal variations. Existing counts may be used if taken within 12 months of the submittal of the TIS. In most cases, counts should be taken when school is in session unless otherwise determined by the DTE. Other information that may be required as determined by the DTE may include, but not limited to, crash data, stopping sight distances, and 50th and 85th percentile speeds.
4. **Future Background Growth** - Estimate of future background traffic growth. If the planned completion date for the project or the last phase of the project is beyond 1 year of the study an estimate of background traffic growth for the adjacent street network shall be made and included in the analysis. In general, the growth factor will be determined from local or statewide data. Also included, is the state, local, or private transportation improvement projects in the project study area that will be underway in the build-out year and traffic that is generated by other proposed developments in the study area.
5. **Estimate of trip generation** - The site forecasted trips should be based on the most recent edition of the *ITE Trip Generation Manual*. A table should be provided in the report outlining the categories and quantities of land uses, with the corresponding trip generation rates or equations, and the resulting number of trips. The reason for using the rate or equation should be documented. For large developments that will have multiple phases, the table should be divided based on the trip generation for each phase. Any reductions due to internal trip

- capture and pass-by trips, transit use, and transportation demand management should be justified and documented. All trip generation and trip reduction calculations and supporting documentation shall be included in the report appendix.
6. **Trip Distribution and Traffic Assignment** - The distribution (inbound versus outbound, left turn versus right turn) of the estimated trip generation to the adjacent street network and nearby intersections shall be included in the report and the basis should be explained. The distribution percentages with the corresponding volumes should be provided in a graphical format.
 7. **Analysis and Estimate of Impact** - A capacity analysis should be performed at each of the study intersections and access intersection locations (signalized and unsignalized) in the vicinity of the development. Intersection analysis shall include LOS determination for all approaches and movements. The levels of service will be based on the procedures in the latest edition of Transportation Research Board's *Highway Capacity Manual*. Coordination analysis will be required for the signal systems or portion of the signal systems analyzed.
 8. **Access Management Standards** - The report shall include a map and description of the proposed access including any sight distance limitations, adjacent driveways and intersections, and a demonstration that the number of driveways proposed is the fewest necessary and that they provide safe and efficient traffic operations.
 9. **Traffic signalization:** If a traffic signal is being proposed, a signal warrant analysis shall be included in the study. The approval of a traffic signal on projected volumes may be deferred until volumes meet warrants given in the MUTCD. The developer should make any laneage improvements during construction so that if in the horizon year a signal is warranted, one may be installed with little impact to the intersection.
 10. **Mitigation and alternatives** - The traffic impact study should include proposed improvements or access management techniques that will mitigate any significant changes in the levels of service. The DTE will be responsible for final determination of mitigation improvements required to be constructed by the applicant.

The applicant shall provide all supporting information to the department. Electronic copies of supporting data may be submitted along with printed documents and could expedite the review process. This information may include traffic volumes, capacity analysis, and signal warrant analysis files from software packages. The electronic files that are submitted should be named to identify the contents.

When conditions indicate that there is no need to prepare a TIS, the developer may submit a waiver request to the DTE explaining the purpose of the waiver and providing the necessary supporting information.

The following checklist is used by the SCDOT in the review process and can aid in the preparation of a traffic impact study. This checklist shows the minimum requirements for a traffic impact study to be complete and does not certify or guarantee adequacy or approval. The DTE may require additional requirements during the review process, or during the initial meeting with the developer. Incomplete traffic studies will not be reviewed and will be immediately returned to the permittee.

Traffic Impact Study Technical Completeness Checklist**Analyst Requirements**

☐ Yes ☐ No South Carolina PE Stamp and Signature

☐ Yes ☐ No **Introduction and Executive Summary**

Existing Conditions

☐ Yes ☐ No Study Area Descriptions and Roadway Classifications
☐ Yes ☐ No Analysis Period Correct (AM, Mid-day, PM and/or Saturday)
☐ Yes ☐ No Existing Traffic Operations (LOS, Volumes, Speed Limits, Crash Data, Etc.)
☐ Yes ☐ No Other projected transportation improvements in the study area

Impacts

☐ Yes ☐ No Trip Generation Summary (ITE Trip Generation Manual, latest edition)
☐ Yes ☐ No Trip Distribution and traffic assignment (assumptions justified)
☐ Yes ☐ No LOS Analysis: Background traffic growth and site build out
 (Identify existing and background LOS deficiencies)
☐ Yes ☐ No Analysis of Sight Distance at Access Points

Mitigation

☐ Yes ☐ No Identify need for Turn Lanes, Capacity and Storage Length
☐ Yes ☐ No Identify need for Signalization
☐ Yes ☐ No Identify Measures to Mitigate LOS deficiencies

Figures

☐ Yes ☐ No Vicinity Map
☐ Yes ☐ No Site Plan and Proposed Land Use
☐ Yes ☐ No Existing Peak hour volumes (counts conducted within the last 12 months)
☐ Yes ☐ No Projected Background Peak Hour Volumes
☐ Yes ☐ No Trip Distribution % Including Added Project Peak Hour Volumes
☐ Yes ☐ No Project Build-Out Volumes
☐ Yes ☐ No Existing and Recommended Lane Configurations
☐ Yes ☐ No Intersection LOS (existing, background, build, mitigated) (Figure or Table or both)

Tables

☐ Yes ☐ No Trip Generation
☐ Yes ☐ No Intersection LOS (existing, background, build, mitigated) (Figure or Table or both)

Other

☐ Yes ☐ No Technical Appendix (e.g. HCM and Synchro Analysis Reports, Trip Generation and Trip
 Reduction Calculations, Signal Warrant Analysis, and etc.)
☐ Yes ☐ No Copies of any Reference Material

THIS PAGE INTENTIONALLY LEFT BLANK

CHAPTER 7 – SIGHT DISTANCE



Source: Chapter Adapted from Section 10.4 of the SCDOT Highway Design Manual (SCHDM)

7A GENERAL

For an at-grade intersection to operate properly, adequate sight distance should be available. The designer should provide sufficient sight distance for a driver to perceive potential conflicts and to perform the actions needed to negotiate the intersection safely. The additional costs and impacts of removing sight obstructions are often justified. In general, intersection sight distance (ISD) refers to the corner sight distance available in intersection quadrants that allows a driver approaching an intersection to observe the actions of vehicles on the crossing leg(s). ISD evaluations involve establishing the needed sight triangle in each quadrant by determining the legs of the triangle on the two intersecting roadways. The necessary clear sight triangle is based on the type of traffic control at the intersection and on the design speeds of the two roadways. The types of traffic control and maneuvers are as follows:


- Case A – Intersections with no control (not used by SCDOT),
- Case B – Intersections with stop control on the minor road:
 - Case B1 – Left-turn from the minor road,
 - Case B2 – Right-turn from the minor road,
 - Case B3 – Crossing maneuver from the minor road
- Case C – Intersections with yield control on the minor road:
 - Case C1 – Crossing maneuver from the minor road (not used by SCDOT),
 - Case C2 – Left or right-turn from the minor road,
- Case D – Intersections with traffic signal control,
- Case E – Intersections with all-way stop control, and
- Case F – Left turns from the major road.

For guidance on these cases, see the AASHTO *A Policy on Geometric Design of Highways and Streets* or NCHRP Report 383, *Intersection Sight Distance*.

7B BASIC CRITERIA

The Department uses gap acceptance as the conceptual basis for its ISD criteria at stop-controlled and traffic signal controlled intersections. The intersection sight distance is obtained by providing clear sight triangles both to the right and left as shown in Figure 7-23.

Figure 7-23: Sight Triangles



Note: The turning radius can change the 15-foot eye location. Adjust this 15-foot dimension using a turning template, if needed.

The lengths of legs of these sight triangles are determined as follows:

- 1) Minor Road. The length of leg along the minor road is based on two parts. The first is the location of the driver's eye on the minor road. This is typically assumed to be 15 feet from the edge of traveled way for the major road and in the center of the lane on the minor road; see [Figure 7-23](#). The second part is based on the distance to the center of the vehicle on the major road. For vehicles approaching from the left, this is assumed to be the center of the closest travel lane from the left. For vehicles approaching from the right, this is assumed to be the center of the closest travel lane for vehicles approaching from the right; see [Figure 7-23](#).
- 2) Major Road. The length of the sight triangle leg or ISD along the major road is determined using the following equation:

$$\text{ISD} = 1.47 \times V_{\text{major}} \times t_g \quad \text{Equation 7.1}$$

Where:

ISD	= length of sight triangle leg along major road (ft)
V_{major}	= design speed of major road (mph)
t_g	= gap acceptance time for entering the major road (sec)

The gap acceptance time (t_g) varies according to the design vehicle, the maneuver type, the grade on the minor road approach, the number of lanes on the major roadway, the type of operation, and the intersection skew.

- 3) Height of Eye/Object. The height of eye for passenger cars is assumed to be 3.5 feet above the surface of the minor road. The height of object (approaching vehicle on the major road) is also assumed to be 3.5 feet. An object height of 3.5 feet assumes that a sufficient portion of the oncoming vehicle must be visible to identify it as an object of concern by the minor road driver. If there are a sufficient number of trucks to warrant their consideration, assume an eye height of 7.6 feet for a tractor/semitrailer and 6 feet for single-unit trucks and buses. If a truck is the assumed entering vehicle, the object height will still be 3.5 feet for the passenger car on the major road.

Within this clear sight triangle, if practical, the objective is to remove, lower any object, trim lower tree branches, etc., that obstruct the driver's view. These objects may include buildings, parked or turning vehicles, trees, hedges, tall crops, unmowed grass, fences, retaining walls and the actual ground line. In addition, where a crossroad intersects the major road near a bridge on a crest vertical curve, items such as bridge parapets, piers, abutments, guardrail or the crest vertical curve itself may restrict the clear sight triangle.

7B-1 Case B – Intersections with Stop Control on the Minor Road

Where traffic on the minor road of an intersection is controlled by stop signs, the driver of the vehicle on the minor road should have sufficient sight distance for a safe departure from the stopped position assuming that the approaching vehicle comes into view as the stopped vehicle begins its departure. At a four-leg intersection, the designer should also check the sight distance across the intersection.

7B-1.1 Case B1– Left-Turn From the Minor Road

To determine the ISD for vehicles turning left onto the major road, the designer should use [Equation 7.1](#) and the gap acceptance times (t_g) presented in [Table 7-11](#) for vehicles approaching from the left and right.

[Table 7-12](#) and [Table 7-13](#), which solve [Equation 7.1](#), provide the ISD values for left-turning design vehicles onto a two-lane level facility and a four-lane with a two-way left-turn lane (TWLTL) level facility, respectively. The designer should also consider the following:

- 1) **Multilane Facilities.** For multilane facilities, the gap acceptance times presented in [Table 7-11](#) should be adjusted (i.e., add 0.5 second for passenger cars or 0.7 second for trucks) to account for the additional distance required by the turning vehicle to cross the additional lanes or median.
- 2) **Medians.** The following will apply:
 - For a multilane facility which does not have a median wide enough to store a design vehicle, divide the median width by 12 feet to determine the lane value (e.g., for a 4-foot median use 0.33), and then use the criteria in [Table 7-11](#) to determine the appropriate time factor.
 - On facilities with a median wide enough to store the design vehicle (e.g., 3 feet clearance at both ends of vehicle, see table with AASHTO design vehicle lengths below), the designer should evaluate the sight distance needed in two separate steps:

Design Vehicle Type	Overall Vehicle Length
Passenger Car	19 feet
Single-Unit Truck (SU)	30 feet
School Bus (S-BUS 40)	40 feet
Semitrailer (WB-62)	68.5 feet

- First, with the vehicle stopped on the side road (the bottom portion in [Figure 7-24](#)), use the gap acceptance times and distances for a vehicle turning right ([Table 7-11](#) and [Table 7-12](#)) to determine the applicable ISD. Under some circumstances, it may be necessary to check the crossing maneuver to determine if it is the critical movement. Crossing criteria are discussed in [7C-1.3](#).
- Second, with the vehicle stopped in the median (top portion in [Figure 7-24](#)), assume a two-lane roadway design and use the adjusted gap acceptance times and distances for vehicles turning left ([Table 7-11](#), [Table 7-11](#), and [Table 7-12](#)) to determine the applicable ISD.

- 3) **Approach Grades.** If the approach grade on the minor road exceeds 3 percent, increase the level ISD value by 10 percent.
- 4) **Design Vehicle.** A passenger vehicle is used in most design ISD situations. However, at some intersections (e.g., near truck stops, interchange ramps, schools, grain elevators), the designer should use the design vehicle for determining the ISD. The gap acceptance times (tg) for passenger cars, single unit (SU) and tractor/semitrailer trucks are provided in [Table 7-11](#). ISD values for level, two-lane roadways are presented in [Table 7-12](#). The height of eye for these vehicles is discussed earlier in [Section 7B](#).

Table 7-11: Gap Acceptance Times, Left Turns from Minor Road

Design Vehicle	Gap Acceptance Time (tg) (sec)
Passenger Car	7.5
Single Unit Truck (SU)	9.5
Tractor/Semitrailer	11.5

1. **Multilane Highways.** For left turns onto two-way multilane highways, add 0.5 second for passenger cars or 0.7 second for trucks for each additional lane from the left, in excess of one, to be crossed by the turning vehicle. Assume that the left-turning driver will enter the left-travel lane on the far side of the major road.
2. **Minor Road Approach Grades.** If the approach grade on the minor road exceeds 3 percent, increase the level ISD value by 10 percent.
3. **Major Road Approach Grade.** Major road grade does not affect calculations.

Table 7-12: Intersection Sight Distance, Vehicles Approaching from the Left and For Vehicles Approaching from the Right on a Two-Lane Highway or Street Only

Design Speed (V _{major}) (mph)	Intersection Sight Distance (Feet)		
	Passenger Car	Single-Unit Truck	Tractor/Semitrailers
30	335	420	510
35	390	490	595
40	445	560	680
45	500	630	765
50	555	700	850
55	610	770	930
60	665	840	1015


Note: These ISD values assume a minor road approach grade less than or equal to 3 percent. For grades greater than 3 percent, increase the ISD value by 10 percent.

Table 7-13: Intersection Sight Distance For Vehicles Approaching from the Right on a Four-Lane Highway with a 15 Foot TWLTL Only

Design Speed (V _{major}) (mph)	Intersection Sight Distance (Feet)		
	Passenger Car	Single-Unit Truck	Tractor/Semitrailers
30	385	490	580
35	445	570	675
40	510	655	770
45	575	735	865
50	635	815	965
55	700	900	1060
60	765	980	1155

1. Calculated ISD is not shown. Values in the figure have been rounded up to the next highest 5-foot increment.
2. These ISD values assume a minor road approach grade less than or equal to 3 percent. For grades greater than 3 percent, increase the ISD value by 10 percent.
3. These ISD values assume the left-turning vehicle will enter the inside travel lane on the far side of the major road.
4. For a right turn from a minor road (i.e., ISD to the left), use the ISD values presented in [Table 7-12](#).
5. Gap acceptance time (t_g) adjustment factors have been used for each additional lane from the left, in excess of one, to be crossed by the turning vehicle (i.e., additional 0.5 second for passenger cars, additional 0.7 second for trucks).

Figure 7-24: Sight Triangles on Divided Facilities

**7C-1.2 Case B2 – Right-Turn From the Minor Road**

ISD for right turns is determined using [Table 7-12](#). Note that there are no adjustments required for facilities with medians.

7C-1.3 Case B3 – Crossing Maneuver From the Minor Road

In the majority of cases, the ISD for turning vehicles typically will provide adequate sight distance to allow a vehicle to cross the major road. However, in the following situations, the crossing sight distance may be the more critical movement:

- where left and/or right turns are not permitted from a specific approach and the crossing maneuver is the only legal or expected movement (e.g., indirect left turns);
- where the design vehicle must cross more than six travel lanes or, with medians, the equivalent distance; or
- where a substantial volume of heavy vehicles cross the highway and there are steep grades on the minor road approach.

Use Equation 7.1 and the adjusted gap acceptance times (t_g) in [Table 7-14](#) to determine the ISD for crossing maneuvers. [Table 7-15](#) presents the applicable ISD values for crossing maneuvers for a level, two-lane highway with no median. Where medians are present, include the median width in the overall length to determine the applicable gap time. Divide this width by 12 feet to determine lane value for the crossing maneuver (e.g., for a 15-foot median use 1.25).

Table 7-14: Gap Acceptance Times for Crossing Maneuvers

Design Vehicle	Gap Acceptance Time (tg) (sec)
Passenger Car	6.5
Single Unit Truck (SU)	8.5
Tractor/Semitrailer	10.5

Adjustments:

1. *Multilane Highway.* Where the design vehicle is crossing a major road with more than two lanes, add 0.5 second for passenger cars or 0.7 second for trucks for each additional lane in excess of two. See the discussion in Section 7C-1.3 for additional guidance.
2. *Approach Grade.* If the approach grade on the minor road exceeds 3 percent, increase the ISD value by 10 percent.

Table 7-15: Two-Lane Intersection Sight Distances

Design Speed (V _{major}) (mph)	Intersection Sight Distance (Feet)		
	Passenger Car	Single-Unit Truck	Tractor/Semitrailers
30	290	375	465
35	335	440	545
40	385	500	620
45	430	565	695
50	480	625	775
55	530	690	850
60	575	750	930

Notes:

1. These ISD values assume turns onto a two-lane facility without a median.
2. These ISD values assume a minor road approach grade of 3 percent. For grades greater than 3 percent, increase the ISD value by 10 percent.

7C-2 Case D – Intersections with Traffic Signal Control

Traffic signals should not be an alternative to providing adequate sight distance. Intersection sight distance as described in Section 7B-1 should be provided.

7C-3 Case E – Intersections With All-Way Stop Control

For intersections with all-way stop control, provide sufficient sight distance so that the first stopped vehicle on each approach is visible to all other approaches. The ISD criteria for left- or right-turning vehicles as discussed in Section 7B-1 are not applicable in this situation. Often, intersections are converted to all-way stop control to address limited sight distance at the intersection.

7C-4 Case F – Left Turns From the Major Road

For all intersections, regardless of the type of traffic control, the designer should consider the sight distance for a stopped vehicle turning left from the major road. This situation is illustrated in [Figure 7-25](#). The driver will need to see straight ahead for a sufficient distance to turn left and clear the opposing travel lanes before an approaching vehicle reaches the intersection. Sight distance for opposing left turns may be increased by offsetting the left-turn lanes.

Use [Equation 7.1](#) and the gap acceptance times (t_g) from [Table 7-16](#) to determine the applicable ISD for the left-turning vehicle. Where the left-turning vehicle must cross more than one opposing lane, add 0.5 second for passenger cars or 0.7 second for trucks for each additional lane in excess of one. Where medians are present and the left-turns are not offset, the designer will need to consider the median width in the same manner as discussed in [Section 7B-1.1](#). [Table 7-17](#) provides the ISD values for typical design vehicles and two common left-turning situations.

7C-5 Effect of Skew

Where it is impractical to realign an intersection that is greater than 30 degrees from the perpendicular, adjust the gap acceptance times (t_g) presented in the above sections to account for the additional travel time required for a vehicle to make a turn or cross a facility. For oblique-angled intersections, determine the actual path length for a turning or crossing vehicle by dividing the total distance of the lanes and/or median to be crossed by the sine of the intersection angle. If the actual path length exceeds the total width of the lanes to be crossed by 12 feet or more, apply the applicable adjustment factors; see [Figure 7-26](#).

Figure 7-25: Sight Distance for a Stopped Vehicle Turning Left on a Major Road




Table 7-16: Gap Acceptance Times for Left Turns on a Major Road


Design Vehicle	Gap Acceptance Time (tg) (sec)
Passenger Car	5.5
Single Unit Truck (SU)	6.5
Tractor/Semitrailer	7.5

Adjustments: Where left-turning vehicles cross more than one opposing lane, add 0.5 second for passenger cars or 0.7 second for trucks for each additional lane in excess of one. See Section 10.4.5 of the SCDOT Highway Design Manual for additional guidance on median widths.

Table 7-17: Intersection Sight Distances, Left Turns from Major Road

Design Speed (V _{major}) (mph)	Intersection Sight Distance (Feet)					
	Passenger Car		Single-Unit Truck		Tractor/Semitrailers	
	Crossing 1 Lane	Crossing 2 Lanes	Crossing 1 Lane	Crossing 2 Lanes	Crossing 1 Lane	Crossing 2 Lanes
30	245	265	290	320	335	365
35	285	310	335	370	390	425
40	325	355	385	425	445	485
45	365	400	430	480	500	545
50	405	445	480	530	555	605
55	445	490	530	585	610	665
60	485	530	575	640	665	725

Figure 7-26: Sight Distance at Skewed Intersection



INTERSECTION SIGHT DISTANCE QUICK REFERENCE TABLE

Type of Roadway	Type of Turn from Minor Road		
	Right Turn	Thru Movement	Left Turn
Two - Lane Highway *	Table 7-12	Table 7-15	Table 7-12
Three - Lane Highway * ^	Table 7-12	Equation 7.1 with Table 7-14 for t_g	Equation 7.1 with Table 7-11 for t_g
Four - Lane Highway *	Table 7-12	Equation 7.1 with Table 7-14 for t_g	Equation 7.1 with Table 7-11 for t_g
Five - Lane Highway * ^	Table 7-12	Equation 7.1 with Table 7-14 for t_g	Table 7-13
Six or More Lanes	Table 7-12	Equation 7.1 with Table 7-14 for t_g	Equation 7.1 with Table 7-11 for t_g

* - Assumed 12' Lanes

^ - Assumed 15' Median

If assumptions listed above are not correct - Equation 7.1 is to be used.

CHAPTER 8 –TRAFFIC CONTROL DEVICES



8A GENERAL

Traffic control at access points shall comply with the MUTCD and *SCDOT Standard Specifications for Highway Construction* and shall be designed to accommodate the needs of traffic generated by development while minimizing interference with other traffic. Traffic control devices and pavement markings shall be installed on all streets and on driveways that have geometric and operational characteristics resembling those of a street. Design, equipment, installation, and maintenance of traffic control devices, with the exception of some traffic signals, shall be the responsibility of the owner and shall require approval by the Department. All permanent traffic control devices are to be included as part of the encroachment permit.

8B TRAFFIC SIGNALS

Traffic signals are a vital element in the safe and efficient movement of people and goods. Proper planning and design are critical to the operations of the road system. All traffic signal systems on the state highway system shall conform to the following guidelines and specifications: *SCDOT Traffic Signal Design Guidelines* (SCTSDG), *SCDOT Traffic Signal Specifications*, *SCDOT Traffic Signal Standard Drawings*, and the MUTCD.

8B-1 Traffic Signal Requests

If a permittee is requesting a signal as part of their access, a study should be prepared by their traffic engineer at the permittee's cost and submitted to the SCDOT for review. An engineering study of traffic conditions, pedestrian characteristics, and physical characteristics of the location shall be performed to determine whether installation of a traffic signal is justified at a particular location. The study should follow the guidelines outlined in the *SCDOT Traffic Signal Design Guidelines* and the *MUTCD*. Any trip generation should also be in conformance with the *ITE Trip Generation Manual* or other accepted standard. Engineering judgment and rationale should also be applied to indicate that installing a traffic control signal would improve the overall safety and/or operation of the intersection.

The decision of whether a signal is approved is under the District Engineering Administrator's (DEA) authority.

8B-3 Design and Installation of Traffic Signals

Signal Plans shall be prepared under the supervision of a professional engineer registered in South Carolina. The signal plan shall be signed and sealed under the same engineer. They should include accurate depictions of pavement markings, signal head placement, span wires, right-of-ways, driveways, sidewalks, control of access, and also should indicate signal timings, speed limits, grades, route names and numbers, adjacent development, coordination details, etc. Plans and specifications should be made part of the driveway encroachment permit and submitted to the SCDOT for review. All costs associated with the design and installation shall be the responsibility of the developer unless otherwise specified by SCDOT Engineering Directive #2 which is provided in [Appendix D](#).

SCDOT's Traffic Signal Shop shall inspect all traffic signal work and shall be notified before any traffic control signal is placed in operation. SCDOT's Traffic Signal Shop should also be included in any preconstruction conferences. Electronic cadd files of the signal plans shall be provided to the respective District Traffic Engineer (DTE).

8B-4 Traffic Signal Maintenance

Fiscal and maintenance responsibilities for traffic signal installations on the State Highway System are outlined in SCDOT Engineering Directive #2. This directive has been provided in [Appendix D](#). The developer will be responsible for the recurring electric costs at the signal if it serves a private driveway.

8B-5 Mast Arms

The SCDOT's *Traffic Signal Design Guidelines* and SCDOT Engineering Directives #2 and #33 has established a policy indicating that SCDOT does not install or maintain mast arms for traffic signals, as indicated below:

"Special equipment such as decorative poles or mast arms are not considered to be standard equipment and are to be paid for by the permittee or agent. If replacement for any reason is required, the Department will replace with standard equipment unless the requesting agency agrees to provide funding for special equipment."

Although, SCDOT recognizes the desire for mast arm installation by local governments for aesthetic purposes, typically mast arm costs far exceed other signal supports, such as span wire with wood, steel, or concrete poles. SCDOT will allow the installation of mast arms provided the local government having jurisdictional authority at the signalized intersection enters into an agreement with SCDOT concerning the maintenance of the mast arms.

8C PAVEMENT MARKINGS

General information and typical drawings regarding pavement markings can be found in the latest edition of the SCDOT *Standard Drawings for Road Construction*. This publication is available on the web at <http://www.scdot.org/doing/sddisclaimer.asp>. These standards include specific typical drawings for intersections, turn lane installations, and raised pavement marker placement. All standards are in accordance with the MUTCD. For additional information not included in the SCDOT Standard Drawings, refer to the most recent edition of the MUTCD which can be accessed via the web at <http://mutcd.fhwa.dot.gov>.

THIS PAGE INTENTIONALLY LEFT BLANK

CHAPTER 9 –ROADSIDE ENCROACHMENTS



9A MAILBOXES

The location and construction of mailboxes shall conform to SCDOT Standards, the guidance given in the *AASHTO Roadside Design Guide*, and the rules and regulations of the United States Postal Service. An encroachment permit is not required for mailbox installations. Mailbox structure and location on South Carolina DOT right-of-way are governed by *SCDOT Standard Drawing* Number 203-905-00. This drawing can be accessed via the SCDOT website at <http://www.scdot.org/doing/sddisclaimer.asp>.

In accordance with Section 57-7-210 of the South Carolina Code of Laws, any mailbox construction which is considered a hazardous fixed object, such as a brick structure, shall not be allowed as a support, encasement, or housing for the mailbox. When any mailbox installation is found to violate the intent of these standards the postal patron will be advised in writing that the installation constitutes a hazard to the motoring public. A copy of the notice will be provided to the local postmaster. At the discretion of the Department, based on an assessment of danger to the public, the patron will be granted not less than 10 nor more than 30 days to remove an unacceptable mailbox installation. After the specified removal period has expired, the unacceptable mailbox may be removed by the Department.

9B SIGNS

Any unauthorized sign placed on the highway right-of-way by an individual or private organization constitutes a public nuisance and will be removed pursuant to Section 56-5-1020 of the Code of Laws of South Carolina (1976 as amended). By the same authority, any sign in view of a highway which purports to be or interferes with the effectiveness of an official traffic control device is likewise a public nuisance and will be removed accordingly in accordance with Engineering Directive Memorandum #9 (provided in the [Appendix D](#)).

9C LIGHTS AND REFLECTIVE SURFACES

When in view of a highway, any sign lighting must be constructed and maintained to prevent light from being directed at any portion of the roadway pursuant to Section 57-25-140 of the Code of Laws of South Carolina (1976 as amended). Sign lighting which causes glare, impairs vision, unduly distracts, or otherwise interferes with the operation of a motor vehicle is prohibited. These conditions also apply to individual lights, lighting or surfaces reflecting light or sun glare. Flashing or pulsing lights may not be attached to or used to illuminate any sign, except a sign giving brief messages regarding public service information such as time, temperature, weather, or similar information. Lights which change color may not be attached to or used to illuminate any sign.

9D ROADWAY LIGHTING

Roadway lighting should be designed to meet the requirements as outlined in the latest edition of the *AASHTO Roadway Lighting Design Guide*. More detailed requirements for interstate lighting, including exit and entrance ramps, are available from the Director of Traffic Engineering. A photometric analysis of the lighting for the section of roadway should be submitted to Director of Traffic Engineering and approved before the permit is approved.

Where roadway lighting is installed, the pole setback will vary based on the speed and cross section design of the roadway. Light standards on the right-of-way or within the clear-zone of the roadway should be equipped with breakaway supports designed so that no fixed part of the support extends further than three inches above ground level. When used, the breakaway capability of the support shall incorporate the use of breakaway electrical connectors so that no live electrical wires exist after impact by a vehicle.

The breakaway poles shall meet the criteria established in the latest edition of the *AASHTO Standard Specifications for Structural Supports for Highway Sign Luminaires and Traffic Signals* and be approved by the Federal Highway Administration as meeting the requirements of NCHRP Report 350.

9E GATEWAY MONUMENTS FOR INTERSTATE HIGHWAYS

9E-1 General

A Gateway Monument is defined as any freestanding structure, non-integral or non-required highway feature that will communicate the name of a city, county, or town (Local Entity) within SCDOT interstate right of way. A Gateway Monument may include the name of the Local Entity and/or the officially adopted seal or logo. The approval of a Gateway Monument submittal shall be made with due consideration to safety, aesthetics, community support, and maintainability.

Once SCDOT approves a Gateway Monument and an Encroachment Permit is issued, no changes shall be made to the Gateway Monument without prior written approval of the District Permit Engineer and review by FHWA.

9E-2 Guidance

A Local Entity is defined as a county, municipal corporation, state or local authority, board, commission, agency, department or political subdivision created under

the authority of the state. The responsible Local Entity is encouraged to initiate early coordination with SCDOT to ensure the project scope and goals are achieved in compliance with state and federal guidelines. The Local Entity must possess the financial means to provide maintenance of the improvements in perpetuity.

Only one Gateway Monument will be allowed per interstate route in each direction into a Local Entity. Other improvements such as landscaping or accent lighting may be considered in conjunction with the Gateway Monument submittal.

9E-3 Review and Approval Process

SCDOT shall have responsibility for approval of all Gateway Monuments on the interstate highway system and in addition, the Federal Highway Administration (FHWA) must approve Gateway Monuments on the interstate system. Gateway Monument encroachment permit submittals will be provided to the District Permit Engineer for approval. The District Permit Engineer will provide the submittal to the State Permit Engineer. The State Permit Engineer will coordinate with other SCDOT offices and FHWA as needed.

Gateway Monument submittals shall be reviewed with primary considerations to safety. The incorporation of a Gateway Monument will be evaluated for its potential for creating a distraction to motorists. Gateway Monuments shall comply with South Carolina's currently approved version of the International Building Code (IBC) and be permitted by the local building department. A copy of the building permit must be provided to the District Permit Engineer prior to approval of the encroachment permit.

9E-4 Maintenance

Gateway Monuments shall require a Maintenance Partnership Agreement (MPA). The agreement will define the Local Entity's maintenance responsibilities. Coordinate with the SCDOT District Permit Engineer to determine the requirements for the MPA. If the Local Entity neglects to uphold these requirements, SCDOT has the authority to revoke the encroachment permit and require the removal of the Monument from the right of way. Examples of requirements for the MPA are as follows:

- Gateway Monument shall be kept clean and in good repair.
- Local Entity shall provide regularly scheduled maintenance for the projected lifespan of the Monument.
- Local Entity shall provide for restoration work to maintain the integrity of the approved Monument and any associated landscaping or lighting.
- Graffiti removal shall conform to current SCDOT policies and guidelines, which require prompt removal of offensive messages and timely removal of all other graffiti.
- Maintenance access shall be coordinated with SCDOT.

9E-5 Design and Placement of Gateway Monuments

A) Proposed Gateway Monuments shall:

- 1) Be freestanding.
- 2) Feature the letters of the community name and/or officially adopted seal/logo.
- 3) Be in proper size and scale with its surroundings; i.e., it must be appropriately integrated to the urban or rural context. The maximum size of the Gateway Monument face shall not exceed 300 square feet in total. The height shall not exceed 15 feet above existing grade. The proposed Gateway Monument shall be large enough to interpret at highway speed, but not so large that it distracts the motorist.
- 4) Be composed of materials that are durable for the projected life span of the project.
- 5) Be located one and one half times beyond the maximum clear zone for both mainline traffic and ramp/frontage road traffic.

- 6) Be located a minimum of 50 feet away from any SCDOT bridge or roadway structure (earth retaining structure, culvert, etc.).
- 7) Be located a minimum of 500 feet beyond the physical gore nose.
- 8) Be located where maintenance can be safely performed.

B) *Proposed Gateway Monuments **shall not:***

- 1) Be allowed within the center median.
- 2) Contain religious, political, special interest, private, or commercial messages of any sort, including, but not limited to, symbols, logos, business names, trade names, personal names, jingles, or slogans not found on the official seal or logo of the local entity.
- 3) Display any sort of advertising, decorative banners, flags, or flag poles.
- 4) Display telephone numbers, street addresses, websites, or email addresses.
- 5) Interfere with airspace above the roadway.
- 6) Create a distraction to the motoring public.
- 7) Include reflective or glaring surface finishes.
- 8) Include illumination that impairs or distracts the vision of transportation system users.
- 9) Display blinking or intermittent or moving lights, including changeable message signs, digital displays or lighted static displays such as LED.
- 10) Include moving elements (kinetic art, clocks) or simulated movement.
- 11) Include water features of any sort.
- 12) Interfere with official traffic control devices nor interfere with the operational right of way above the roadway.
- 13) Be attached to trees or drawn upon rocks or other existing natural features.
- 14) Make use of or simulate colors or combinations of colors usually reserved for official traffic control devices described in the Manual on Uniform Traffic Control Devices.
- 15) Negatively impact existing highway features, including existing signs, irrigation systems, drainage, cameras, lighting, message boards, and other facilities.

9E-6 Requirements for Gateway Monument Permit Submittal

A Gateway Monument Encroachment Permit submittal (design phase) must be submitted in the name of the Local Entity that has jurisdiction in the area where the Gateway Monument will be incorporated. The Local Entity shall issue a letter on official letterhead that specifies the following:

- Jurisdiction over the area of the project site.
- Approval of the Gateway Monument content and appearance.
- Funding responsibility.
- A signed Maintenance Partnership Agreement.
- Proposed schedule for commencing and completing project installation.

A South Carolina licensed architect or engineer shall prepare, sign, and seal submittals for Gateway Monuments. Exhibits, plans, and details shall include, but are not limited to the following:

- A full description of the proposed Gateway Monument, including: location, proposed color scheme, and proposed materials (including, but not limited to, paint and protective coatings).

- A scaled drawing indicating the placement of the proposed Gateway Monument. All clear zone dimensions shall be labeled from the edge of the traveled way.
- Plan sheets and details clearly illustrating and dimensioning the monument.
- Landscape, irrigation, and lighting plans if required.
- Traffic Control details including construction and maintenance access.
- Local building permit.

9F UTILITIES

Public Utility lines may be located within the highway right-of-way provided they are constructed so as not to endanger the safety of persons or to interfere with the use of the highway. Utility lines over bridge rights-of-way must be at a height sufficient to accommodate bridge maintenance, improvements and reconstruction. The Department must approve such an encroachment. Applications from the utility companies are reviewed for acceptance using the latest edition of the Department's "A Policy for Accommodating Utilities on Highway Rights-of-Way" as a guide. A copy of this document is available from the SCDOT Utilities Office or online at http://www.scdot.org/doing/ua_policy.shtml.

A permit will not be required for aerial service connections from an existing distribution line on Department Rights-of-way unless it is anticipated that there will be an interference with the normal flow of vehicular traffic on or along the highway or a new pole is to be placed on the Department's rights-of-way. Also, a permit will not be required for normal maintenance such as replacing existing poles, cables, pedestals, marker, etc. unless such repairs will entail alterations of normal traffic flow, or the maintenance activities require the relocation of the existing utility.

9G VISIBILITY ENHANCEMENT

Selective removal of vegetation for the purpose of making commercial and industrial sites more visible is governed by the Department's Engineering Directive 29. (See [Appendix D](#))

9H HISTORICAL MARKERS AND BLUE STAR MEMORIAL HIGHWAY SIGNS

SCDOT recommends that Historical Markers and Blue Star Memorial Highway Markers be placed off of the highway right-of-way. If it is not possible to place the marker off of the right-of-way, an encroachment permit must be approved prior to installation. The permit should indicate the location of the marker and include a copy of the marker approval letter from the South Carolina Department of Archives and History (SCDAH). To determine if a proposed marker location is within the highway right-of-way and if the location is feasible, the permittee should contact the SCDOT Resident Maintenance Engineer in the county where the marker will be located.

If located within the highway right-of-way, a marker must be installed on a single breakaway post or post/breakaway slip base coupling that has been tested and certified as meeting the requirements of NCHRP 350. Submit certifications for the breakaway post or post system as part of the encroachment permit. Typically, an alternate round post must be substituted for the standard octagonal-shaped post supplied with the marker when the breakaway slip base coupling system is used. The marker sponsor should notify the manufacturer when ordering that the post must be breakaway so that the alternate post can be substituted and shipped with the marker. The manufacturer may require the sponsor to obtain a post from a separate vendor/local retailer when breakaway is required. Vendor contact information for the breakaway slip base couplings can be obtained from Traffic Operations in the Headquarters Traffic Engineering office.

In cases where the highway right-of-way may be wider than usual or in other special cases, the clear zone distance for the roadway in accordance with AASHTO's *Roadside Design Guide* (Latest Edition) may be used to determine if a breakaway post is required instead of the right-of-way line/distance. In urban areas or areas with curb and sidewalk, where vehicle speeds are low (35 mph or less) and pedestrian activity is significant, SCDOT prefers that posts for markers be direct burial instead of breakaway, to decrease the chances of pedestrian injuries if a marker is struck by a vehicle. Coordination with the District Traffic Engineer is required in these urban area cases. If a marker is installed off of SCDOT right-of-way, no encroachment permit is required.

SCDOT does NOT accept delivery of Historical Markers nor Blue Star Memorial Highway Markers from the manufacturer, does NOT install the markers, and does NOT maintain the markers. The marker sponsor or permittee is responsible for providing the necessary arrangements for delivery, installation, and maintenance

THIS PAGE INTENTIONALLY LEFT BLANK

THIS PAGE INTENTIONALLY LEFT BLANK

CHAPTER 10 — DRAINAGE



10A GENERAL REQUIREMENTS

Each access point shall be constructed in a manner that prevents water from flowing onto the roadway and from adversely affecting the existing storm drainage system. For example, driveways and paved areas sloping down toward the roadway should have provisions for water to be intercepted off the right-of-way and shall not have a low point within the shoulder break line. The driveway's slope between the shoulder break line and roadway edge shall be the same as the slope of the shoulder as specified in Chapter 3 subsection 3G-3.

10B DESIGN AND DISCHARGE

Drainage collected from off the right-of-way shall not be discharged onto the highway right-of-way unless discharge is approved by the Department's issuance of an encroachment permit. The applicant shall submit a drainage study that details the existing and proposed drainage for the site and compares the pre and post discharges at the point of release onto Department right-of-way. The applicant must follow the drainage design requirements as given in the latest edition of the SCDOT *Hydraulic Design Requirements*, which can be found on the SCDOT website at <http://www.scdot.org/doing/pdfs/requirements.pdf>.

Post-development release rates to the highway right-of-way for the 2-year, 10-year, and 25-year storm events shall be equal to or less than those calculated for the pre-development condition for the 2-year, 10-year, and 25-year storm events, respectively, as determined in accordance with Department design policy for the given site conditions. If the post-development discharges for the 2-year, 10-year, and 25-year

storm events exceed the pre-development discharges for the given storm event to the Department right-of-way, the applicant will be required to provide flow detention on site so that the pre-developed discharge condition is met. When the proposal is to connect directly to a SCDOT crossline pipe, the applicant will be required to meet the pre- and post-development rates for the 50-year storm if the roadway is a Primary (SC, US) or Interstate route. Details for detention structures and means of discharge, as well as design calculations, shall be approved by a registered professional engineer in compliance with Sections 40-21-10 and 40-21-30 of the Code of Laws of South Carolina (1976 as amended).

For cases where a driveway or new road intersects the state highway system, sag and catch basins will be required prior to the intersection to collect the water from the new road prior to the highway right-of-way in order to prevent flooding of the state highway system.

All of the aforementioned items shall be submitted with the Application for Encroachment Permit. Approval by a professional engineer or the Department does not preclude the need for compliance with any applicable federal, state, or local regulations or ordinances.

10C MAINTENANCE AND SAFETY CONSIDERATIONS

Pipes or ditches discharging into the highway drainage system shall join the system at an appropriate angle and have other provisions as necessary to prevent scour, erosion, or blockage of the existing drainage components.

The design of drainage structures shall be in conformance with the latest edition of the SCDOT *Standard Drawings*. New drainage components that would create maintenance problems or compromise safety shall not be permitted. These may include, but are not limited to, vertical wingwalls/headwalls, grates, pipes, and aboveground catch basin covers which are within 30 feet of the roadway. Curbing on driveways or streets shall not extend beyond the right-of-way line or ditch line when the driveway or street connects to a roadway not having curbing. Culverts shall extend at least the full distance from the toe of one side of a fill to the toe of the opposite side. All drainage components shall conform to the existing roadway cross-section and profile. All structures shall be brought to a final grade flush with the existing profile and cross section. Catch basins are strongly discouraged in curved sections and within intersection radii.

Sediment and erosion control measures shall be shown on the application and constructed as the first phase of construction to prevent any sediment from reaching the highway right-of-way or drainage system.

10D NPDES CONSIDERATIONS

With the implementation of the Municipal Separate Storm Sewer System (MS4) permit, the Department is now responsible for the water quality of its storm water discharges. Therefore, the applicant will be required to be responsible for the water quality of their discharges if their encroachment permit is approved. The permittee must evaluate the SCDOT system they intend to discharge to and document whether or not that system discharges to a water body listed on the 303(d) Impaired water bodies list which can be found at www.scdhec.net/environment/water/docs/06_303d.pdf. If so, the applicant must determine what pollutant(s) the water body is/are impaired for. In

addition, the permittee must establish whether or not the system discharges to a body of water with a Total Maximum Daily Load (TMDL). If so, the permittee must ascertain what the pollutant(s) of concern is/are for that TMDL. South Carolina Total Daily Maximum Loads can be found at www.scdhec.net/environment/water/tmdl/tmdlsc.htm.

These analyses must be performed for both the construction and the post-construction phases of the project and the impacts to water quality of the impaired waters from the SCDOT system must be documented. The permittee must implement Best Management Practices (BMPs) if it is determined that the discharges will have adverse impacts to the impaired water body during either the construction or post-construction phases. The water quality analysis for the system in question must demonstrate that the selected BMPs meet the requirements of the TMDL. In addition, stormwater management devices and BMPs placed within SCDOT right-of-way should conform to SCDOT requirements. Applicants must also comply with all applicable federal and state storm water management and sediment and erosion control guidelines.

10E PERMIT APPLICATION REQUIREMENTS

The applicant's encroachment permit package for the hydraulic engineering reviews should include the following as a minimum:

- A statement by applicant that no work will begin until concurrence letter from DHEC or OCRM and any other governmental agency whose concurrence is required is received, if applicable,
- A set of detailed engineer's pre- and post-development drawings of the site that includes grading and drainage,
- Detailed hydraulic and stormwater management design studies that show the calculations, including a well-written narrative that explains existing conditions, they study, and what is to be done,
- A CD with the computer input and output files used by the engineer,
- A determination of whether or not the proposed construction causes any impacts to downstream roads, buildings, bridges, etc.,

THIS PAGE INTENTIONALLY LEFT BLANK

CHAPTER 11 — ENVIRONMENTAL



11A GENERAL REQUIREMENTS

Any encroachment or access requests shall be evaluated by the permittee with respect to impacts to Water of the United States (e.g. rivers, creeks, streams, swamps, ponds, marshes, roadside ditches, etc.). If impacts to these jurisdictional resources will occur as result of an access point request, authorization from a state or federal agency may be required. Coordination with the SCDOT Environmental Management Office shall be completed prior to approving any requests that potentially impact these resources.

11B PERMITTING REQUIREMENTS

If the requested access impacts a jurisdictional resource, a delineation of the impacted area must be completed and submitted to the Corps of Engineers for their review and approval. Once the delineation is approved, the applicant, or his designee, will prepare and submit a permit application package to the appropriate state and federal regulatory agencies. The applicant will be responsible for obtaining the appropriate permits prior to beginning of the encroachment work. A copy of the approved permits will be submitted to the SCDOT Environmental Management Office for review and verification prior to commencement of construction. Information concerning permitting requirements may be obtained from the SCDOT Environmental Management Office.

THIS PAGE INTENTIONALLY LEFT BLANK

CHAPTER 12 — BRIDGES, CULVERTS, AND RETAINING WALLS



12A GENERAL REQUIREMENTS

When an encroachment permit application includes the construction of a bridge, culvert, or retaining wall, replacement of one of these structure types, modifications to one of these structure types, or construction activities immediately adjacent to one of these structure types, the design and details of the proposed construction are subject to the requirements of the latest editions of all applicable SCDOT design and construction manuals as well as SCDOT policies and standard practices. Design and construction criteria may be found in the most current editions of the following:

- AASHTO LRFD Bridge Design Specifications
- AASHTO LRFD Bridge Construction Specifications
- AASHTO Policy on Geometric Design of Highways and Streets
- SCDOT Bridge Design Manual
- SCDOT Seismic Design Specifications for Highway Bridges
- SCDOT Geotechnical Design Manual
- SCDOT Highway Design Manual
- SCDOT Requirements for Hydraulic Design Studies
- SCDOT Plan Preparation Guide
- SCDOT Bridge Design Memoranda
- SCDOT Bridge Design Drawings and Details
- SCDOT Standard Specifications for Highway Construction
- SCDOT Supplemental Specifications
- SCDOT Standard Drawings
- SCDOT Construction Manual

Information regarding the applicable SCDOT publications can be found on the SCDOT website at: <http://www.scdot.org/doing/default.shtml>.

Five copies of the following shall be included along with the application:

- Geotechnical Report
- Hydrology Report (required for structures crossing or conveying water)
- Construction Plans (22" x 36") including Traffic Control Plans and Contract Special Provisions
- Structural Design Calculations

The Geotechnical Report, Hydrology Report, Structural Design Calculations, Construction Plans, and Special Provisions shall be signed and sealed by a registered professional engineer, registered in the State of South Carolina. The title sheet of the construction plans must include a location map and state the firm or persons that will perform the construction inspection and certification to ensure that the Contractor's work is performed in accordance with the contract plans, special provisions, and the current edition of the *SCDOT Standard Specifications for Highway Construction*. The title sheet must also include any necessary municipality and/or county approval including any state or federal permits when applicable.

The application shall also include a letter indicating that maintenance of the structure is the responsibility of the Permittee, unless there is a signed agreement between the SCDOT and the Permittee stating otherwise.

After the completion of the construction, the Permittee shall provide the Department two copies (22" x 36") of the as-built construction plans. One copy shall be kept in the District and one copy forwarded to the As-Built Plans Office in Preconstruction Support to be scanned and placed in the SCDOT Plan Library.

12B PRELIMINARY COORDINATION

Prior to submitting a permit application that involves construction of significant sized or complex bridges, culverts, or retaining walls, it is recommended that the applicant contact the Structural Design Support Engineer at (803) 737-4814 to arrange a meeting to discuss the scope of the structural work. It is also recommended that the Applicant, prior to finalizing the required attachments for the permit application, provide preliminary plans and 95% Plans to the Structural Design Support Engineer for review and comment.

CHAPTER 13 — CONSTRUCTION



13A GENERAL

All construction performed on SCDOT rights-of-way, including modification to existing features, shall be subject to the terms and conditions of the approved encroachment permit along with accompanying plans, drawings, sketches, special provisions, specifications, or other attachments. No work shall be performed on highway rights-of-way by the applicant or his contractor prior to approval of the encroachment permit by the Department and a notice to proceed has been issued by the Resident Maintenance Engineer (RME). The permittee or his contractor shall maintain a copy of the approved encroachment permit on site during construction. Verbal permission to begin work cannot be given.

The permittee shall have the responsibility to determine and comply with all applicable federal, state, and local laws and ordinances in connection with all work associated with the approved encroachment permit. This obligation shall include but not be limited to procurement of all permits and licenses. The permittee shall be responsible for all charges, fees, taxes, and etc. associated with all work in the approved encroachment permit.

The permittee shall be responsible for ensuring that all work performed on SCDOT's rights-of-way is constructed in conformance with the encroachment permit and other specifications as directed below in this chapter.

The permittee shall indemnify and hold SCDOT harmless from any and all claims, liabilities, and causes of action for any fines or penalties imposed on SCDOT arising from work associated with the encroachment permit.

13B INSPECTION AND APPROVAL

The level of inspection, certification, and ultimate acceptance of work by SCDOT will vary depending on the type of work specified in the encroachment permit. All work on SCDOT's rights-of-way associated with encroachment permits will require a notice to proceed from the RME prior to work beginning and a letter of final acceptance upon completion of the project prior to opening for public use.

For the purposes of construction, encroachment permits for access shall be divided into three categories; residential driveways, commercial driveways, and large commercial driveways. The following standards and guidelines are to be used for each specific category.

13B-1 Residential Driveways

Residential driveways are driveways installed by the property owner or his contractor at his expense to serve low volume land uses such as 1 to 2 single family homes. The approved encroachment permit shall serve as the notice to proceed. The permittee shall adhere to all special provisions listed in the encroachment permit. The *Manual of Uniform Traffic Control Devices* (MUTCD – latest edition) and the latest edition of the SCDOT *Standard Drawings* shall be used in the development of the traffic control plan.

Upon completion of all work, the permittee shall contact the RME for a final inspection of the work. If the work has been completed satisfactorily, a letter of acceptance will be issued. If the work is not completed satisfactorily, a punch list will be developed noting all deficiencies. Once the deficiencies have been corrected by the permittee, a follow up inspection will be conducted for verification. Upon correction of all deficiencies, a letter of acceptance will be issued.

13B-2 Medium Volume Commercial Driveways

Medium Volume commercial driveways are those driveways installed by the permittee or the permittee's contractor to serve land uses such as small subdivisions and apartment complexes, or small businesses. There are no other items to be installed per encroachment permit onto SCDOT's rights-of-way other than the driveway, associated driveway pavement markings, channelization devices, and curb & gutter associated with the driveway. All items are transverse to the rights-of-way and no longitudinal items are included.

Prior to the permittee beginning work, a traffic control plan and sediment and erosion control plan shall be submitted to the RME for approval or included in the encroachment permit package. Also, a preconstruction meeting shall be held with the RME prior to the commencement of work. The agenda for the preconstruction conference should include, at a minimum, the work schedule to include the start work and end work dates within SCDOT's rights-of-way and a contact list of names and phone numbers of the Permittee and superintendent in charge of the daily activities. After the preconstruction conference is held and the traffic control plan and sediment & erosion control plan have been approved, the RME will issue a notice to proceed. The *Manual of Uniform Traffic Control Devices* (MUTCD – latest edition) and the latest edition of the SCDOT *Standard Drawings* shall be used in the development of the traffic control plan.

Upon completion of all work, the permittee shall contact the RME for a final inspection of the work. If the work has been completed satisfactorily, a letter of acceptance will be issued. If the work is not completed satisfactorily, a punch list will be developed noting all deficiencies. Once the deficiencies have been corrected by the

permittee, a follow up inspection will be conducted for verification. Upon correction of all deficiencies, a letter of acceptance will be issued.

13B-3 High and Major Volume Commercial Access Encroachments

High and major volume commercial access encroachments are commercial encroachments that include additional work items within SCDOT's rights-of-way above and beyond driveway construction included in the encroachment permit. These additional items include but are not limited to the following: traffic signals, turn lanes, roadway signage, drainage, resurfacing, roadway widening, cross walks, roadway pavement markings, roadway channelization devices, and etc.

For large commercial access encroachments, the permittee shall use a SCDOT pre-qualified contractor for all work to be completed within SCDOT's rights-of-way. The permittee's contractor shall be responsible for the Quality Control testing and sampling and material certifications as per the SCDOT *Construction Manual* (latest edition) and SCDOT's *Standard Specifications for Highway Construction* (latest edition).

A traffic control plan and sediment & erosion control plan shall be included in the encroachment permit package and must be approved prior to the beginning of the work. Also, a preconstruction meeting shall be held with the RME prior to the commencement of work. The agenda for the preconstruction conference should include, at a minimum, the work schedule to include the start work and end work dates within SCDOT's rights-of-way and a contact list of names and phone numbers of the Permittee and superintendent in charge of the daily activities. After the preconstruction conference is held and the traffic control plan and sediment & erosion control plan have been approved, the RME will issue a notice to proceed. The *Manual of Uniform Traffic Control Devices* (MUTCD – latest edition) and the latest edition of the SCDOT *Standard Drawings* shall be used in the development of the traffic control plan.

Upon completion of all work, the permittee shall contact the RME for a final inspection of the work. If the work has been completed satisfactorily, a letter of acceptance will be issued. If the work is not completed satisfactorily, a punch list will be developed noting all deficiencies. Once the deficiencies have been corrected by the permittee, a follow up inspection will be conducted for verification. Upon correction of all deficiencies and all materials are certified, a letter of acceptance will be issued.

CHAPTER 14 – LANDSCAPING GUIDELINES

14A Introduction

This chapter serves as a guide for the placement of plantings within SCDOT rights-of-way. The values and criteria specified in these guidelines are intended to assist the designer in developing landscaping projects.

14A-1 Highway Terms

Backslope – The side slope created by the connection of the ditch bottom or shelf, upward and outward, to the natural ground.

Central Business District – A central business district (CBD) is the commercial, business and transportation network center of a city or town. In larger cities, it is often synonymous with the city's "financial district." Geographically, it often coincides with the "city center" or "downtown," but the two concepts are separate: many cities or towns have a central business district located away from its commercial or cultural city center or downtown. CBDs typically have development immediately adjacent to the right-of-way line with sidewalks from the curb to the business fronts.

Clear Zone – The unobstructed, traversable area provided beyond the edge of the through traveled way for the recovery of errant vehicles. The clear zone includes shoulders, bike lanes, and auxiliary lanes, except those auxiliary lanes that function like through lanes. For more detailed information regarding the application of clear zone, reference AASHTO's *Roadside Design Guide*.

Curb and Gutter – A curb element combined with a gutter section to provide an improved longitudinal drainage system.

Curb Extension – A feature that extends from the sidewalk into the pavement at an intersection, at the termination of on-street parking, or at a mid-block crossing. This shortens pedestrian crossing distance at crosswalks and is also known as a *curb bulb*, *neckdown*, or *bulbout*.

Design Speed – Design Speed (DS) is a selected speed used to determine the various geometric design features of the roadway. The project design speed will be utilized when landscaping is proposed as part of a roadway improvement project.

Foreslope – This is the side slope in a cut section created by connecting the shoulder to the ditch hinge point, downward and outward.

Hinge Point – The point where the height of fill and the depth of cut are determined. For fills, the point is located at the intersection of the shoulder and the fill slope. For cuts, the hinge point is located at the toe of the back slope.

Horizontal Clearance – The lateral offset distance from a designated point to a vertical roadside element. Measured from face of tree/planting to back of curb where curb is present. Measured from face of tree/planting to edge of pavement where no curb is present. Face of tree/planting location is estimated based on the tree's Diameter at Breast Height (DBH) at maturity.

Islands – An island is a defined area between traffic lanes used for control of vehicle movements. Islands also provide an area for pedestrian refuge and traffic control devices. Within an intersection, a median or an outer separation is also considered an island. (Channelizing Islands) Control and direct traffic movements into the proper paths for their intended use are an important part of intersection design. Confusing traffic movements resulting from spacious areas may be eliminated by the conversion of unused areas into islands that leave little to driver discretion. Channelizing islands may be of many shapes and sizes, depending on the conditions and dimensions of the intersection. A common form is the corner triangular shape that separates right-turning traffic from through traffic. Central islands may serve as a guide around which turning vehicles operate. (Divisional Islands) Often are introduced on undivided highways at intersections. They alert the drivers to the crossroad ahead and regulate traffic through the intersection. These islands are particularly advantageous in controlling left turns at skewed intersections and at locations where separate roadways are provided for right-turning traffic. (Refuge Islands) Aid and protect pedestrians and bicyclists who cross the roadway. Raised-curb corner islands and center channelizing or divisional islands can be used as refuge areas. Refuge islands are used primarily in urban areas.

Line of sight – Line of sight is the visible path of travel from your vehicle to the target area. This line should not be blocked by plantings. Reference SCDOT roadway design guidelines for additional details.

Median – The area of a divided highway separating the traffic into opposing directions. Medians may be Flush, Raised, or Earthen Depressed.

OGEE Curb – The OGEE curb is a gently rounded curb approximately 4 inches high. Vehicles can easily traverse over the curb. It can be used for roadside access (e.g., driveways) where curb cuts are not desired. Where drainage structures are required, provide a special detail to transition the OGEE curb to SCDOT standard drainage inlets.

Planting strip – An unpaved area within the right-of-way that separates the street from the sidewalk; serves as a buffer between vehicles and pedestrians.

Right-of-way – The land secured and reserved by the Department for the construction and maintenance of infrastructure.

Shoulder – The portion of a roadway contiguous to the travel way for the accommodations of stopped vehicles, for emergency use, and for lateral support of pavement.

Sight distance – (Stopping Sight Distance) The available sight distance on a roadway that is sufficiently long to enable a vehicle traveling at or near the design speed to stop before reaching a stationary object in its path. (Intersection Sight Distance) The sight distance required within the corners of intersections to safely allow a variety of vehicular access or crossing maneuvers based on the type of traffic control at the intersection.

(Decision Sight Distance) The distance needed for a driver to detect an unexpected or otherwise difficult-to-perceive information source or condition in a roadway environment that may be visually cluttered, recognize the condition or its potential threat, select an appropriate speed and path, and initiate and complete complex maneuvers.

Sloping Face Curb – Sloping curbs are generally 6 inches in height with a sloped face (4H:5V). Sloping curbs will allow a vehicle to mount the curb and can be used with any design speed. If the design speed is greater than 45 miles per hour, place the curb on the outside edge of the shoulder. For freeways and ramps, only use sloping curbs at the outside edge of the shoulder, where necessary. With this curb type, the designer needs to select the appropriate drainage structure.

Street furniture – Physical features included as part of the streetscape, such as benches, bike racks, lighting, trash receptacles, bollards, and banners.

Travel Lane – The portion of the roadway for the movement of vehicles, exclusive of shoulders and auxiliary lanes.

Valley Gutter – A paved longitudinal element placed at the roadway edge to control drainage.

Vertical Face Curb – Vertical curbs are normally 6 inches in height with steep vertical faces (1H:6V). Do not use vertical curbs adjacent to travel lanes where design speeds exceed 45 miles per hour.

9 inch x 15 inch Curb – The 9 inch x 15 inch curb can be used with raised medians where the adjacent pavement is sloped away from the median. It is a sloping curb, which can be easily mounted.

14A-2 Landscape Terms

Balled and burlapped (B&B) – Plant dug and removed from the ground for replanting, with the roots and soil wrapped in burlap.

Cultivar – Cultivated variety of a plant. Cannot be reproduced without human assistance. Compared to *variety*.

Diameter at Breast Height (DBH) – Acronym for anticipated tree diameter at maturity. Measured at breast height, 4.5 feet above ground.

Ground Cover – Plants or groups of plants used in landscaping to cover the ground. Ground covers include herbaceous perennials, ornamental grasses, and vines.

Indigenous/Native plant – A species that occurs naturally in a particular region, ecosystem and/or habitat without direct or indirect human actions.

Integrated Roadside Vegetation Management (IRVM) – System of managing plant communities in which compatible and incompatible vegetation is identified, action thresholds are considered, control methods are evaluated and selective controls are implemented to achieve a specific objective.

Invasive species – Non-native organisms likely to spread, disrupting the natural balance of an ecosystem.

Large Tree – A tree with a caliper of greater than 4 inches DBH at maturity.

Ornamental Grass – Grass or grass-like plants used in landscaping.

Plantings – A generic name that is inclusive of all types of plants addressed within this guide (trees, shrubs, grasses, vines, and/or flowers).

Shrub – A woody plant typically with a number of stems arising from the base, and usually smaller than a tree.

Small Tree – A tree with a caliper of less than or equal to 4 inches DBH at maturity. When a tree with multiple trunks or a group of small trees close enough will have at maturity a combined cross-sectional area greater than 4 inches, then it will be offset as a large tree.

Tree – Woody perennial usually having one dominant trunk and a mature height greater than 16 feet.

Trunk flare (root flare) – Transition zone from trunk to roots where the trunk expands into the structural roots (also root collar).

Variety – Naturally occurring subdivision of a species having a distinct difference and breeding true to that difference. Compared to *cultivar*.

Vine – A plant whose stems requires support and which climbs by tendrils, twining, or creeps along the ground.

14B Policy

The landscape plan must be designed by a professional landscape architect licensed in South Carolina or other qualified designer as approved by the Department.

14B-1 Plan Content

A scaled drawing with plan sheets must be provided for Department review. Additional information may be requested by the Department in order to complete the review. The plan sheets must include the following items:

- Plant Materials List with common and botanical names
- Projected mature DBH of the plants
- Projected mature height and spread of the plants
- Plant quantities and the approximate planting location
- Approximate location of existing vegetation and other site elements
- Location and posted speed of the highway
- Outdoor Advertising sign (billboard) locations within the vicinity
- Location of Adjacent Businesses

- Location and Identification of All Adjacent Property Owners
- Average Daily Traffic (ADT)
- Location of guardrail
- Location of curb and gutter
- Slope type (cut or fill)
- Work Zone Traffic Control Plan (in accordance with Section 7 of the *SCDOT Vegetation Management Guidelines*)

14B-2 Encroachment Permit

Reference the *SCDOT Vegetation Management Guidelines* for guidance related to landscaping projects. An encroachment permit is required for landscaping work performed by Non-SCDOT Entities on the highway rights-of-way. Encroachment permit applicants shall furnish, install, and maintain all plantings.

The Resident Maintenance Engineer shall forward the application packet to their respective district for review. If necessary, the District Permit Engineer (DPE) will coordinate a review with the landscape architect through the State Permit Engineer located in the Preconstruction Support Office. The DPE will review all comments prior to responding to the applicant. No work will be allowed until the formal permit is approved by the Department and returned to the applicant. Special provisions may be stated in the encroachment permit application as per the discretion of the reviewers.

14B-3 Maintenance/Maintenance Agreement

See the *SCDOT Vegetation Management Guidelines* with regards to maintenance and maintenance agreements.

14B-4 Legal

The Department will exercise care in maintenance, construction, or reconstruction to avoid unnecessary damage. SCDOT shall not be responsible to protect plantings or irrigation systems against damage or theft. If subsequent changes to the highway require removal of plantings, this must be done by the Non-SCDOT Entity at their own expense. If in the future a planting's growth obstructs the view of signs or interferes with the sight distances of approaching traffic, the Department will require the Non-SCDOT Entity to remove, relocate, or prune the plantings to eliminate this obstruction at their expense.

SCDOT will have the right, but not the obligation, to review and comment upon the encroachment permit plans. SCDOT's review comments shall be addressed in written form prior to approval of the permit. This review and comment is fully discretionary; however, no review or comment nor any failure to review or comment shall operate to absolve the applicant of its responsibility to defend and hold harmless SCDOT from all liability and claims resulting from the project, including but not limited to any impairment or blockage of visibility of an existing property owner, or to shift responsibility or liability to SCDOT.

14C Guidance

14C-1 Planting Selection

A list of suggested plant species can be found in the Landscaping Guidelines section on the *SCDOT Roadway Design Website*. Species were selected based on characteristics that are suitable for right-of-way planting. Consideration was given to root structure, canopy shape and size, amount of tree litter, and hardiness in an urban environment. Additional species may be submitted to the Department's Landscape Architect for consideration based on the above characteristics (See the *Plant Consideration Form* in the Landscaping Guidelines section on the *SCDOT Roadway Design Website*). The Department has identified invasive species of plants that are not allowed within SCDOT rights-of-way. These plantings can be found in the Landscaping Guidelines section on the *SCDOT Roadway Design Website*.

14C-2 Planting Location

- Minimum horizontal clearances for trees and shrubs are specified in *Tables 14-1, 14-2 and 14-3*.
- Place plantings so that no interference will occur at maturity with highway safety, traffic visibility, traffic control devices (signals, signs, etc.) and applicable sight distances. Evaluate stopping, decision, and intersection sight distances using SCDOT roadway design guidelines. For roundabouts, evaluate sight distances in accordance with National Cooperative Highway Research Program (NCHRP) Report 672.
- Review all driveways to ensure the plantings do not interfere with traffic visibility and applicable sight distances.
- Ensure no plantings are located within the slopes of ditches or swales. Offset plantings 2 feet from the top or bottom of slope, measured horizontally from face of planting at maturity.
- Plantings on the fill portion of retaining walls shall be no closer to the wall than one times the height of the wall for plantings greater than 4 inch DBH at maturity and half the height of the wall for plantings less than or equal to 4 inch DBH at maturity. Additional offset distance may be required for walls with more complex designs. On the cut side plantings shall be a minimum of 4 feet from the furthest extension of the footing.
- At bridge locations, no planting shall be placed within the bridge right-of-way. This is typically 75 feet from the bridge ends and 75 feet from the centerline.
- Upon meeting the horizontal clearances in *Tables 14-1 and 14-2*, no trees are allowed within 2 feet of sidewalk and drainage structures. Trees in close proximity to sidewalk and drainage structures require special attention to ensure the root system does not damage these features. All species of oak trees shall require a root barrier system when placed within 4 feet of these features. The Department may require a root barrier system for other species greater than 4 inch DBH at maturity when placed within 4 feet from these features.

- Consider future plans for sidewalk when determining the placement of plantings.
- When the design includes both trees and pedestrian facilities it is SCDOT's preference that the trees be placed as close as possible to the R/W (trees behind the sidewalk). This is to provide optimum visibility for pedestrians and motorists and improves visibility for traffic signage.
- Ground covers are allowed within the horizontal clearances specified in *Tables 14-1, 14-2 and 14-3* and must be selected to have a mature height of 2.5 feet or less.
- No trees, only ground covers will be allowed within curb extensions, divisional islands, channelization islands, and refuge islands.
- For locations with guardrail, place plantings such that there is a minimum clearance of 8 feet behind the guardrail for maintenance and repair (measured from back of posts to the foliage line or face of trunk depending on the plant species). Evaluate the length of need for the guardrail in accordance with the SCDOT roadway design guidelines to ensure the guardrail adequately shields the planting. No ornamental grasses, ground covers, shrubs, or trees may be planted in front of, or directly under, guardrails.
- Landscaping shall not impair visibility windows of permitted Outdoor Advertising (ODA) structures. Plantings in the vicinity of permitted Outdoor Advertising structures shall be approved by the Regional Outdoor Advertising Coordinator prior to the approval of the landscaping plans.
- Ensure ground mounted landscape lighting is placed to eliminate glare towards motorists. Utilize cutoff shields to control the direction of the light.

14C-3 Installation

- Furnish and install landscaping in accordance with the current version of the *SCDOT Standard Specifications for Highway Construction*.
- All landscaping work performed by Non-SCDOT Entities within the SCDOT right-of-way is to be in compliance with all local ordinances/requirements and all state environmental regulations.
- Ensure the installation is performed under the supervision of the SCDOT with an approved traffic control plan. For encroachment permits, it will be the responsibility of the Non-SCDOT Entity to develop a Work Zone Traffic Control Plan in accordance with the *SCDOT Vegetation Management Guidelines*.
- The exact location of all utility lines must be verified prior to commencement of digging operations by contacting South Carolina 811. Coordinate with the SCDOT District Office prior to commencement of any work within 800 feet of a traffic signal.
- "Planted Median Subsurface Drainage" is required at all locations where new raised planted medians are installed and shall be designed and constructed in accordance with the current version of applicable *SCDOT Standard Drawings* regardless of the presence of irrigation.

- See the *SCDOT Standard Landscaping Details* found in the Landscaping Guidelines section on the *SCDOT Roadway Design Website* for additional notes and details.
- Staking shall be removed by the permittee/Non-SCDOT Entity at the end of the plant establishment period, not to exceed one (1) year.

14C-4 Irrigation Systems

The Department's preference is for the permittee/Non-SCDOT Entity to provide irrigation on all projects; however, exceptions may be made dependent upon the cost, scope, maintenance, location, and other considerations. Design irrigation systems for landscaping so that irrigation can be achieved with minimal system components encroaching on the right-of-way. When encroachment is unavoidable, include details of the irrigation system in the landscaping plans and install in accordance with the *SCDOT Utilities Accommodation Manual* and the Irrigation System Special Provision. A sample Special Provision can be found in the Landscaping Guidelines section on the *SCDOT Roadway Design Website*, and may be edited to meet the needs of a specific project. Ensure irrigation water does not spray or drain onto the roadway, sidewalk, or any traffic signal components, including but not limited to the traffic signal cabinet, pedestrian buttons, and/or the traffic signal meter box. Drip irrigations systems are suggested for urban areas. The correction of any problem involving irrigation water draining or spraying onto the roadway will be the responsibility of the Non-SCDOT Entity, regardless of the Department's approval of the permit and/or landscaping plan. Shut off sprinkler systems that irrigate the right-of-way during sub-freezing temperatures as a routine preventive measure.

Table 14-1: Horizontal Clearances for Shrubs

Classification	Design Speed ²	Minimum Horizontal Clearance
Urban	Less than or equal to 35 mph	2-ft. ¹ Roadside 2-ft. ¹ Median
Urban	Greater than 35 mph	6-ft. ¹ Roadside 6-ft. ¹ Median
Rural	All Speeds	2-ft beyond shoulder width
Interstate	All Speeds	30-ft. Roadside Not allowed in median

Notes:

- 1) Measured from the foliage line of shrub to back of curb where curb is present. Foliage line location is estimated based on the shrubs size at maturity. Place planting 2 feet beyond the required shoulder width where no curb is present. Additionally, when on-street parking or paved shoulder is present the offset may be reduced to a 2 feet minimum assuming the values above are met from the edge of the travel way.
- 2) For retrofit projects, Posted Speed may be utilized in lieu of Design Speed with Department approval.

Other Requirements:

- Regardless of the values above, no shrub greater than 2.5 feet in height shall be located within sight lines.
- Clear zone defined by SCDOT roadway design guidelines. When determining clear zone, use the upper range from the chart and include the horizontal curve adjustment factors.
- Shoulder width based on roadway classification defined by SCDOT roadway design guidelines.

Table 14-2: Horizontal Clearances for Small Trees

Classification	Design Speed ²	Minimum Horizontal Clearance
Urban	Less than or equal to 35 mph	4-ft. ¹ Roadside 4-ft. ¹ Median
Urban	40 – 45 mph	8-ft. ¹ Roadside 8-ft. ¹ Median
Urban	Greater than 45 mph	Outside clear zone
Rural	All Speeds	Outside clear zone
Interstate	All Speeds	Outside clear zone

Notes:

- 1) Measured from face of tree/planting to back of curb where curb is present. Where no curb is present, place tree 2 feet beyond the required shoulder width. Face of tree/planting location is estimated based on the tree's DBH at maturity. Additionally, when on-street parking or paved shoulder is present the offset may be reduced to a 4 feet minimum assuming the values above are met from the edge of the travel way.
- 2) For retrofit projects, Posted Speed may be utilized in lieu of Design Speed with Department approval.

Other Requirements:

- See list of suggested plantings in the Landscaping Guidelines section on the *SCDOT Roadway Design Website*.
- Clear zone defined by SCDOT roadway design guidelines. When determining clear zone, use the upper range from the chart and include the horizontal curve adjustment factors.
- Shoulder width based on roadway classification defined by SCDOT roadway design guidelines.

Table 14-3: Horizontal Clearances for Large Trees

Classification	Design Speed ²	Minimum Horizontal Clearance
Urban CBD	Less than or equal to 25 mph	4-ft. ¹ Roadside 4-ft. ¹ Median
Urban	Less than or equal to 35 mph	6-ft. ¹ Roadside 8-ft. ¹ Median
Urban	Greater than 35 mph	Outside clear zone
Rural	All Speeds	Outside clear zone
Interstate	All Speeds	Outside clear zone

Notes:

- 1) Measured from face of tree/planting to back of curb where curb is present. Where no curb is present, place tree 2 feet beyond the required shoulder width. Face of tree/planting location is estimated based on the tree's DBH at maturity. Additionally, when on-street parking or paved shoulder is present the offset may be reduced to a 4 feet minimum assuming the values above are met from the edge of the travel way.
- 2) For retrofit projects, Posted Speed may be utilized in lieu of Design Speed with Department approval.

Other Considerations:


- See list of suggested plantings in the Landscaping Guidelines section on the *SCDOT Roadway Design Website*.
- Clear zone defined by SCDOT roadway design guidelines. When determining clear zone, use the upper range from the chart and include the horizontal curve adjustment factors.
- Shoulder width based on roadway classification defined by SCDOT roadway design guidelines.

APPENDIX

Appendix A

Drawings


Typical Commercial One-Way Driveway.....	A-1
Typical Access to Outparcel – #1.....	A-2
Typical Access to Outparcel – #2.....	A-3
Median Opening Design.....	A-4
Median Nose Design.....	A-5
Vertical Profile of Intersection of Street or High Volume Driveway	A-6
Channelizing Island Design.....	A-7
Typical Right-In, Right-Out Driveway Design.....	A-7.1
Left-Turn Lane Widening.....	A-8
Roadway Widening Typical Adjacent to School Sites	A-9
Roadway Widening Typical Adjacent to School Sites	A-10
On-Street Parking Configurations	A-11



(DRAWING NOT TO SCALE)


TYPICAL COMMERCIAL HIGH TURNOVER
OR ONE WAY DRIVEWAY

FIGURE A-1




TYPICAL ACCESS TO OUTPARCEL #1

FIGURE A-2



TYPICAL ACCESS TO OUTPARCEL #2


FIGURE A-3



- M1 = Median Width measured between the two edges of the inside travel lane.
M2 = Width of divisional island (flush, raised-curb, depressed) remaining after the width of the left-turn (if present) has been subtracted from the median width (M1).

MEDIAN OPENING DESIGN


FIGURE A-4



- L = Length of median opening.
- M1 = Median Width measured between the two edges of the inside travel lane.
- M2 = Width of divisional island (flush, raised-curb, depressed) remaining after the width of the left-turn (if present) has been subtracted from the median width (M1).
- O = Nose offset.
- R1 = Variable, based on design vehicle and median width (M2).
- R2 = $M2/5$ to edge of left-turn lane, where present.
- P = As shown in the figure.

MEDIAN NOSE DESIGN

FIGURE A-5



- 1 See Chapter 15 of the Highway Design Manual for vertical curve options.
- 2 If practical, the gradient of the landing area where vehicles may be stored should not exceed 3 percent.
- 3 Actual field conditions will determine final design .


VERTICAL PROFILE OF INTERSECTION OF STREET OR HIGH / MAJOR VOLUME DRIVEWAY

FIGURE A-6




South Carolina Department of Transportation

Access and Roadside
Management Standards



(a) Street with Curb and Gutter



(b) Road with Shoulders


CHANNELIZING ISLAND DESIGN

FIGURE A-7

NOTES

1. 100 S.F. MINIMUM AREA OF CONCRETE ISLAND.
150 S.F. MINIMUM AREA OF CONCRETE ISLAND WHERE PEDESTRIAN ACCOMMODATIONS ARE REQUIRED.
MINIMUM 12' SIDES AFTER ROUNDING OF CORNERS.
2. ON A ROAD WITH CURB AND GUTTER, OFFSET THE CONCRETE ISLAND A MINIMUM OF 4' FROM THE EDGE OF TRAVELWAY. ON A ROAD WITH SHOULDERS, PROVIDE A MINIMUM OFFSET EQUAL TO THE SHOULDER WIDTH.
3. CONSTRUCT THE CONCRETE ISLAND AND MEDIAN IN ACCORDANCE WITH SCDOT STANDARD DRAWINGS.
ON CURB AND GUTTER ROADWAYS, ALL ADA-REQUIRED DESIGN ELEMENTS SHOULD BE INCLUDED IN ACCORDANCE WITH SCDOT STANDARD DRAWINGS.
4. THIS DESIGN MAY BE ADJUSTED AT THE DISCRETION OF THE DISTRICT TRAFFIC ENGINEER DEPENDING ON VARYING CIRCUMSTANCES AT INDIVIDUAL LOCATIONS SUCH AS WHEN ACCEL/DECEL LANES ARE REQUIRED IN ACCORDANCE WITH THE SC HIGHWAY DESIGN MANUAL.


WHEN CURB IS DROPPED, REFER TO SCDOT STANDARD DRAWINGS FOR CURB TRANSITION DETAILS.



TYPICAL RIGHT-IN RIGHT-OUT DRIVEWAY DESIGN

Left-Turn Lane Widening

Symmetrical and Non-Symmetrical



Posted Speed Limit, s (mph)	Reverse Radius (ft)	Length needed for Turn Lane Development, L1 (ft)	Symmetric	Non-Symmetric
			Taper Length, L2 (ft)	Taper Length, L2 (ft)
30	300	120	120	240
35	480	152	164	327
40	480	152	213	427
45	670	179	360	720
50	670	179	400	800
55	840	201	440	880
60	840	201	480	960

Notes: This table provides the design values for the development of a 12 ft. left turn lane with 16 ft. of widening. The formulas provided can be used to determine the design values for other scenarios.

Symmetrical Widening

$$L1 = \sqrt{W(4R - W)}$$

$$L2 = \frac{W1}{2} * s^2 \quad S \leq 40 \text{ mph}$$

$$L2 = \frac{W1}{2} * s \quad S \geq 45 \text{ mph}$$

Non-symmetrical Widening

$$L1 = \sqrt{W(4R - W)}$$

$$L2 = \frac{W1 * s^2}{60} \quad S \leq 40 \text{ mph}$$


$$L2 = W1 * s \quad S \geq 45 \text{ mph}$$

L1= Turn Lane Development Length
L2= Taper Length
W= Storage Lane Width
W1= Amount of Widening
s= Speed Limit


FIGURE A-8

ROADWAY WIDENING TYPICALS ADJACENT TO SCHOOL SITES

LEFT/RIGHT TURN LANES FOR NEW ACCESS OPPOSITE EXISTING ROAD/DRIVEWAY



LEFT/RIGHT TURN LANES BETWEEN MULTIPLE ACCESS



Reverse Radius and Taper Length Requirements

Speed (mph)	Reverse Radius (ft)	Turn Lane Development Length, L1 (ft)	Amount of Widening and Associated Taper (L2) (Symetrical)					Amount of Widening and Associated Taper (L2) (Non-Symetrical)				
			11 ft	12 ft	14 ft	16 ft	18 ft	11 ft	12 ft	14 ft	16 ft	18 ft
30	300	120	*	*	*	*	*	*	*	210	240	270
35	480	152	*	*	*	*	*	225	245	286	327	368
40	480	152	*	*	*	213	240	293	320	373	427	480
45	670	179	248	270	315	360	405	495	540	630	720	810
50	670	179	275	300	350	400	450	550	600	700	800	900
55	840	201	303	330	385	440	495	605	660	770	880	990


*200 ft. minimum taper length

Right-Turn Lane and Associated Taper Length


Posted Speed Limit	Taper Length (ft)	Turn Lane Length (ft)
< 40 MPH	150	150
45 MPH	180	200
50 MPH	180	200
≥ 55 MPH	200	250

ROADWAY WIDENING TYPICALS ADJACENT TO SCHOOL SITES

LEFT-TURN FOR SINGLE ACCESS



RIGHT-TURN FOR SINGLE ACCESS




Reverse Radius and Taper Length Requirements

Speed (mph)	Reverse Radius (ft)	Turn Lane Development Length, L1 (ft)	Amount of Widening and Associated Taper (L2) (Symmetrical)					Amount of Widening and Associated Taper (L2) (Non-Symmetrical)				
			11 ft	12 ft	14 ft	16 ft	18 ft	11 ft	12 ft	14 ft	16 ft	18 ft
30	300	120	*	*	*	*	*	*	*	210	240	270
35	480	152	*	*	*	*	*	225	245	286	327	368
40	480	152	*	*	*	213	240	293	320	373	427	480
45	670	179	248	270	315	360	405	495	540	630	720	810
50	670	179	275	300	350	400	450	550	600	700	800	900
55	840	201	303	330	385	440	495	605	660	770	880	990

*200 ft. minimum taper length

Right-Turn Lane and Associated Taper Length

Posted Speed Limit	Minimum Taper Length L2 (ft)	Turn Lane Length (ft)
≤ 40 MPH	150	150
45 MPH	180	200
50 MPH	180	200
≥ 55 MPH	200	250



L = given curb length with parking spaces, ft
 N = number of parking spaces over distance L
 A = required distance between face of curb and back of stall assuming that bumper of parked car does not extend beyond curb face, ft
 B = minimum clear distance needed for a parked vehicle to back out of stall while clearing adjacent parked vehicle, ft
 ETW = Edge of Traveled Way

- See SCHDM Figures 21.3A and 21.3C for parking lane widths

ON-STREET PARKING CONFIGURATIONS

FIGURE A-11

Appendix B

SCDOT Personnel Contact Information

HEADQUARTERS:

South Carolina Department of Transportation
955 Park Street
Post Office Box 191
Columbia, South Carolina 29202-0191

The following officials are located in the headquarters building:

Deputy Director for Construction, Engineering, and Planning	(803) 737-7900
Director of Traffic Engineering	(803) 737-1462
Director of Maintenance	(803) 737-1290
Director of Construction	(803) 737-1308
Director of Preconstruction.....	(803) 737-1350
Utilities Engineer	(803) 737-1293

DISTRICT ENGINEERING ADMINISTRATORS AND OTHER DISTRICT PERSONNEL:


District One	1400 Shop Road Columbia, SC 29201	(803) 737-6660
District Two	510 W. Alexander Avenue Greenwood, SC 29646	(864) 227-6971
District Three	252 South Pleasantburg Drive Greenville, SC 29607	(864) 241-1010
District Four	J. A. Cochran Bypass Post Office Box 130 Chester, SC 29706	(803) 377-4155
District Five	Post Office Box 1911 Florence, SC 29501	(843) 661-4710
District Six	6355 Fain Blvd. North Charleston, SC 29406-4989	(843) 740-1665
District Seven	US Route 178 East Bowman Road Drawer 1086 Orangeburg, SC 29116-1086	(803) 531-6850

RESIDENT MAINTENANCE ENGINEERS:

County	Street Address	City, State, Zip	Telephone
01 Abbeville	127 McGowan Avenue	Abbeville, SC 29620	(864) 459-4206
02 Aiken	P. O. Box 2010	Aiken, SC 29801	(803) 641-7665
03 Allendale	P. O. Box 296	Allendale, SC 29810	(803) 584-3465
04 Anderson	4740 Liberty Highway	Anderson, SC 29621	(864) 260-2215
05 Bamberg	P. O. Box 545	Bamberg, SC 29003	(803) 245-5181
06 Barnwell	P. O. Box 366	Barnwell, SC 29812	(803) 259-1141
07 Beaufort	13 Munch Drive	Beaufort, SC 29902	(843) 524-7255
08 Berkeley	P. O. Box 698	Moncks Corner, SC 29461	(843) 761-8481
09 Calhoun	P. O. Box 406	St. Matthews, SC 29135	(803) 874-3231
10 Charleston	6355-C Fain Blvd.	N. Charleston, SC 29406	(843) 740-1655
11 Cherokee	P. O. Box 237	Gaffney, SC 29342	(864) 489-5622
12 Chester	P. O. Box 386	Chester, SC 29706	(803) 377-8101
13 Chesterfield	P. O. Box 649	Chesterfield, SC 29706	(843) 623-2543
14 Clarendon	P. O. Box 26	Manning, SC 29102	(803) 435-4431
15 Colleton	P. O. Box 169	Walterboro, SC 29488	(843) 538-8031
16 Darlington	P. O. Drawer 495	Darlington, SC 29532	(843) 393-6171
17 Dillon	P. O. Box 1009	Dillon, SC 29536	(843) 774-7376
18 Dorchester	P. O. Box 96	St. George, SC 29477	(843) 563-3451
19 Edgefield	P. O. Box 490	Edgefield, SC 29824	(803) 637-6511
20 Fairfield	P. O. Box 261	Winnsboro, SC 29180	(803) 635-4222
21 Florence	P. O. Box 1911	Florence, SC 29501	(843) 661-4715
22 Georgetown	P. O. Box 593	Georgetown, SC 29442	(843) 546-2405
23 Greenville	13 Saluda Dam Road	Greenville, SC 29611	(864) 241-1224
24 Greenwood	510 W. Alexander Ave.	Greenwood, SC 29646	(864) 227-6701
25 Hampton	P. O. Box 278	Hampton, SC 29924	(803) 943-3721
26 Horry	P. O. Box 1663	Conway, SC 29526	(843) 365-2130
27 Jasper	P. O. Box 490	Ridgeland, SC 29936	(843) 726-3431
28 Kershaw	P. O. Box 509	Camden, SC 29020	(803) 432-4358
29 Lancaster	P. O. Box 929	Lancaster, SC 29721	(803) 283-3397
30 Laurens	P. O. Box 750	Laurens, SC 29360	(864) 984-7632
31 Lee	P. O. Box 191	Bishopville, SC 29010	(803) 484-6236
32 Lexington	P. O. Box 70	Lexington, SC 29071	(803) 359-4103
33 Marion	P. O. Box 986	Marion, SC 29571	(843) 431-1130
34 Marlboro	P. O. Box 276	Bennettsville, SC 29512	(843) 479-4161
35 McCormick	Route 2, Box 83T, Road 53	McCormick, SC 29835	(864) 465-2216
36 Newberry	P. O. Drawer 39	Newberry, SC 29108	(803) 276-0554
37 Oconee	P. O. Box 38	Richland, SC 29675	(864) 647-0798
38 Orangeburg	P. O. Box 508	Orangeburg, SC	(803) 531-6870
39 Pickens	P. O. Box 877	Pickens, SC 29671	(864) 859-0039
40 Richland	7201 Fairfield Rd	Columbia, SC 29203	(803) 786-0128
41 Saluda	P. O. Box 715	Saluda, SC 29138	(864) 445-2586
42 Spartanburg	P. O. Box 5706	Spartanburg, SC 29304	(864) 587-4725
43 Sumter	P. O. Box 417	Sumter, SC 29150	(803) 778-5466
44 Union	P. O. Box 458	Union, SC 29379	(864) 427-3575
45 Williamsburg	PO Box 180	Kingstree, SC 29556	(843) 354-7491
46 York	P. O. Box 2932 CRS	Rock Hill, SC 29731	(803) 327-6186

DISTRICT TRAFFIC SIGNAL SUPERVISORS:

District 1	(803) 737-6974
District 2	(864) 227-8651
District 3	(864) 241-1117
District 4	(803) 581-8551
District 5	(843) 365-8251
District 6	(843) 740-1668
District 7	(803) 531-6870
Headquarters	(803) 737-1050



Appendix C

Directions for Completion of Permit Application

Note: Reference the following eight guidelines to the sample permit applications on pages B-2 through B-3. See pages B-4 and B-5 for a checklist and sample sketches.

- 1) A permit number will be assigned by the Department.
- 2) Fill in name and address of applicant (owner or his or her agent). Provide telephone number(s) at which the contact person may be reached 24 hours a day, 7 days a week. Give name of contact person if different from applicant
- 3) Provide name of county, road or route number, and road name if known.
- 4) Provide a detailed description of the type of encroachment (driveway, landscape, subdivision street, etc.).
- 5) Provide description of location. For example, "2.1 miles north of intersection of road S-04-22" or "300 feet west of road S-04-66." This information shall also be included on the drawing as instructed in the permit application checklist.
- 6) Provide applicant's name, signature, and date of application.
- 7) The Department will provide the date by which the work is to be completed.
- 8) The Department will add any special provisions to the permit. For example, "applicant shall erect Department approved stop signs" or "work shall only be done between hours of 9 A.M. and 4 P.M. on weekdays."

Application for Encroachment Permit

S.C. Department of
Transportation
Form 637 (Rev 11/2003)

Permit Nbr: _____

1

Applicant: _____	County: _____
Street: _____	Enter <u>Road/Route</u> And then the corresponding <u>Road Name</u> below:
City: _____	1. _____ 1. _____
State & Zip: _____ 2	2. _____ 2. _____
Phone: _____	3. _____ 3. _____ 3
	4. _____ 4. _____
	5. _____ 5. _____

1. The undersigned applicant hereby applies to the South Carolina Department of Transportation (SCDOT) for a permit for encroachment on State Highway Right of Way as shown and described below:

2. Type of Encroachment: _____ **4**

3. Description of Location: _____

5

(Attach sketch indicating roadway features such as: pavement width, shoulder width, sidewalk and curb and gutter location, significant drainage structure, north arrow, right of way width, and location of the proposed encroachment with respect to the roadway centerline and the nearest intersecting road on the State system.)

4. The undersigned applicant hereby requests the SCDOT to permit encroachment on the SCDOT right of way as described herein. It is expressly understood that the encroachment, if and when constructed, shall be installed in accordance with the sketch attached hereto and made a part hereof.

The applicant agrees to comply with and be bound by the SCDOT's "A Policy for Accommodating Utilities on Highways Rights of way", "Standard Specifications for Highway Construction", the "General Provisions" and "Special Provisions", attached hereto or made a part hereof by reference, during the installation, operation and maintenance of said encroachment within the SCDOT's Right of Way.

The applicant hereby further agrees, and binds his/her/its heirs, personal representatives, successors, assigns, to assume any and all liability for accidents or injuries to persons, or damage to property, including the highway, that may be caused by the construction, maintenance, use, moving or removing of the physical appurtenances contemplated herein, and the applicant agrees to indemnify and hold SCDOT harmless from and against any and all claims for personal injury and/or property damage which may be sustained by any person by reason of the construction, maintenance or existence of said encroachment on the SCDOT's right of way.

Applicant's Name: _____ **6**
(Please print or type)

Date: _____

Applicant's Sig: _____

Title: _____

In accordance with your request and subject to all the provisions, terms, conditions and restrictions stated in the application and the general and special provisions attached hereto, the SCDOT hereby approves your application for an encroachment permit. This permit shall become null and void unless the work contemplated herein shall have been

completed prior to: _____

7,8

(Date received by
Res. Maint. Engr.)

(SCDOT Approval)

(Date)

☐ Resident Maintenance Engineer

☐ State Highway Engineer

☐ District Engineering Administrator


☐ District Maint./Constr. Engineer

Available online at <https://www.scdot.org/business/permits.aspx>

Encroachment Permit Application Checklist

- I. Permit Form: The appropriate completed quadruplicate form is required.
- II. Drawing: At least four copies of a drawing are to be included, giving details of the proposed work and existing conditions and including but not limited to the following:
 - 1) Roadway on which the encroachment is located.
 - 2) Direction and distance to the nearest intersecting State and county roadways, if applicable.
 - 3) North arrow.
 - 4) Drawing to be to scale. For example, 1" = 20' (1:250), 1" = 50' (1:600), etc.
 - 5) Existing and proposed roadway geometry including pavement widths, curves, driveways, etc.
 - 6) Existing and proposed pavement design, if applicable.
 - 7) Existing and proposed drainage features with flow direction.
 - 8) Existing right-of-way and associated property lines.
 - 9) Existing sight distance, if applicable.
 - 10) Existing and proposed structures.
 - 11) Proposed utility work.
 - 12) Traffic Control Plan, if applicable.
 - 13) Erosion control.
- III. Proof of Bonding: Evidence of any required bond must accompany the permit application.
- IV. Stormwater Management and Sediment Control Plan: All applications for encroachment permits that involve bringing stormwater runoff or sediment to the highway for a developed area of 2 acres or more must include a copy of a Stormwater Management and Sediment Control Plan approved by DHEC, the local government, or the conservation district responsible for approving such plans pursuant to The Stormwater Management and Sediment Reduction Act. See S. C. Code Ann. Section 48-14-10, et seq. (Supp. 1995). The plan should include drainage design computations. If the area is less than 2 acres, the application must include a drainage plan with supporting design computations limiting the post construction 10-year peak discharge to the pre-developed 10-year peak.
- V. Bridges, culverts, retaining walls or other significant structures: All applications for encroachment permit that involve these type of structures must include five signed and sealed copies of the Geotechnical Report, Hydrology Report, Construction Plans and Documents, and Structural Design Calculations as outlined in Chapter 13.

Note: Drawing should be submitted on 8½" x 11" or 11" x 17" size paper. A 36" x 22" site plan showing the relationship of the driveways to the circulation plan and the site development may be required. When readily available, a 36" x 22" site plan should be submitted initially to facilitate review of the application. An example sketch has been provided below.



SCDOT ACCESS WAIVER

This form is a request for approval of waiver from the access guidelines found in SCDOT's *Access and Roadside Management Standards*. This form shall be accompanied by an Encroachment Permit Application.

Submitted By: _____ Date: __/__/__

To: _____
Resident Maintenance Engineer

PROJECT CHARACTERISTICS

County: _____ City: _____

Road/Route: _____ Description of Location: _____

Work Type: _____

Type of Terrain: (Level / Rolling / Mountainous)

Posted Speed Limit of Road: _____ (mph)

Average Daily Traffic of Road: _____

Driveway Classification:

- | | | | |
|-------------------------------------|--|--------------------------------------|---------------------------------------|
| <input type="checkbox"/> Low Volume | <input type="checkbox"/> Medium Volume | <input type="checkbox"/> High Volume | <input type="checkbox"/> Major Volume |
| 1-20 trips/day | 21-600 trips/day | 601-4,000 trips/day | >4,000 trips/day |
| 1-5 trips/hour | 6-60 trips/hour | 61-400 trips/hour | >400 trips/hour |

Site Land Use: _____

CHECK APPROPRIATE BOX(ES) FOR ACCESS WAIVER(S)

- | | |
|--|--|
| <input type="checkbox"/> Sight Distance | <input type="checkbox"/> Driveway Grade |
| <input type="checkbox"/> Driveway Spacing | <input type="checkbox"/> Driveway Width / Radius |
| <input type="checkbox"/> Corner Clearance | <input type="checkbox"/> Driveway Throat Length |
| <input type="checkbox"/> Driveway Location | <input type="checkbox"/> _____ |

DESCRIBE ELEMENT(S) FOR ACCESS WAIVER(S)

(Attach additional sheets as needed) _____

(Attach additional sheets as needed) _____


(Attach additional sheets as needed)

Resident Maintenance Engineer	HQ Section Head/DEA	Other _____
<input type="checkbox"/> Recommended	<input type="checkbox"/> Recommended	<input type="checkbox"/> Recommended
<input type="checkbox"/> Not Recommended	<input type="checkbox"/> Not Recommended	<input type="checkbox"/> Not Recommended

(Attach additional sheets as needed)

☐ **Denied**

Permit Appeal Review Flowchart



Appendix D

Engineering Directives

All SCDOT Engineering Directives are available on the SCDOT internet website at the following web address:

<https://www.scdot.org/business/business-landing.aspx>



The screenshot shows the SCDOT website interface. At the top is a navigation bar with links: Home, DOT Resources, Disclaimer, Contact Us, Site Map, Search, and Go!. Below this is a secondary navigation bar with links: Inside SCDOT, Getting Around in SC, Doing Business with SCDOT, Public Forum, and Community Service. The main content area is titled 'Doing Business with SCDOT' and features a sidebar with various links categorized under Construction Letting, Permits, Contractor/Consultant, Construction, Materials and Research, Road Design, and Bridge Design. The main content area is titled 'State Highway Engineer Engineering Directive Memorandums' and includes a photograph of a highway construction site. The text explains that the SCDOT state highway engineer sets engineering policy and direction, which requires compliance by the appropriate engineering divisions and all other providers of service to the Engineering Division, such as consultants and contractors. The state highway engineer issues engineering directive memorandums containing the procedures for carrying out engineering policy. Engineering directive memorandums are reviewed annually. It also provides contact information for the State Highway Engineer's office at (803)737-7900 or fill out the EDM help form. A link is provided for an index of the engineering directive memorandums as well as all engineering directive memorandums are provided in Adobe Reader Format. Below this is a section titled 'All Engineering Directive Memorandums' with a table listing the memorandums.

State Highway Engineer Engineering Directive Memorandums

The SCDOT state highway engineer sets engineering policy and direction, which requires compliance by the appropriate engineering divisions and all other providers of service to the Engineering Division, such as consultants and contractors. The state highway engineer issues engineering directive memorandums containing the procedures for carrying out engineering policy. Engineering directive memorandums are reviewed annually.

If you have questions about engineering directive memorandums, please call the State Highway Engineer's office at (803)737-7900 or fill out the [EDM help form](#).

A [index of the engineering directive memorandums](#) as well as all engineering directive memorandums are provided in [Adobe Reader Format](#).

Select a engineering directive memorandum category from the list below. Then select the view button. Your changes will appear in the table below.

All Directives

EDM	Effective Date	Revision Date	Title
1	11/21/2003	None	Development of Department of Transportation Engineering Directives
2	11/21/2003	None	Fiscal and Maintenance Responsibilities for Traffic Signal Installations on the State Highway System

Appendix E

Frequently Asked Questions for Landscaping Irrigation and Maintenance

As SCDOT moves forward to enhance SC highways, we have considered the need for irrigation and long-term maintenance. In this regard, our State Highway Engineer is requiring that all landscaping projects on the Department's R/W with extensive landscaping have provisions for maintenance including irrigation systems. We encourage the use of irrigation systems that will reduce hand watering of landscaping on our R/W. Applicants for encroachment permits should refer to the requirements in Section 4E-2 in the Access & Roadside Standards handbook.

1. What determines an extensive landscape project, the size of the project or the dollars spent on the project? *Both--SCDOT determines this on a case-by-case basis. **When it is practical and cost effective to install an irrigation system, the system should be incorporated into your project. The cost of the irrigation system can be included in the itemized list of the Project Cost. If the cost of the irrigation system exceeds the cost of the total landscaping, then it may be more cost effective to hand water the landscaping.***

Irrigation Recommendations for Sample Enhancement Projects

- A. My streetscape enhancement project (on DOT R/W) includes some street tree planting, but a majority of the cost of the project involves new sidewalks, light poles and other street furniture. Do I need to include a sprinkler irrigation system? *A sprinkler irrigation system (or a drip system) is recommended. If the landscaping is not spread out over several blocks, the irrigation system would probably be cost-effective during the sidewalk construction. If an irrigation system is not included, then you will need to stipulate some type alternative watering of the landscaping. These alternatives include watering by city crews on a regular basis or using "gatorbags" to assist in long-term watering operations.*
 - B. My bikeway/landscaping or recreational path/landscaping enhancement project involves street tree planting, but it is spread over a length of several miles. Do I need to include a sprinkler irrigation system? *A sprinkler irrigation system (or a drip system) probably would not be cost effective over that distance. If an irrigation system is not included, then you will need to stipulate some type alternative watering of the landscaping. These alternatives include watering by city crews on a regular basis or using "gatorbags" to assist in long-term watering operations.*
 - C. My railroad depot restoration project contains a substantial amount of landscaping on the grounds. Do I need to include a sprinkler irrigation system? *Yes. A location such as this would already have a water hook up and there would be no need for a well to supply water.*
2. My enhancement project is not on SCDOT right-of-way. Am I still required to include arrangements for irrigation for extensive landscaping in my project? ***Yes, in order for us to ensure that the landscaping will be watered.***
 3. What will the SCDOT require if the area is in a location where there is no water hook up/connection? ***In this type of situation, a well can be dug, and the cost can be included in the itemized list of the Project Cost. For example, Adopt-An-Interchange projects often involve extensive landscaping in a concentrated area, and therefore sprinkler irrigation systems are strongly recommended.***

4. Will the SCDOT allow us to include the cost of water and the long-term cost of the maintenance of the sprinkler irrigation system in the expenses in our cost estimate? No, the SCDOT can only provide funds for initial installation costs. Any type of long-term maintenance, including landscape maintenance, should not be included in the itemized list of the Project Cost.

Additional guidance on landscaping can be found on the SCDOT website at <http://www.scdot.org/community/Landscapeguidelines.shtml>

SCDOT Home | DOT Resources | Disclaimer | Contact Us | Site Map | Search Go!

Inside SCDOT | Getting Around in SC | Doing Business with SCDOT | Public Forum | Community Service

Community Service Quicklinks Go!

Motorist Assistance
[SCDOT Incident Response](#)

Youth Outreach
[Youth Corps Program](#)
[Summer Trans. Inst. Program](#)
[Tech. & Trans. Futures Prog.](#)
[Coop. Education Program](#)
[Safe Routes to School](#)

Adopt-A-Highway
[Getting Started](#)
[Group Leader Guidelines](#)
[County Coordinators](#)
[One Time Pick-Up Program](#)

Transportation Enhancement Program
[General Information](#)
[Application & Instructions](#)
[Metropolitan Area](#)
[Rural Area Projects](#)
[Adopt an Interchange](#)

Touring Routes
[Heritage Corridor](#)
[Scenic Byways](#)
[Bicycle and Pedestrian Routes](#)

Roadside Beautification
[Wildflower Program](#)
[Anticipated Blooming](#)
[Wildflower Directory](#)
[Wildflower Photo Gallery](#)
[Keep It Beautiful Tag](#)
[Landscaping Guidelines](#)

Highway Beautification Landscaping Guidelines

The South Carolina Department of Transportation cooperates with organizations desiring to undertake projects to beautify sections of highway rights-of-way. The guidelines contained in the Access and Roadside Access Manual establish a framework for preparing design work for such projects. For more information about these guidelines download our [Access and Roadside Management Manual \(54Kb\)](#).

Related Topics

[Access and Roadside Management Manual \(roadsidemanual.pdf 54Kb\)](#)

[Adopt-an-Interchange](#)

[Suggestions for Street Trees/Sidewalk Plantings \(street_tree_selection_guide.pdf 266Kb\)](#)

[Roadside Plants to Avoid \(plants_to_avoid.pdf 18Kb\)](#)

[South Carolina Forestry Commission "Tree Care and Urban Forestry"](#)

You will need [Adobe Reader](#) to view the pdf files above.

Appendix F

Land Use	50 Peak Hour Directional Trips*
Single Family Home	45 units
Apartments	75 units
Condominiums/Townhouses	95 units
Mobile Home Park	85 units
Shopping Center – Gross Leasable Area (GLA)	3,000 sq. ft.
Fast Food Restaurant With drive-in – Gross Floor Area (GFA)	1,500 sq. ft.
Gas Station with Convenience Store	4 fueling positions
Banks w/drive-in (GFA)	1,000 sq. ft.
General Office	33,500 sq. ft.
Medical/Dental Office	14,500 sq. ft.
Research & Development	35,500 sq. ft.
Light Industrial / Warehousing (GFA)	92,500 sq. ft.
Manufacturing Plant (GFA)	72,000 sq. ft.

*Rates/Equations used to calculate above thresholds are found in the 7th Edition of the *ITE Trip Generation Manual* for the P.M. Peak hour of the adjacent street.