

BRIDGE PACKAGE 14

Design-Build

Cherokee County, South Carolina

Contract ID 1162220



Submitted by:



October 24, 2022

For ease of reference and navigation [Blue Bold Underlined Text](#) indicates links to various items in the Appendix.

Easily Navigate to Previous View:

To return to PREVIOUS VIEW, click ALT + left arrow. You can also set your PDF viewing preferences by following these steps:

- 1) View
- 2) Show/Hide
- 3) Toolbar Items,
- 4) Show Page Navigation Tools
- 5) Check “Previous View”.

A back button will appear on your toolbar and can be used to go directly to your previous view.



Bookmarks are also set for your convenience



NAVIGATION

4.1.1. PROJECT DELIVERY & APPROACH

Featured Team's Approach


SCDOT's Bridge Package 14 will provide important infrastructure upgrades to multiple bridges in Cherokee County. Achieving the project goals requires a strong, experienced design-build (DB) team to partner with the Department to address the specific project challenges, which include:

- ✓ Prioritizing the replacement of S-138 over Goucher Creek bridge
- ✓ Avoiding right-of-way (ROW) acquisition at Kings Mountain National Military Park
- ✓ Maintaining project progress to meet all project schedule goals, including milestone dates
- ✓ Minimizing purchase of new ROW & avoiding/minimizing utility impacts

The Lane Construction Corporation (Lane) and design partner Infrastructure Consulting & Engineering, PLLC (ICE) have partnered as the Lane/ICE Team to provide the resources, knowledge, and experience to deliver this project promptly and efficiently. Our solutions are focused on these issues to provide an optimized design and seamless construction process that showcases innovation and added value to SCDOT with reduced impacts, decreased costs, and a shortened project duration, as demonstrated throughout our proposal.

4.1.1.a. Assurances and ability to complete the project within the required timeframe

In developing our project approach during the procurement phase, the Lane/ICE Team's primary goals are to reduce risks and accelerate the project schedule. Our initial analysis has offered several opportunities to accomplish these goals, focused primarily on advancing the design to produce complete preliminary bridge and roadway packages for submission shortly after contract execution.




The design team is comprised exclusively of ICE employees, who will self-perform all bridge, roadway, geotechnical, and hydraulic design through final design and RFC plans, as well as utility coordination and permitting. This concentrated team does not need to rely on coordination between multiple firms, optimizing processes and communication to maintain continual progress. Following award, weekly coordination will be scheduled between Project Manager (PM) Jeff Nichols, Assistant PM Matt Miltner, Lead Design Engineer Ray Spence, and other designers at the ICE corporate office in West Columbia, where the Team will integrate for effective communication, coordination, and appropriate input between all design disciplines and construction. Through a phased design approach, our Team will optimize the progression of final construction plans and reports for SCDOT's approval with the goal of completing approved RFC plans for all five sites within 12 months of NTP. As the design progresses, the Team will also strategically locate coordination meetings at ICE's Blacksburg field office to simplify collaboration and integration with the SCDOT District 4 construction office.

With the timely resolution and approval of design plans, construction can begin as soon as possible. The Lane/ICE Team's approach emphasizes early completion by leveraging Lane's established strengths and experience, such as performing work simultaneously on multiple bridges sites. We will begin construction with the Unnamed and Goucher Creek bridges, moving then to Kings Creek, and finishing with concurrent work on Horse Creek and Suck Creek, as shown in the map graphic to the right. Our Team is fully prepared to meet the resource challenges

of this project, despite the ongoing nationwide difficulties that the industry is facing regarding labor. Lane's I-85 project in Cherokee County, SC, and I-40/I-77 project in Iredell County, NC, are scheduled for completion in December 2022 and June 2023, respectively, providing a full work force that is ready to mobilize and execute on concurrent bridge sites.

In addition, our strategically located offices will enhance coordination and collaboration between District 4, as well as our field crews and design teams. Coupling this with our established, existing relationships with local suppliers and subcontractors positions the

Lane/ICE Team to efficiently and safely deliver this project within the required timeframe.



4.1.1.b. How the Lane/ICE Team's design minimizes the need for new right-of-way

The Lane/ICE Team has been working throughout the procurement phase to determine strategies to minimize the need for new ROW at all bridge sites. [FATC 2](#), combined with field investigations and extensive hydraulic modeling, have enabled our Team to maintain or reduce the ROW required at all sites compared to the approach in the conceptual plans.

The Team began by modifying the hydraulic models provided in the RFP based on our own data collection and analysis to verify that our bridge lengths meet all hydraulic design criteria. This process facilitated a design that lowers the existing bridge low chord elevation at three sites. Additionally, we verified that the 75 feet of ROW required at each bridge is set correctly, as well as minimized the ROW needed on the roadway approaches through the additional design considerations listed below.

ADDITIONAL DESIGN CONSIDERATIONS

- Using box beams and cored slabs to reduce superstructure depth to minimize raising the existing roadway grade while meeting hydraulic requirements
- Maintaining existing K-Values where allowable to keep roadway profiles as low as possible and embankment footprints as narrow as possible
- Maximizing guardrail limits to maintain 2:1 slopes for longer lengths in higher fill areas
- Utilizing steepened slopes and compressed shoulders with extra length guardrail posts

ICE's design team performed field investigations at all sites to collect the following data:

- ✓ Verify the survey provided in the RFP for accuracy
- ✓ Determine presence of debris accumulation
- ✓ Determine condition of channel
- ✓ Visually inspect channel/bridge performance
- ✓ Determine condition of drainage structures and ditches
- ✓ Measure depth of channel/structure and freeboard
- ✓ Explore opportunities to improve the hydraulic opening




Picture from Hydro Site Visit (S-86 Over Kings Creek)

The NEPA documents assume that new acquisitions will not have negative effects to resources or landowners and will be located within the project study area. During our weekly pursuit meetings, we discussed impacts such as damages to remainders and ingress/egress requirements with our ROW consultant, Colliers Engineering & Design. Any potential issues were addressed and eliminated with our design. The scope of work requires that the Contractor shall, “Provide sufficient right of way to cover all permanent facilities.” Our Team will submit ROW plans for the Department to review that fully comply with all RFP requirements and NEPA assumptions. [Table 4.1.1.b](#) on the following page shows the amount of ROW the Lane/ICE Team anticipates acquiring at each site. Our proposed design results in a net **savings of 0.594 acres** of ROW, which correlates to a **savings of 20%**.



Pictures from Hydro Site Visit (Left to Right: S-106 over Branch of Suck Creek, S-138 over Goucher Creek, & S-56 over Horse Creek)

Conceptual Plans for each site ([APPENDIX A](#)) include “Bumper Sticker” call-out captions that further describe the Team’s approach to reducing the impacts and optimizing the designs. “Bumper Stickers” are also used to denote design exceptions that are included in the RFP and utilized in our design.








**FATC 01:
REMOVED SKEW REQUIREMENT
FROM ALL BENTS**

**FATC 01:
REMOVED SKEW REQUIREMENT
FROM ALL BENTS**

Example "Bumper Sticker" Call Out Captions on Conceptual Plans

Design Team's approach to design and how it minimizes the need for new ROW:

Table 4.1.1.b Bridge Site		Design Approach and Result	Required ROW		Savings
			SCDOT	Lane/ICE	
<u>S-138 over Goucher Creek</u>		<p>Optimized roadway profile:</p> <ul style="list-style-type: none"> Lengthens guardrail to allow 2:1 slopes, minimizing ROW Reduces approach lengths, reducing required ROW from fill impacts <p>Performed extensive hydraulic analysis:</p> <ul style="list-style-type: none"> Demonstrates option to lower existing bridge low chord elevation, which reduces the amount of roadway approach work required 	0.514	0.525	-0.011
<u>S-226 over Unnamed Stream</u>		<ul style="list-style-type: none"> Reduced required ROW by 0.236 acres (10,280 SF) Minimized ROW by eliminating the need to shift stream alignments (<u>FATC 2</u>) Optimized roadway profile to reduce fill, reducing ROW and stream impacts 	0.677	0.441	.236
<u>S-86 over Kings Creek</u>		<ul style="list-style-type: none"> Required ROW reduced by 0.248 acres (10,802 SF) Avoided ROW from National Military Park with minimal alignment shift and roadway profile design Utilized steepest slope allowable with geotechnical information provided in Attachment B Performed extensive hydraulic analysis to demonstrate the existing bridge low chord elevation can be lowered, reducing the amount of roadway approach work required 	0.586	0.338	.248
<u>S-106 over Branch of Suck Creek</u>		<ul style="list-style-type: none"> Required ROW reduced by 0.121 acres (5,270 SF) Utilize <u>FATC 2</u> and steepened slopes per RFP Exhibit 4f, 2.2 to eliminate stream impacts and potential ROW impacts with relocation Obtain permissions for driveway reconstruction outside of bridge maintenance ROW requirements 	0.611	0.490	.121
<u>S-56 over Horse Creek</u>		<ul style="list-style-type: none"> Limited new ROW to bridge maintenance ROW requirements Optimized roadway profile design to reduce approach lengths, reducing required ROW 	0.434	0.434	0

4.1.1.c. Design submittal process

Design Submittal Process and Anticipated Deliverables

The Lane/ICE Team has developed a [CPM Schedule](#) that summarizes the sequence of all design submittal packages, SCDOT reviews, ROW acquisitions, and utility relocations activities. The submittals in [Table 4.1.1.c.](#) were derived from our preliminary [CPM Schedule](#) and illustrate our anticipated submission of no more than two initial submittal packages per month, beginning in March 2023 and ending in December 2023.

Table 4.1.1.c	Design Submittal:	2023												2024	
		J	F	M	A	M	J	J	A	S	O	N	D	J	F
Bridge Site	1. Submittal 000 – Design QC & Submittal Schedule														
	2. Detour Plans														
S-138 over Goucher Creek	3. ROW & Prelim Bridge														
	4. Road & Bridge Final														
S-226 over Unnamed Stream	5. ROW & Prelim Bridge														
	6. Road & Bridge Final														
S-86 over Kings Creek	7. ROW & Prelim Bridge														
	8. Road & Bridge Final														
S-106 over Branch of Suck Creek	9. ROW & Prelim Bridge														
	10. Road & Bridge Final														
S-56 over Horse Creek	11. ROW & Prelim Bridge														
	12. Road & Bridge Final														

Each bridge submittal will be separated by a minimum of 5 days.






■ Production ■ SCDOT Review/ Comment Resolution ■ RFC Plans

All packages will contain the deliverables listed in Exhibit 4z of the RFP for Preliminary/ROW and Final Plans. Shortly after award, the design team will meet with SCDOT's DB Group to review the proposed Design Quality Control Plan, which includes the Design Submittal sequencing procedures and our detailed [CPM Schedule](#) for the Project Design Deliverables (Submittal 000). The flow of submittals is shown in the schedule below. The design submittal process will be monitored using Bluebeam Studio® software, our preferred document control system. This system assigns accountability and ensures SCDOT's review is complete and efficient with key features as described below. Preliminary design and plan production will begin at our own risk immediately after notification of award as further evidence of our commitment to the timely delivery of the Project.



Key Features of Our Design Submittal Process	
✓	Independent QA/QC for all design submittals prior to submission to SCDOT to ensure RFP compliance and minimize SCDOT review comments.
✓	Comprehensive constructability review by the Contractor to improve design and minimize RFIs during construction.
✓	All design submittals will be uploaded to SCDOT's ProjectWise system in PDF format. Plan submissions will be sized at 11"x17" so that they may be printed on a standard printer or any plotter at a specific scale.
✓	The design submission schedule will be posted to SCDOT's ProjectWise site and updated monthly.
✓	Facilitate <u>monthly</u> design meeting/conference call to allow for status updates of the design, to provide a forum for asking questions related to the design during review, and to serve as an opportunity for clarification/discussion of comments.

4.1.2. Innovation and Added Value to SCDOT and the Public

A summary of the Lane/ICE Team's innovative and added value items described below, including those in the previously authorized Formal ATCs, is included in [Appendix B. Quality Credit Matrix.](#)

Bridge Site	Innovation and Added Value Items	Photo of Existing Bridge
<u>S-138 over Goucher Creek</u>	<p>Eliminated interior bent (3-span to 2-span bridge)</p> <ul style="list-style-type: none"> ○ Accelerates bridge construction and reduces cost ○ Reduces potential scour and long-term maintenance ○ Reduces the potential for debris accumulation and long-term maintenance <p>Optimized roadway profile</p> <ul style="list-style-type: none"> ○ Reduces overall approach lengths, which reduces schedule and construction costs <p>Accelerated schedule</p> <ul style="list-style-type: none"> ○ Submit preliminary plans on NTP ○ Begin utility coordination at award to expedite relocation process for Goucher Water (Tri-County Utilities) waterline and AT&T (Both attached to existing bridge) 	
<u>S-226 over Unnamed Stream</u>	<p>Optimized roadway profile (FATC 2)</p> <ul style="list-style-type: none"> ○ Reduces sliver fills on slopes and long-term maintenance ○ Reduces ROW impacts ○ Reduces stream impacts ○ Eliminates need for additional borrow, which reduces hauling on public roads 	
<u>S-86 over Kings Creek</u>	<p>Eliminated skew (FATC 1)</p> <ul style="list-style-type: none"> ○ Eliminates interior bent (3-span to 2-span) <ul style="list-style-type: none"> ▪ Accelerates bridge construction and reduces construction cost ▪ Reduces potential scour and long-term maintenance ▪ Reduces the potential for debris accumulation and long-term maintenance <p>Optimized roadway profile</p> <ul style="list-style-type: none"> ○ Reduces approach length on west side 	
<u>S-106 over Branch of Suck Creek</u>	<p>Optimized roadway profile (FATC 2)</p> <ul style="list-style-type: none"> ○ Reduces ROW impacts ○ Reduces stream impacts ○ Reduces need for additional borrow, which reduces hauling on public roads ○ Reduces overall approach lengths reduces schedule and construction costs 	
<u>S-56 over Horse Creek</u>	<p>Optimized roadway profile</p> <ul style="list-style-type: none"> ○ Reduces approach lengths ○ Reduces overall earthwork 	

Authorized FATCs:

INNOVATION / SOLUTION	ADDED VALUES / BENEFITS				
FATC 1 S-86 Two Span Bridge with No Skew	<ul style="list-style-type: none">Eliminates interior bent on the outside bank of a meander bend that is currently experiencing erosion and damage along the channel bankEliminates potential for local pier scour on the overbankAccelerates bridge constructionReduced construction cost by eliminating interior bent and decreasing quantity of beams to be delivered and placedReduces the potential for debris accumulation				
					
FATC 2 Alternative detail to protect roadway fill slopes	<ul style="list-style-type: none">Significantly reduces and potentially eliminates stream impacts at S-226 over Unnamed Stream and S-106 over Branch of Suck Creek (see Table 4.1.1.b)Reduced impacts to WOUS will allow construction to begin soonerEliminates the need to relocate streams, decreases the required ROW at both sitesReduces mitigation and construction cost				
Site Location	SCDOT Impacts	SCDOT Mitigation Credits/Costs	Proposed Impacts (LF)	Proposed Mitigation Credits/Cost	Cost Savings
S-226 over Unnamed	270	1404 / \$245,700	51	254/\$44,468	\$ 201,232
S-106 over Suck Creek	90	469 / \$82,075	40	208/\$36,402	\$ 45,673
TOTAL SAVINGS					\$ 246,905
FATC 3* Additional pavement option for bridge approaches – CMRB <i>*Evaluating for potential use at each site.</i>	<ul style="list-style-type: none">Cement Modified Recycled Base provides a more efficient pavement section with a Structural Number (SN) higher than RFP proposed pavement options.Increases quality of final product by eliminating the need to perform full depth patching on the roadway approaches since the CMRB operation will reconstruct the entire roadway section.				

Considerations and mitigation strategies to high-risk items:

CRITICAL ISSUES / PROBLEMS / POTENTIAL IMPACT	THE LANE/ICE TEAM MITIGATION STRATEGIES
RISK A. MEETING PROJECT SCHEDULE GOALS AND MILESTONE DATES	
Begin Construction of S-138 over Goucher Creek within 180 days of NTP	<ul style="list-style-type: none"> • Submit ROW and Preliminary Bridge Package on NTP • Coordinate with precast fabricator to provide beam shop drawings in final plans to shorten the procurement/fabrication of beams • Early and frequent coordination with Goucher Water and AT&T to facilitate timely relocations (ICE has met with utilities to incorporate realistic relocation timelines into our CPM Schedule)
Utility Relocations Impact or Delay to Start of Construction	<ul style="list-style-type: none"> • During the pursuit phase, the Lane/ICE Team proactively contacted all potentially impacted utility companies to discuss relocation timelines. These activities and conservative durations are included in our CPM Schedule and were used to help determine the sequence of design and construction.
Appraisals / Condemnation can delay acquisitions and schedule	<ul style="list-style-type: none"> • Prioritize ROW submittals to allow ROW acquisition to begin as soon as possible for critical sites / tracts • Obtain right-of-entry to avoid construction delays • Order appraisal immediately if the property owner is not going to accept the cost estimate
Foundation Installation High-Risk Construction Activity for Schedule	<ul style="list-style-type: none"> • Reduced interior bents by 50% compared to SCDOT conceptual bridge plans. • Drilled shaft locations were strategically selected and planned for ease of access and installation.
Detour Signage installed within 45 days of NTP	<ul style="list-style-type: none"> • ICE will begin detour plan preparation on or before contract execution to allow detour plans to be submitted at risk prior to NTP
RISK B. MINIMIZING IMPACTS TO SCDOT RIGHT-OF-WAY ACQUISITION COSTS	
ROW Acquisition Costs SCDOT may have additional, unplanned ROW costs	<ul style="list-style-type: none"> • Optimized roadway design to reduce the needed ROW at three sites (See Table 4.1.1.b) • Obtain permissions where possible to limit ROW costs • Design allows for utilities to be relocated within existing or new ROW
RISK C. AVOIDING OR MINIMIZING IMPACTS TO UTILITIES	
Broad River Electric at Kings Creek Potential for full relocations	<ul style="list-style-type: none"> • ICE design and Lane construction means and methods minimize relocation by only moving a single pole approximately 15 feet in line.
Duke Energy Distribution at S-56 over Horse Creek Potential for Relocation	<ul style="list-style-type: none"> • ICE design and Lane construction means and methods eliminate the need for a relocation of Duke Energy Distribution at this site.

CONCEPTUAL PLANS

A.1 – Roadway Plans

S-138 over Goucher Creek

S-226 over Unnamed Stream

S-86 over Kings Creek

S-106 over Branch of Suck Creek

S-56 over Horse Creek

APPENDIX A



Package I4\S-138 over Goucher Creek Roadway\PLANS\SH1_01.dgn
10/19/2022

INDEX OF SHEETS		
SHEET NO.	DESCRIPTION	SHEET
1	TITLE SHEET	1
1A	RIGHT-OF-WAY TITLE SHEET	OMITTED
2	SUMMARY OF ESTIMATED QUANTITIES	OMITTED
3	TYPICAL SECTIONS	1
4	RIGHT-OF-WAY DATA SHEET	OMITTED
4A	PROPERTY STRIP MAP	OMITTED
5	GENERAL CONSTRUCTION NOTE	OMITTED
5A - 5B	REFERENCE DATA SHEET	1
6	PLAN AND PROFILE SHEET	1
TC1	TRAFFIC CONTROL SHEET	OMITTED
PM1	PAVEMENT MARKING AND SIGNING SHEET	OMITTED
EC1 - EC2	EROSION CONTROL SHEETS	OMITTED
U1	UTILITY SHEET	OMITTED
X1	CROSS SECTIONS	OMITTED
		4



PROPOSED PLANS
FOR

CHEROKEE COUNTY

PROJECT ID: 1162220

S-138 (GOUCHER SCHOOL ROAD)

ROADWAY APPROACHES TO BRIDGE OVER GOUCHER CREEK

BRIDGE PLANS BOUND
UNDER A SEPARATE COVER

Design Reference for these plans is the:
2021
SCDOT "Roadway Design Manual"

Hydraulic Design Reference for these plans is the:
2009
Edition of SCDOT's "Requirements for
Hydraulic Design Studies"


3 DAYS BEFORE DIGGING IN
SOUTH CAROLINA
CALL 811
SOUTH CAROLINA 811 (SC811)
WWW.SC811.COM
ALL UTILITIES MAY NOT BE A MEMBER OF SC811

RAILROAD INVOLVEMENT?
YES / **NO**

TRAFFIC DATA

2020 ADT 750
2040 ADT 1095
TRUCKS 8 %

PROJECT: 1162220 S-138
(GOUCHER SCHOOL ROAD)
STA. 86+40.00 TO STA. 91+36.00
SEE SHEET 6



LAYOUT
NOT TO SCALE

CHEROKEE COUNTY

CONSTRUCT 120.00' PRESTRESSED
CONCRETE BOX BEAM BRIDGE
STA. 88+37.00 TO STA. 89+57.00
(SEE BRIDGE PLANS)

NET LENGTH OF ROADWAY	0.072	MILES
NET LENGTH OF BRIDGES	0.022	MILES
NET LENGTH OF PROJECT	0.094	MILES
LENGTH OF EXCEPTIONS	0.000	MILES
GROSS LENGTH OF PROJECT	0.094	MILES

NOTE: EXCEPT AS MAY BE OTHERWISE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS,
ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL CONFORM TO THE SOUTH
CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY
CONSTRUCTION (2007 EDITION) AND THE STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN
EFFECT AT THE TIME OF FINAL RFP.



ENGINEER OF RECORD

PRELIMINARY
NOT FOR CONSTRUCTION

FOR CONSTRUCTION : _____ DATE _____


SHEET NO.	TOTAL SHEETS
1	4

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-138	3

■ VARIABLE – SEE PLANS & CROSS SECTIONS

* ADD 3.75 WHERE GUARDRAIL IS ERECTED

PROVIDE NON-MOW STRIP FOR GUARDRAIL IN ACCORDANCE WITH STD. DWG. 805-525-01



- ① HOT MIX ASPHALT SURFACE COURSE
- ② HOT MIX ASPHALT INTERMEDIATE COURSE
- ③ VARIABLE HOT MIX ASPHALT FOR BUILDUP
- ④ HOT MIX ASPHALT BASE COURSE OR GABC

SEE RFP
EXHIBIT 4C
FOR PAVEMENT
STRUCTURE



FUNCTIONAL CLASSIFICATION	RTE. S-138 DESIGN SPEED		
	MPH	FROM STA.	TO STA.
RURAL MAJOR COLLECTOR	50	86 + 40.00	91 + 36.00
	EXCEPTIONS TO DESIGN SPEED		

PRELIMINARY
NOT FOR CONSTRUCTION

N.T.S.

7			
6			
5			
4			
3			
2			
1			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

TYPICAL SECTION

S-138 (GOUCHER SCHOOL ROAD)
OVER GOUCHER CREEK

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-138	5A

Beginning chain S138 description

Point 6 N 1,142,066.6006 E 1,792,286.1476 Sta 71+09.20

Course from 6 to PC S138A N 18° 52' 21.96" E Dist 9.9999

Curve Data

Curve S138A
P.I. Station 73+97.57 N 1,142,339.4668 E 1,792,379.4257

Delta = 33° 53' 39.44" (LT)

Degree = 6° 16' 19.17"

Tangent = 278.3693

Length = 540.4071

Radius = 913.5181

External = 41.4713

Long Chord = 532.5617

Mid. Ord. = 39.6704

P.C. Station 71+19.20 N 1,142,076.0629 E 1,792,289.3822

P.T. Station 76+59.61 N 1,142,608.3238 E 1,792,307.2774

C.C. N 1,142,371.5564 E 1,791,424.9756

Back = N 18° 52' 21.96" E

Ahead = N 13° 01' 17.49" W



Chord Bear = N 1° 55' 32.23" E

Course from PT S138A to 16 N 13° 01' 17.49" W Dist 2,826.4626

Point 16 N 1,145,338.2020 E 1,791,574.7095 Sta 104+86.07

Ending chain S138 description

DS = RETAIN EXIST.
eMAX = RETAIN EXIST.
e = RETAIN EXIST.
LG-PC = RETAIN EXIST.
LG-PT = RETAIN EXIST.



PRELIMINARY
NOT FOR CONSTRUCTION


SCALE: 1" = 100'

7			
6			
5			
4			
3			
2			
1			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

REFERENCE DATA SHEET

S-138 (GOUCHER SCHOOL ROAD)
OVER GOUCHER CREEK



S-138 (GOUCHER SCHOOL ROAD)
OVER GOUCHER CREEK

Package 14\N-S-226 over Unnamed Stream\Roadway\PLANS\SHT_01.dgn
10/20/2022
\$\$\$\$user\$\$\$

SHEET NO.	DESCRIPTION	SHEET
1	TITLE SHEET	1
1A	RIGHT-OF-WAY TITLE SHEET	OMITTED
2	SUMMARY OF ESTIMATED QUANTITIES	OMITTED
3	TYPICAL SECTIONS	1
4	RIGHT-OF-WAY DATA SHEET	OMITTED
4A	PROPERTY STRIP MAP	OMITTED
5	GENERAL CONSTRUCTION NOTE	OMITTED
5A	REFERENCE DATA SHEET	1
6	PLAN AND PROFILE SHEET	1
TC1	TRAFFIC CONTROL SHEET	OMITTED
PM1	PAVEMENT MARKING AND SIGNING SHEET	OMITTED
EC1 – EC2	EROSION CONTROL SHEETS	OMITTED
U1	UTILITY SHEET	OMITTED
X1 – X10	CROSS SECTIONS	10
		14



PROPOSED PLANS
FOR

CHEROKEE COUNTY

PROJECT ID: 1162220

S-226 (HAMMET GROVE ROAD)

ROADWAY APPROACHES TO BRIDGE OVER UNNAMED STREAM

BRIDGE PLANS BOUND
UNDER A SEPARATE COVER

Design Reference for these plans is the:
2021

SCDOT "Roadway Design Manual"

Hydraulic Design Reference for these plans is the:
2009
Edition of SCDOT's "Requirements for
Hydraulic Design Studies"

3 DAYS BEFORE DIGGING IN
SOUTH CAROLINA

CALL 811

SOUTH CAROLINA 811 (SC811)
WWW.SC811.COM
ALL UTILITIES MAY NOT BE A MEMBER OF SC811

RAILROAD INVOLVEMENT?
YES / NO


TRAFFIC DATA

2020 ADT 200

2040 ADT 256

TRUCKS 5 %

PROJECT: 1162220 S-226
(HAMMET GROVE ROAD)
STA. 161+13.00 TO STA. 167+00.00
SEE SHEET 6



LAYOUT
NOT TO SCALE

CHEROKEE COUNTY

CONSTRUCT 80.00' PRESTRESSED
CONCRETE BOX BEAM BRIDGE
STA. 161+98.00 TO STA. 162+78.00
(SEE BRIDGE PLANS)

NET LENGTH OF ROADWAY	0.096	MILES
NET LENGTH OF BRIDGES	0.015	MILES
NET LENGTH OF PROJECT	0.111	MILES
LENGTH OF EXCEPTIONS	0.000	MILES
GROSS LENGTH OF PROJECT	0.096	MILES

NOTE: EXCEPT AS MAY BE OTHERWISE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS,
ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL CONFORM TO THE SOUTH
CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY
CONSTRUCTION (2007 EDITION) AND THE STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN
EFFECT AT THE TIME OF FINAL RFP.



ENGINEER OF RECORD

PRELIMINARY
NOT FOR CONSTRUCTION

FOR CONSTRUCTION :

DATE

SHEET NO.	TOTAL SHEETS
1	14


Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\PLANS\SHT_03.dgn
10/20/2022

FED. RD. DW. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	3

■ VARIABLE – SEE PLANS & CROSS SECTIONS

* ADD 3.75 WHERE GUARDRAIL IS ERECTED
EXCEPT IN AREAS OF COMPRESSED
SHOULDER GUARDRAIL

PROVIDE NON-MOW STRIP FOR
GUARDRAIL IN ACCORDANCE WITH
STD. DWG. 805-525-01



USE THIS SECTION
S-226 (HAMMETT GROVE ROAD)
STA. 161+13.00 TO STA. 161+78.00
STA. 162+98.00 TO STA. 167+00.00

- 1 HOT MIX ASPHALT SURFACE COURSE
- 2 HOT MIX ASPHALT INTERMEDIATE COURSE
- 3 HOT MIX ASPHALT BASE COURSE OR GABC

SEE RFP
EXHIBIT 4C
FOR PAVEMENT
STRUCTURE



FUNCTIONAL CLASSIFICATION	RTE. S-226			DESIGN SPEED		PRELIMINARY NOT FOR CONSTRUCTION	7				SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
	MPH	FROM STA.	TO STA.	6							
	35	161 + 13.00	167 + 00.00	5							
				4							
RURAL LOCAL GROUP 4	EXCEPTIONS TO DESIGN SPEED			3					TYPICAL SECTION		
				2							
				1							
											S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	5A

Beginning chain S226 description

Point 7 N 1,129,293.4059 E 1,774,334.6451 Sta 146+96.98
Course from 7 to PC S226A S 81° 51' 36.47" E Dist 260.6679

Curve Data

Curve S226A
P.I. Station 155+13.56 N 1,129,177.7865 E 1,775,142.9966
Delta = 60° 40' 14.09" (LT)
Degree = 6° 01' 52.48"
Tangent = 555.9103
Length = 1,005.9380
Radius = 949.9827
External = 150.7004
Long Chord = 959.5952
Mid. Ord. = 130.0672
P.C. Station 149+57.65 N 1,129,256.4979 E 1,774,592.6869
P.T. Station 159+63.59 N 1,129,619.0011 E 1,775,481.1769
C.C. N 1,130,196.9099 E 1,774,727.1951
Back = S 81° 51' 36.47" E
Ahead = N 37° 28' 09.44" E
Chord Bear = N 67° 48' 16.48" E

DS = RETAIN EXIST.
eMAX = RETAIN EXIST.
e = RETAIN EXIST.
LG% = RETAIN EIXST.

Course from PT S226A to 15 N 37° 28' 09.44" E Dist 76.8026

Point 15 N 1,129,679.9578 E 1,775,527.8987 Sta 160+40.39

Course from 15 to PC S226B N 35° 22' 17.37" E Dist 278.1041

Curve Data

Curve S226B
P.I. Station 165+04.50 N 1,130,058.3985 E 1,775,796.5592
Delta = 11° 33' 33.59" (RT)
Degree = 3° 07' 04.34"
Tangent = 186.0035
Length = 370.7443
Radius = 1,837.6570
External = 9.3894
Long Chord = 370.1159
Mid. Ord. = 9.3417
P.C. Station 163+18.49 N 1,129,906.7283 E 1,775,688.8863
P.T. Station 166+89.24 N 1,130,185.4167 E 1,775,932.4403
C.C. N 1,128,842.9537 E 1,777,187.3411
Back = N 35° 22' 17.37" E
Ahead = N 46° 55' 50.95" E
Chord Bear = N 41° 09' 04.16" E

DS = 35 MPH
eMAX = 6%
e = 3%
LG-PC = 0.62%
LG-PT = 0.62%

Course from PT S226B to PC S226C N 46° 55' 50.95" E Dist 76.3737

Curve Data


Curve S226C
P.I. Station 170+25.75 N 1,130,415.2152 E 1,776,178.2732
Delta = 30° 29' 41.02" (RT)
Degree = 6° 00' 13.03"
Tangent = 260.1395
Length = 507.9390
Radius = 954.3538
External = 34.8195
Long Chord = 501.9650
Mid. Ord. = 33.5938
P.C. Station 167+65.61 N 1,130,237.5709 E 1,775,988.2335
P.T. Station 172+73.55 N 1,130,471.8497 E 1,776,432.1730
C.C. N 1,129,540.3871 E 1,776,639.9435
Back = N 46° 55' 50.95" E
Ahead = N 77° 25' 31.98" E
Chord Bear = N 62° 10' 41.47" E

DS = RETAIN EXIST.
eMAX = RETAIN EXIST.
e = RETAIN EXIST.
LG% = RETAIN EIXST.

Course from PT S226C to 28 N 77° 25' 31.98" E Dist 208.3599

Point 28 N 1,130,517.2113 E 1,776,635.5352 Sta 174+81.91

Ending chain S226 description



ALIGNMENT CONTROL CAN BE FOUND ON
REFERENCE DATA SHEET



PRELIMINARY
NOT FOR CONSTRUCTION

SCALE: 1" = 100'

7			
6			
5			
4			
3			
2			
1			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

REFERENCE DATA SHEET

S-226 (HAMMET GROVE ROAD)
OVER UNNAMED STREAM

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	6


**FATC 2: REDUCES STREAM IMPACTS
AND REDUCES REQUIRED ROW**

**RFP DESIGN EXCEPTION (EXHIBIT 4B, 2.1.21)
AT BOTH ENDS OF BRIDGE, TRANSITION THE
BARRIER FOR GUARDRAIL ATTACHMENT ON THE BRIDGE**

**PROPOSED VERTICAL CURVE
IMPROVES EXISTING K-VALUE -
WITHIN 10 MPH OF DESIGN SPEED**

**RFP DESIGN EXCEPTION (EXHIBIT 4B, 2.1.15)
LOW POINT PROVIDED AT 23.27' FROM BRIDGE END**

HYDROLOGY DATA	
DA = 1 SQ. MI.	
DESIGN FLOOD: 4% (25-YEAR)	
Q (AEP-4%) = 684 CFS	
V (AEP-4%) = 6.6 FT./SEC.	
W.S. ELEV. (AEP-4%) = 544.38 FT.	
DESIGN FLOOD: 1% (100-YEAR)	
Q (AEP-1%) = 984 CFS	
V (AEP-1%) = 7.0 FT./SEC.	
W.S. ELEV. (AEP-1%) = 545.43 FT.	
BACKWATER ELEVATION UPSTREAM OF BRIDGE:	
H.W. ELEV. (25 YR.) = 544.38 FT.	
(INCLUDING 0.48 FT. BACKWATER)	
H.W. ELEV. (100 YR.) = 545.43 FT.	
(INCLUDING 0.71 FT. BACKWATER)	
STRUCTURE OVERTOPPING FLOOD:	
0.2% AEP (500-YR.) FLOW = 1350 CFS	
OVERTOPPING FLOW = GREATER THAN	
0.2% AEP (500-YR.) FLOW	



ALIGNMENT CONTROL CAN BE FOUND ON
REFERENCE DATA SHEET 5A



**PRELIMINARY
NOT FOR CONSTRUCTION**

HORIZONTAL SCALE: 1" = 50' VERTICAL SCALE: 1" = 10'

REV. NO.	BY	DATE	DESCRIPTION OF REVISION
7			
6			
5			
4			
3			
2			
1			


SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE SHEET

S-226 (HAMMETT GROVE ROAD)
OVER UNNAMED STREAM

Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\DGN\CROSS SECTIONS\226_XS_SHEETS.dgn
10/20/2022

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X1




PRELIMINARY
NOT FOR CONSTRUCTION

4			
3			
2			
1			
0			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
CROSS SECTION SHEET
S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\DGN\CROSS SECTIONS\226_XS_SHEETS.dgn
10/20/2022

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X2




PRELIMINARY
NOT FOR CONSTRUCTION

4			
3			
2			
1			
0			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
CROSS SECTION SHEET
S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\DGN\CROSS SECTIONS\226_XS_SHEETS.dgn
10/20/2022

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X3




PRELIMINARY
NOT FOR CONSTRUCTION

4			
3			
2			
1			
0			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
CROSS SECTION SHEET
S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\DGN\CROSS SECTIONS\S226_XS_SHEETS.dgn
10/20/2022

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X4




PRELIMINARY
NOT FOR CONSTRUCTION

4			
3			
2			
1			
0			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
CROSS SECTION SHEET
S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\DGN\CROSS SECTIONS\S226_XS_SHEETS.dgn
10/20/2022

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X5




PRELIMINARY
NOT FOR CONSTRUCTION

4			
3			
2			
1			
0			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
CROSS SECTION SHEET
S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X6



4				SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION CROSS SECTION SHEET S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM
3				
2				
1				
0				
REV. NO.	BY	DATE	DESCRIPTION OF REVISION	

PRELIMINARY
NOT FOR CONSTRUCTION




SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

CROSS SECTION SHEET

S-226 (HAMMET GROVE ROAD)
OVER UNNAMED STREAM

Z:\Projects\22-6\Bridge Package 14\S-226 over Unnamed Stream\Roadway\DCN\CROSS SECTIONS\S226_XS-SHEETS.dgn
10/20/2022

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X7



Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\DGN\CROSS SECTIONS\S226_XS_SHEETS.dgn
10/20/2022




PRELIMINARY
NOT FOR CONSTRUCTION

4			
3			
2			
1			
0			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
CROSS SECTION SHEET
S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\DGN\CROSS SECTIONS\S226_XS_SHEETS.dgn
10/20/2022

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X8




PRELIMINARY
NOT FOR CONSTRUCTION

4			
3			
2			
1			
0			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
CROSS SECTION SHEET
S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\DGN\CROSS SECTIONS\S226_XS_SHEETS.dgn
10/20/2022

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X9




PRELIMINARY
NOT FOR CONSTRUCTION

4			
3			
2			
1			
0			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
CROSS SECTION SHEET
S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

Z:\Projects\22-61 Bridge Package 14\S-226 over Unnamed Stream\Roadway\DGN\CROSS SECTIONS\S226_XS_SHEETS.dgn
10/20/2022

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-226	X10



PRELIMINARY
NOT FOR CONSTRUCTION

4			
3			
2			
1			
0			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
CROSS SECTION SHEET
S-226 (HAMMET GROVE ROAD) OVER UNNAMED STREAM

\$\$\$user\$\$
ridge Package I4\S-86 over Kings Creek\Roadway\PLANS\SHT_01.dgn
10/19/2022

INDEX OF SHEETS		
SHEET NO.	DESCRIPTION	SHEET
1	TITLE SHEET	1
1A	RIGHT-OF-WAY TITLE SHEET	OMITTED
2	SUMMARY OF ESTIMATED QUANTITIES	OMITTED
3	TYPICAL SECTIONS	1
4	RIGHT-OF-WAY DATA SHEET	OMITTED
4A	PROPERTY STRIP MAP	OMITTED
5	GENERAL CONSTRUCTION NOTE	OMITTED
5A	REFERENCE DATA SHEET	1
6-6A	PLAN AND PROFILE SHEET	2
TC1	TRAFFIC CONTROL SHEET	OMITTED
PM1	PAVEMENT MARKING AND SIGNING SHEET	OMITTED
EC1 - EC2	EROSION CONTROL SHEETS	OMITTED
U1	UTILITY SHEET	OMITTED
X1 - X10	CROSS SECTIONS	OMITTED
		5



PROPOSED PLANS
FOR
CHEROKEE COUNTY
PROJECT ID: 1162220
S-86 (ROCK HOUSE ROAD)
ROADWAY APPROACHES TO BRIDGE OVER KINGS CREEK

BRIDGE PLANS BOUND
UNDER A SEPARATE COVER


Design Reference for these plans is the:
2021
SCDOT "Roadway Design Manual"

Hydraulic Design Reference for these plans is the:
2009
Edition of SCDOT's "Requirements for
Hydraulic Design Studies"

3 DAYS BEFORE DIGGING IN
SOUTH CAROLINA
CALL 811
SOUTH CAROLINA 811 (SC811)
WWW.SC811.COM
ALL UTILITIES MAY NOT BE A MEMBER OF SC811

RAILROAD INVOLVEMENT?
YES / **NO**

TRAFFIC DATA
____ 2020 ____ ADT ____ 200 ____
____ 2040 ____ ADT ____ 256 ____
TRUCKS ____ 5 ____ %



PROJECT: 1162220 S-86
(ROCK HOUSE ROAD)
STA. 47+50.00 TO STA. 55+25.00
SEE SHEETS 6-6A

CONSTRUCT 160.00' PRESTRESSED
CONCRETE BOX BEAM BRIDGE
STA. 49+06.20 TO STA. 50+66.20
(SEE BRIDGE PLANS)

NET LENGTH OF ROADWAY	0.117	MILES
NET LENGTH OF BRIDGES	0.030	MILES
NET LENGTH OF PROJECT	0.147	MILES
LENGTH OF EXCEPTIONS	0.000	MILES
GROSS LENGTH OF PROJECT	0.147	MILES

NOTE: EXCEPT AS MAY BE OTHERWISE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS,
ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL CONFORM TO THE SOUTH
CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY
CONSTRUCTION (2007 EDITION) AND THE STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN
EFFECT AT THE TIME OF FINAL RFP.



PRELIMINARY
NOT FOR CONSTRUCTION

FOR CONSTRUCTION : _____ DATE _____

SHEET NO.	TOTAL SHEETS
1	5


FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-86	3

■ VARIABLE – SEE PLANS & CROSS SECTIONS


* ADD 3.75' WHERE GUARDRAIL IS ERECTED
EXCEPT IN AREAS OF COMPRESSED
SHOULDER GUARDRAIL

PROVIDE NON-MOW STRIP FOR
GUARDRAIL IN ACCORDANCE WITH
STD. DWG. 805-525-01

Ø 6' MIN WHEN USING 6:1 SLOPES
8' MIN WHEN USING 4:1 SLOPES



USE THIS SECTION
S-86 (ROCK HOUSE ROAD)
STA. 50+86.20 TO +/- STA. 51+30.00
+/- STA. 53+11.00 TO STA. 55+25.00



USE THIS SECTION
S-86 (ROCK HOUSE ROAD)
STA. 47+50.00 TO STA. 48+86.20
+/- STA. 51+30.00 TO +/- STA. 53+11.00

- ① HOT MIX ASPHALT SURFACE COURSE
- ② HOT MIX ASPHALT INTERMEDIATE COURSE
- ③ VARIABLE HOT MIX ASPHALT FOR BUILDUP
- ④ HOT MIX ASPHALT BASE COURSE OR GABC

SEE RFP
EXHIBIT 4C
FOR PAVEMENT
STRUCTURE



FUNCTIONAL
CLASSIFICATION

RURAL LOCAL GROUP 4

RTE. S-86 DESIGN SPEED		
MPH	FROM STA.	TO STA.
50	47+50.00	55+25.00

EXCEPTIONS TO DESIGN SPEED

PRELIMINARY
NOT FOR CONSTRUCTION

N.T.S.

7			
6			
5			
4			
3			
2			
1			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

TYPICAL SECTION

S-86 (ROCK HOUSE ROAD)
OVER KINGS CREEK

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-86	5A

EXISTING DATA

Beginning chain S86A description

Point 5000 N 1,206,531.7956 E 1,876,459.9730 Sta 34+00.54

Course from 5000 to 5001 S 47° 33' 13.86" E Dist 904.4406

Point 5001 N 1,205,921.3914 E 1,877,127.3705 Sta 43+04.98

Course from 5001 to PC S86A-1 S 47° 16' 36.18" E Dist 930.9487

Curve Data

Curve S86A-1
P.I. Station 53+80.63 N 1,205,191.6094 E 1,877,917.5831
Delta = 18° 58' 35.23" (LT)
Degree = 6° 37' 04.18"
Tangent = 144.6989
Length = 286.7475
Radius = 865.7793
External = 12.0086
Long Chord = 283.4387
Mid. Ord. = 11.8443
P.C. Station 52+22.68 N 1,205,389.7816 E 1,877,811.2817
P.T. Station 55+22.68 N 1,205,133.3397 E 1,878,050.0309
C.C. N 1,205,925.8168 E 1,878,398.6768
Back = S 47° 16' 36.18" E
Ahead = S 66° 15' 11.41" E
Chord Bear = S 56° 45' 53.79" E

Curve Data

Curve S86A-2
P.I. Station 59+46.59 N 1,204,962.6333 E 1,878,438.0491
Delta = 54° 47' 56.11" (LT)
Degree = 7° 00' 21.23"
Tangent = 423.9090
Length = 782.1828
Radius = 817.8222
External = 103.3358
Long Chord = 752.7095
Mid. Ord. = 91.7435
P.C. Station 55+22.68 N 1,205,133.3397 E 1,878,050.0309
P.T. Station 63+04.86 N 1,205,181.2928 E 1,878,801.2114
C.C. N 1,205,881.9200 E 1,878,379.3647
Back = S 66° 15' 11.41" E
Ahead = N 58° 56' 52.48" E
Chord Bear = N 86° 20' 50.54" E

Course from PT S86A-2 to 5002 N 58° 56' 52.48" E Dist 238.0284

Point 5002 N 1,205,304.0719 E 1,879,005.1300 Sta 63+42.89

Ending chain S86A description

PROPOSED DATA

Beginning chain PR_S86 description

Curve Data



Curve PR_S86-1
P.I. Station 48+28.70 N 1,205,566.0669 E 1,877,512.1181
Delta = 0° 45' 01.73" (LT)
Degree = 0° 45' 53.42"
Tangent = 53.7039
Length = 107.4064
Radius = 8,200.0000
External = 0.1759
Long Chord = 107.4056
Mid. Ord. = 0.1759
P.C. Station 47+75.00 N 1,205,602.5028 E 1,877,472.6651
P.T. Station 48+82.41 N 1,205,530.1509 E 1,877,552.0450
C.C. N 1,211,626.5422 E 1,883,036.0228
Back = S 47° 16' 36.18" E
Ahead = S 48° 01' 37.91" E
Chord Bear = S 47° 39' 07.04" E

Course from PT PR_S86-1 to PC PR_S86-2 S 48° 01' 37.91" E Dist 398.5386

Curve Data

Curve PR_S86-2
P.I. Station 54+02.54 N 1,205,182.2952 E 1,877,938.7468
Delta = 18° 13' 38.64" (LT)
Degree = 7° 33' 31.72"
Tangent = 121.5978
Length = 241.1411
Radius = 758.0000
External = 9.6914
Long Chord = 240.1256
Mid. Ord. = 9.5690
P.C. Station 52+80.94 N 1,205,263.6172 E 1,877,848.3434
P.T. Station 55+22.09 N 1,205,133.3310 E 1,878,050.0506
C.C. N 1,205,827.1616 E 1,878,355.2770
Back = S 48° 01' 37.91" E
Ahead = S 66° 15' 16.55" E
Chord Bear = S 57° 08' 27.23" E

Ending chain PR_S86 description



PRELIMINARY
NOT FOR CONSTRUCTION

SCALE: 1" = 100'

7				
6				
5				
4				
3				
2				
1				
REV. NO.	BY	DATE	DESCRIPTION OF REVISION	


SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

REFERENCE DATA SHEET

S-86 (ROCK HOUSE ROAD)
OVER KINGS CREEK

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-86	6

FATC 1 - TWO SPAN BRIDGE
WITH NO SKEW




EXISTING ROW LIMITS MAINTAINED ADJACENT TO
KINGS MOUNTAIN NATIONAL MILITARY PARK
(PARCEL 5)

HORIZONTAL CENTERLINE SHIFTED <6' TO AVOID
KINGS MOUNTAIN NATIONAL MILITARY PARK (PARCEL 5)
RFP ALLOWED MAXIMUM SHIFT OF 10'
(EXHIBIT 4A, 2.6)

LENGTHENED GUARDRAIL W/ COMPRESSED SHOULDER
TO AVOID ROW IMPACTS AT
KINGS MOUNTAIN NATIONAL MILITARY PARK

NOTE: SEE SHEET 6A FOR PROFILE



ALIGNMENT CONTROL CAN BE FOUND ON
REFERENCE DATA SHEET 5A



PRELIMINARY
NOT FOR CONSTRUCTION

SCALE: 1" = 50'



REV. NO.	BY	DATE	DESCRIPTION OF REVISION
7			
6			
5			
4			
3			
2			
1			

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE SHEET

S-86 (ROCK HOUSE ROAD)
OVER KINGS CREEK

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-86	6A



ALIGNMENT CONTROL CAN BE FOUND ON
REFERENCE DATA SHEET



PRELIMINARY
NOT FOR CONSTRUCTION

HORIZONTAL SCALE: 1" = 50' VERTICAL SCALE: 1" = 10'

7			
6			
5			
4			
3			
2			
1			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE SHEET

S-86 (ROCK HOUSE ROAD)
OVER KINGS CREEK

\$\$\$user\$\$
ridge Package I4\S-106 over Suck Creek Roadway\PLANS\SHT_01.dgn
10/19/2022

INDEX OF SHEETS		
SHEET NO.	DESCRIPTION	SHEET
1	TITLE SHEET	1
1A	RIGHT-OF-WAY TITLE SHEET	OMITTED
2	SUMMARY OF ESTIMATED QUANTITIES	OMITTED
3	TYPICAL SECTIONS	1
4	RIGHT-OF-WAY DATA SHEET	OMITTED
4A	PROPERTY STRIP MAP	OMITTED
5	GENERAL CONSTRUCTION NOTE	OMITTED
5A	REFERENCE DATA SHEET	1
6	PLAN AND PROFILE SHEET	1
TC1	TRAFFIC CONTROL SHEET	OMITTED
PM1	PAVEMENT MARKING AND SIGNING SHEET	OMITTED
EC1 – EC2	EROSION CONTROL SHEETS	OMITTED
U1	UTILITY SHEET	OMITTED
X1 – X5	CROSS SECTIONS	OMITTED
		4



PROPOSED PLANS
FOR

CHEROKEE COUNTY

PROJECT ID: 1162220

S-106 (ISLAND CREEK ROAD)

ROADWAY APPROACHES TO BRIDGE OVER BRANCH OF SUCK CREEK

BRIDGE PLANS BOUND
UNDER A SEPARATE COVER

Design Reference for these plans is the:
2021

SCDOT "Roadway Design Manual"


Hydraulic Design Reference for these plans is the:

2009

Edition of SCDOT's "Requirements for
Hydraulic Design Studies"

PROJECT: 1162220 S-106
(ISLAND CREEK ROAD)
STA. 29+00.00 TO STA. 35+00.00
SEE SHEET 6

CONSTRUCT 60.00' PRESTRESSED
CONCRETE CORED SLAB BRIDGE
STA. 31+70.00 TO STA. 32+30.00
(SEE BRIDGE PLANS)



LAYOUT
NOT TO SCALE

CHEROKEE COUNTY

3 DAYS BEFORE DIGGING IN
SOUTH CAROLINA
CALL 811
SOUTH CAROLINA 811 (SC811)
WWW.SC811.COM
ALL UTILITIES MAY NOT BE A MEMBER OF SC811

RAILROAD INVOLVEMENT?
YES / **NO**

TRAFFIC DATA

2020 ADT 225

2040 ADT 329

TRUCKS 8 %



NET LENGTH OF ROADWAY	0.103	MILES
NET LENGTH OF BRIDGES	0.011	MILES
NET LENGTH OF PROJECT	0.114	MILES
LENGTH OF EXCEPTIONS	0.000	MILES
GROSS LENGTH OF PROJECT	0.114	MILES

NOTE: EXCEPT AS MAY BE OTHERWISE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS,
ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL CONFORM TO THE SOUTH
CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY
CONSTRUCTION (2007 EDITION) AND THE STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN
EFFECT AT THE TIME OF FINAL RFP.



ENGINEER OF RECORD



PRELIMINARY
NOT FOR CONSTRUCTION

FOR CONSTRUCTION :

DATE

SHEET NO.	TOTAL SHEETS
1	4

- VARIABLE – SEE PLANS & CROSS SECTIONS
- ADD 3.75 WHERE GUARDRAIL IS ERECTED
- * PROVIDE NON-MOW STRIP FOR GUARDRAIL IN ACCORDANCE WITH STD. DWG. 805-525-01



- ① HOT MIX ASPHALT SURFACE COURSE
- ② HOT MIX ASPHALT INTERMEDIATE COURSE
- ③ VARIABLE HOT MIX ASPHALT FOR BUILDUP
- ④ HOT MIX ASPHALT BASE COURSE OR GABC

SEE RFP
EXHIBIT 4C
FOR PAVEMENT
STRUCTURE



FUNCTIONAL CLASSIFICATION	RTE. S-106 DESIGN SPEED		
	MPH	FROM STA.	TO STA.
	35	29+00.00	35+00.00
RURAL MAJOR COLLECTOR	EXCEPTIONS TO DESIGN SPEED		

PRELIMINARY
NOT FOR CONSTRUCTION

REV. NO.	BY	DATE	DESCRIPTION OF REVISION
7			
6			
5			
4			
3			
2			
1			

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION
TYPICAL SECTION
S-106 (ISLAND CREEK ROAD) OVER BRANCH OF SUCK CREEK

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-106	5A

Beginning chain S106 description

Curve Data

Curve S106A
P.I. Station = 18+76.05 N 1,198,790.7816 E 1,749,459.0153
Delta = 45° 44' 10.54" (LT)
Degree = 4° 01' 42.92"
Tangent = 599.8413
Length = 1,135.2924
Radius = 1,422.2295
External = 121.3204
Long Chord = 1,105.3895
Mid. Ord. = 111.7848
P.C. Station = 12+76.21 N 1,199,389.3152 E 1,749,419.4296
P.T. Station = 24+11.50 N 1,198,401.3764 E 1,749,915.2753
C.C. = N 1,199,483.1733 E 1,750,838.5587
Back = S 3° 47' 02.06" E
Ahead = S 49° 31' 12.61" E
Chord Bear = S 26° 39' 07.33" E

Course from PT S106A to PC S106B S 49° 31' 12.61" E Dist 274.0708

Curve Data

Curve S106B
P.I. Station = 28+11.40 N 1,198,141.7736 E 1,750,219.4479
Delta = 10° 02' 24.18" (LT)
Degree = 4° 00' 00.03"
Tangent = 125.8225
Length = 251.0007
Radius = 1,432.3917
External = 5.5156
Long Chord = 250.6797
Mid. Ord. = 5.4944
P.C. Station = 26+85.57 N 1,198,223.4551 E 1,750,123.7430
P.T. Station = 29+36.57 N 1,198,078.0278 E 1,750,327.9273
C.C. = N 1,199,312.9817 E 1,751,053.6235
Back = S 49° 31' 12.61" E
Ahead = S 59° 33' 36.78" E
Chord Bear = S 54° 32' 24.70" E

DS = RETAIN EXIST.
eMAX = RETAIN EXIST.
e = RETAIN EXIST.
LG% = RETAIN EXIST.

DS = RETAIN EXIST.
eMAX = RETAIN EXIST.
e = RETAIN EXIST.
LG% = RETAIN EXIST.

Curve Data

Curve S106C
P.I. Station = 32+63.77 N 1,197,912.2611 E 1,750,610.0209
Delta = 38° 57' 34.66" (LT)
Degree = 6° 11' 38.90"
Tangent = 327.1929
Length = 628.9757
Radius = 924.9999
External = 56.1627
Long Chord = 616.9282
Mid. Ord. = 52.9479
P.C. Station = 29+36.57 N 1,198,078.0277 E 1,750,327.9275
P.T. Station = 35-65.55 N 1,197,960.7354 E 1,750,933.6031
C.C. = N 1,198,875.5275 E 1,750,796.5626
Back = S 59° 33' 36.78" E
Ahead = N 81° 28' 48.55" E
Chord Bear = S 79° 02' 24.12" E

Course from PT S106C to PC S106D N 81° 28' 48.55" E Dist 257.2138

Curve Data

Curve S106D
P.I. Station = 40+50.27 N 1,198,032.5471 E 1,751,412.9706
Delta = 26° 56' 05.13" (RT)
Degree = 6° 01' 52.09"
Tangent = 227.5027
Length = 446.5950
Radius = 949.9996
External = 26.8611
Long Chord = 442.4941
Mid. Ord. = 26.1224
P.C. Station = 38+22.76 N 1,197,998.8421 E 1,751,187.9784
P.T. Station = 42-69.36 N 1,197,960.6799 E 1,751,628.8238
C.C. = N 1,197,059.3261 E 1,751,328.7228
Back = N 81° 28' 48.55" E
Ahead = S 71° 35' 06.32" E
Chord Bear = S 85° 03' 08.89" E

Curve Data

Curve S106E
P.I. Station = 43+99.01 N 1,197,919.7227 E 1,751,751.8388
Delta = 7° 48' 27.03" (RT)
Degree = 3° 00' 56.12"
Tangent = 129.6332
Length = 258.9049
Radius = 1,899.9865
External = 4.4186
Long Chord = 258.7047
Mid. Ord. = 4.4083
P.C. Station = 42-69.36 N 1,197,960.6796 E 1,751,628.8247
P.T. Station = 45-28.26 N 1,197,862.4346 E 1,751,868.1488
C.C. = N 1,196,157.9841 E 1,751,028.6266
Back = S 71° 35' 06.32" E
Ahead = S 63° 46' 39.29" E
Chord Bear = S 67° 40' 52.81" E

Course from PT S106E to 223 S 63° 46' 39.29" E Dist 325.5825



Point 223 N 1,197,718.5737 E 1,752,160.2241 Sta 48+53.85

Ending chain S106 description

DS = 35 MPH
eMAX = 6%
e = 4.4%
LG-PC = 0.62%
LG-PT = 0.62%

DS = RETAIN EXIST.
eMAX = RETAIN EXIST.
e = RETAIN EXIST.
LG% = RETAIN EXIST.

DS = RETAIN EXIST.
eMAX = RETAIN EXIST.
e = RETAIN EXIST.
LG% = RETAIN EXIST.



PRELIMINARY
NOT FOR CONSTRUCTION

SCALE: 1" = 100'

7				
6				
5				
4				
3				
2				
1				
REV. NO.	BY	DATE	DESCRIPTION OF REVISION	

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

REFERENCE DATA SHEET

S-106 (ISLAND CREEK ROAD)
OVER SUCK CREEK



FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-106	6

FATC 2 - REDUCES STREAM IMPACTS AND REDUCES REQUIRED ROW

FILL SLOPES STEEPER THAN 2:1 UTILIZED TO MINIMIZE ROW AND STREAM IMPACTS (RFP EXHIBIT 4F, 2.2)

RFP DESIGN EXCEPTION (EXHIBIT 4B, 2.1.21) AT BEGINNING OF BRIDGE: TRANSITION THE BARRIER FOR GUARDRAIL ATTACHMENT ON THE BRIDGE

RESTORED OVERGROWN DRIVEWAY FOR PARCEL 9



ALIGNMENT CONTROL CAN BE FOUND ON REFERENCE DATA SHEET 5A



PRELIMINARY
NOT FOR CONSTRUCTION

HORIZONTAL SCALE: 1" = 50' VERTICAL SCALE: 1" = 10'

REV. NO.	BY	DATE	DESCRIPTION OF REVISION
7			
6			
5			
4			
3			
2			
1			

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE SHEET

S-106 (ISLAND CREEK ROAD)
OVER BRANCH OF SUCK CREEK

SHEET NO.	TOTAL SHEETS
1	4

SHEET NO.	DESCRIPTION	SHEET
1	TITLE SHEET	1
1A	RIGHT-OF-WAY TITLE SHEET	OMITTED
2	SUMMARY OF ESTIMATED QUANTITIES	OMITTED
3	TYPICAL SECTIONS	1
4	RIGHT-OF-WAY DATA SHEET	OMITTED
4A	PROPERTY STRIP MAP	OMITTED
5	GENERAL CONSTRUCTION NOTE	OMITTED
5A	REFERENCE DATA SHEET	1
6	PLAN AND PROFILE SHEET	1
TC1	TRAFFIC CONTROL SHEET	OMITTED
PM1	PAVEMENT MARKING AND SIGNING SHEET	OMITTED
EC1 – EC2	EROSION CONTROL SHEETS	OMITTED
U1	UTILITY SHEET	OMITTED
X1	CROSS SECTIONS	OMITTED
		4



PROPOSED PLANS
FOR

CHEROKEE COUNTY

PROJECT ID: 1162220

S-56 (MONTGOMERY DRIVE)

ROADWAY APPROACHES TO BRIDGE OVER HORSE CREEK


BRIDGE PLANS BOUND
UNDER A SEPARATE COVER

Design Reference for these plans is the:
2021
SCDOT "Roadway Design Manual"

Hydraulic Design Reference for these plans is the:
2009
Edition of SCDOT's "Requirements for
Hydraulic Design Studies"

PROJECT: 1162220 S-56
(MONTGOMERY DRIVE)
STA. 32+57.00 TO STA. 35+80.00
SEE SHEET 6

CONSTRUCT 50.00' PRESTRESSED
CONCRETE CORED SLAB BRIDGE
STA. 34+05.10 TO STA. 34+55.10
(SEE BRIDGE PLANS)



LAYOUT
NOT TO SCALE

CHEROKEE COUNTY

3 DAYS BEFORE DIGGING IN
SOUTH CAROLINA
CALL 811
SOUTH CAROLINA 811 (SC811)
WWW.SC811.COM
ALL UTILITIES MAY NOT BE A MEMBER OF SC811

RAILROAD INVOLVEMENT?
YES / **NO**

TRAFFIC DATA		
2020	ADT	375
2040	ADT	480
TRUCKS	5	%



NET LENGTH OF ROADWAY	0.052	MILES
NET LENGTH OF BRIDGES	0.009	MILES
NET LENGTH OF PROJECT	0.061	MILES
LENGTH OF EXCEPTIONS	0.000	MILES
GROSS LENGTH OF PROJECT	0.061	MILES

EQUALITIES IN STATIONING
NONE

NOTE: EXCEPT AS MAY BE OTHERWISE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS,
ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL CONFORM TO THE SOUTH
CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY
CONSTRUCTION (2007 EDITION) AND THE STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN
EFFECT AT THE TIME OF FINAL RFP.



ENGINEER OF RECORD
PRELIMINARY
NOT FOR CONSTRUCTION
FOR CONSTRUCTION : DATE


Z:\Projects\22-61 Bridge Package 14\S-56 over Horse Creek\Roadway\PLANS\SHT_03.dgn
10/19/2022

■ VARIABLE – SEE PLANS & CROSS SECTIONS

★ ADD 3.75' WHERE GUARDRAIL IS ERECTED

PROVIDE NON-MOW STRIP FOR
GUARDRAIL IN ACCORDANCE WITH
STD. DWG. 805-525-01

FED. RD. DW. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-56	3



- ① HOT MIX ASPHALT SURFACE COURSE
- ② HOT MIX ASPHALT BASE COURSE
- ③ VARIABLE HOT MIX ASPHALT FOR BUILDUP

SEE RFP
EXHIBIT 4C
FOR PAVEMENT
STRUCTURE



FUNCTIONAL
CLASSIFICATION

RURAL LOCAL GROUP 4

RTE. S-56		DESIGN SPEED
MPH	FROM STA.	TO STA.
30	32+57.00	35+80.00
EXCEPTIONS TO DESIGN SPEED		

PRELIMINARY
NOT FOR CONSTRUCTION

N.T.S.

7			
6			
5			
4			
3			
2			
1			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

TYPICAL SECTION

S-56 (MONTGOMERY DRIVE)
OVER HORSE CREEK

Z:\Projects\22-61Bridge Package 14\S-56 over Horse Creek\Roadway\PLANS\SHT_05A.dgn 10/19/2022

Beginning chain S56 description

Point 400 N 1,219,931.5147 E 1,740,590.3430 Sta 7±19.53

Course from 400 to PC S56A S 24° 42' 00.02" E Dist 356.2133

Curve Data

Curve S56A
P.I. Station 12±84.86 N 1,219,417.9046 E 1,740,826.5773
Delta = 8° 21' 00.01" (RT)
Degree = 2° 00' 00.01"
Tangent = 209.1202
Length = 417.4999
Radius = 2,864.7869
External = 7.6224
Long Chord = 417.1305
Mid. Ord. = 7.6022
P.C. Station 10±75.74 N 1,219,607.8920 E 1,740,739.1928
P.T. Station 14±93.24 N 1,219,217.2412 E 1,740,883.4455
C.C. N 1,218,410.7917 E 1,738,136.5106
Back = S 24° 42' 00.02" E
Ahead = S 16° 21' 00.00" E
Chord Bear = S 20° 31' 30.01" E

Course from PT S56A to PC S56B S 16° 21' 00.00" E Dist 240.8798

Curve Data

Curve S56B
P.I. Station 18±94.04 N 1,218,832.6523 E 1,740,998.2716
Delta = 6° 23' 24.23" (LT)
Degree = 2° 00' 00.00"
Tangent = 159.9174
Length = 319.5032
Radius = 2,864.7886
External = 4.4600
Long Chord = 319.3376
Mid. Ord. = 4.4530
P.C. Station 17±34.12 N 1,218,986.1026 E 1,740,953.2542
P.T. Station 20±53.63 N 1,218,685.1656 E 1,741,060.0878
C.C. N 1,219,792.5526 E 1,743,702.1907
Back = S 16° 21' 00.00" E
Ahead = S 22° 44' 24.23" E
Chord Bear = S 19° 32' 42.12" E

Course from PT S56B to PC S56C S 22° 44' 24.23" E Dist 144.6240

Curve Data

Curve S56C
P.I. Station 23±85.03 N 1,218,379.5199 E 1,741,188.1934
Delta = 14° 51' 31.76" (RT)
Degree = 4° 00' 00.05"
Tangent = 186.7826
Length = 371.4692
Radius = 1,432.3894
External = 12.1268
Long Chord = 370.4292
Mid. Ord. = 12.0250
P.C. Station 21±98.25 N 1,218,551.7835 E 1,741,115.9924
P.T. Station 25±69.72 N 1,218,194.5015 E 1,741,213.8051
C.C. N 1,217,998.0919 E 1,739,794.9454
Back = S 22° 44' 24.23" E
Ahead = S 7° 52' 52.47" E
Chord Bear = S 15° 18' 38.35" E

Course from PT S56C to PC S56D S 7° 52' 52.47" E Dist 804.9963

Curve Data

Curve S56D
P.I. Station 34±78.01 N 1,217,294.7883 E 1,741,338.3504
Delta = 2° 03' 56.45" (RT)
Degree = 0° 59' 59.96"
Tangent = 103.2963
Length = 206.5703
Radius = 5,729.6406
External = 0.9311
Long Chord = 206.5591
Mid. Ord. = 0.9309
P.C. Station 33±74.72 N 1,217,397.1089 E 1,741,324.1864
P.T. Station 35±81.29 N 1,217,192.0236 E 1,741,348.8171
C.C. N 1,216,611.4591 E 1,735,648.6656
Back = S 7° 52' 52.47" E
Ahead = S 5° 48' 56.02" E
Chord Bear = S 6° 50' 54.25" E

Course from PT S56D to PC S56E S 5° 48' 56.02" E Dist 867.7406

Curve Data

Curve S56E
P.I. Station 46±08.03 N 1,216,170.5644 E 1,741,452.8534
Delta = 7° 56' 14.80" (LT)
Degree = 2° 30' 00.01"
Tangent = 159.0030
Length = 317.4973
Radius = 2,391.8276
External = 5.5091
Long Chord = 317.2435
Mid. Ord. = 5.4958
P.C. Station 44±49.03 N 1,216,328.7491 E 1,741,436.7422
P.T. Station 47±66.52 N 1,216,016.1200 E 1,741,490.6543
C.C. N 1,216,560.9720 E 1,743,716.7743
Back = S 5° 48' 56.02" E
Ahead = S 13° 45' 10.83" E
Chord Bear = S 9° 47' 03.42" E

Course from PT S56E to PC S56F S 13° 45' 10.83" E Dist 324.3609



Curve Data

Curve S56F
P.I. Station 53±42.30 N 1,215,456.8492 E 1,741,627.5381
Delta = 36° 25' 59.74" (RT)
Degree = 7° 29' 59.99"
Tangent = 251.4178
Length = 485.7770
Radius = 763.9440
External = 40.3080
Long Chord = 477.6341
Mid. Ord. = 38.2878
P.C. Station 50±90.88 N 1,215,701.0587 E 1,741,567.7668
P.T. Station 55±76.66 N 1,215,224.8733 E 1,741,530.5944
C.C. N 1,215,519.4410 E 1,740,825.7254
Back = S 13° 45' 10.83" E
Ahead = S 22° 40' 48.92" W
Chord Bear = S 4° 27' 49.05" W

Course from PT S56F to 427 S 22° 40' 48.92" W Dist 243.9352

Point 427 N 1,214,999.8014 E 1,741,436.5359 Sta 58±20.60

Ending chain S56 description



PRELIMINARY
NOT FOR CONSTRUCTION

SCALE: 1" = 100'



7			
6			
5			
4			
3			
2			
1			
REV. NO.	BY	DATE	DESCRIPTION OF REVISION

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION


REFERENCE DATA SHEET

S-56 (MONTGOMERY DRIVE)
OVER HORSE CREEK

FED. RD. DIV. NO.	STATE	COUNTY	PROJECT ID	ROAD / ROUTE NO.	SHEET NO.
3	SC	CHEROKEE	1162220	S-56	6



HYDROLOGY DATA	
DA = 1 SQ. MI.	
DESIGN FLOOD: 4% (25-YEAR)	
Q (AEP-4%) = 501 CFS	
V (AEP-4%) = 4.7 FT./SEC.	
W.S. ELEV. (AEP-4%) = 842.35 FT.	
DESIGN FLOOD: 1% (100-YEAR)	
Q (AEP-1%) = 718 CFS	
V (AEP-1%) = 4.7 FT./SEC.	
W.S. ELEV. (AEP-1%) = 843.31 FT.	
BACKWATER ELEVATION UPSTREAM OF BRIDGE:	
H.W. ELEV. (25 YR.) = 842.28 FT.	
(INCLUDING 0.69 FT. BACKWATER)	
H.W. ELEV. (100 YR.) = 843.49 FT.	
(INCLUDING 0.87 FT. BACKWATER)	
STRUCTURE OVERTOPPING FLOOD:	
0.2% AEP (500-YR.) FLOW = 985 CFS	
OVERTOPPING FLOW = GREATER THAN	
0.2% AEP (500-YR.) FLOW	



ALIGNMENT CONTROL CAN BE FOUND ON
REFERENCE DATA SHEET 5A



PRELIMINARY
NOT FOR CONSTRUCTION

HORIZONTAL SCALE: 1" = 50' VERTICAL SCALE: 1" = 10'

REV. NO.	BY	DATE	DESCRIPTION OF REVISION
7			
6			
5			
4			
3			
2			
1			

SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE SHEET

S-56 (MONTGOMERY DRIVE)
OVER HORSE CREEK

CONCEPTUAL PLANS

A.2 – Bridge Plans

S-138 over Goucher Creek

S-226 over Unnamed Stream

S-86 over Kings Creek

S-106 over Branch of Suck Creek

S-56 over Horse Creek

APPENDIX A





South Carolina Department of Transportation



PROPOSED PLANS
FOR

CHEROKEE COUNTY
PROJECT ID P041151
STATE ROUTE S-11-138 (GOUCHER SCHOOL ROAD)
REPLACE BRIDGE OVER GOUCHER CREEK

- INDEX OF SHEETS
- 1. TITLE SHEET
 - 2. BRIDGE PLAN AND PROFILE
 - 3. END BENT DETAILS (1)
 - 4. END BENT DETAILS (2)
 - 5. INTERIOR BENT DETAILS
 - 6. SUPERSTRUCTURE TYPICAL SECTION

Design Reference for these plans is the:

LVB

Supplemental Design Criteria For
Low Volume Bridge Replacement Projects

Approximate Location of Bridge is
Latitude 34°58'30" N
Longitude 81°41'39" W



SITE LOCATION

3 DAYS BEFORE DIGGING IN
SOUTH CAROLINA
CALL 811
SOUTH CAROLINA 811 (SC811)
WWW.SC811.COM
ALL UTILITIES MAY NOT BE A MEMBER OF SC811

ASSET ID NOT ASSIGNED

TRAFFIC DATA

2020 ADT 750 V.P.D.
2040 ADT 1,095 V.P.D.
TRUCKS 8 %



LAYOUT

NET LENGTH OF ROADWAY	0.000	MILES
NET LENGTH OF BRIDGES	0.022	MILES
NET LENGTH OF PROJECT	0.022	MILES
LENGTH OF EXCEPTIONS	0.000	MILES
GROSS LENGTH OF PROJECT	0.022	MILES

NOTE: EXCEPT AS MAY OTHERWISE BE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL CONFORM TO THE SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (2007 EDITION) AND THE STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN EFFECT AT THE TIME OF THE RELEASE OF THE FINAL RFP.

PLANS PREPARED BY:



110 MIDLANDS COURT
WEST COLUMBIA, SC 29169
Telephone: (803) 822-0333

ENGINEER OF RECORD



TECHNICAL PROPOSAL
PLANS


FOR CONSTRUCTION : _____
DATE

REVIEWED	WRS	09-22
DR.	JLJ	BY
	CHK	DATE


Z:\Projects\22-61Bridge Package 14\S-138 over Goucher Creek\Structures\Tech Proposal Plans\S-138_Goucher Cr _TITLE_SHT.dgn 10/19/2022

Z:\Projects\22-61Bridge Package 14\S-138 over Goucher Creek\Structures\Tech Proposal\Plans\S-138 Goucher Cr_PLAN.PROFILE.dgn 10/19/2022






END BENT 1 PLAN



END BENT 1 ELEVATION

(LOOKING BACK ON STATIONING)





END BENT 1 SECTION

**END BENT DEPTH INCREASED
(5'-0" vs. 3'-6") TO AVOID STREAM
IMPACTS OR LENGTHENED BRIDGE**


TECHNICAL PROPOSAL PLANS

REV.			
REV.			
REV.			
REVIEWED			
QUAN.			
DR.			
DES.			
	BY	CHK.	DAT

	
INFRASTRUCTURE CONSULTING & ENGINEERING	
SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION	
<u>END BENT DETAILS (1)</u>	
S-11-138 (GOUCHER SCHOOL ROAD) BRIDGE REPLACEMENT OVER GOUCHER CREEK	
COUNTY CHEROKEE	ROUTE S-11-138




END BENT 3 PLAN



END BENT 3 ELEVATION

(LOOKING IN DIRECTION OF STATIONING)




END BENT 3 SECTION

**END BENT DEPTH INCREASED
(5'-0" vs. 3'-6") TO AVOID STREAM
IMPACTS OR LENGTHENED BRIDGE**


TECHNICAL PROPOSAL PLANS

REV.			
REV.			
REV.			
REVIEWED			
QUAN.			
DR.			
DES.			
	BY	CHK.	DATE

	
INFRASTRUCTURE CONSULTING & ENGINEERING	
SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION	
<u>END BENT DETAILS (2)</u> S-11-138 (GOUCHER SCHOOL ROAD) BRIDGE REPLACEMENT OVER GOUCHER CREEK	
COUNTY	ROUTE
CHEROKEE	S-11-138



Z:\Projects\22-61Bridge Package 14\S-138 over Goucher Creek\Structures\Tech Proposal\Plans\S-138_Goucher Cr_TYP_SECT.dgn
10/19/2022

BRIDGE PLANS ID	SHEET NO.
P041151-B01	6




TYPICAL SECTION - 30'-0" SPAN
(LOOKING IN DIRECTION OF STATIONING)

INTERIOR SLAB SECTION - CORED SLAB




TYPICAL SECTION - 90'-0" SPAN
(LOOKING IN DIRECTION OF STATIONING)

INTERIOR SLAB SECTION - BOX BEAM



**TECHNICAL
PROPOSAL PLANS**

REV.			
REV.			
REV.			
REVIEWED			
QUAN.			
DR.			
DES.			
BY	CHK.	DATE	


INFRASTRUCTURE
CONSULTING & ENGINEERING

SOUTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SUPERSTRUCTURE
TYPICAL SECTION
S-11-138 (GOUCHER SCHOOL ROAD) BRIDGE
REPLACEMENT OVER GOUCHER CREEK

COUNTY CHEROKEE ROUTE S-11-138



South Carolina Department of Transportation



INDEX OF SHEETS

- 1. TITLE SHEET
- 2. BRIDGE PLAN AND PROFILE
- 3. END BENT DETAILS
- 4. SUPERSTRUCTURE TYPICAL SECTION


Design Reference for these plans is the:

LVB

Supplemental Design Criteria For
Low Volume Bridge Replacement Projects

PROPOSED PLANS
FOR
CHEROKEE COUNTY
PROJECT ID P041150
STATE ROUTE S-11-226 (HAMMETT GROVE ROAD)
REPLACE BRIDGE OVER UNNAMED STREAM

Approximate Location of Bridge is
Latitude 34°56'11" N
Longitude 81°44'55" W



SITE LOCATION

3 DAYS BEFORE DIGGING IN
SOUTH CAROLINA
CALL 811
SOUTH CAROLINA 811 (SC811)
WWW.SC811.COM
ALL UTILITIES MAY NOT BE A MEMBER OF SC811

ASSET ID NOT ASSIGNED

TRAFFIC DATA

2020 ADT 200 V.P.D.
2040 ADT 256 V.P.D.
TRUCKS 5 %



LAYOUT

NET LENGTH OF ROADWAY	0.000	MILES
NET LENGTH OF BRIDGES	0.015	MILES
NET LENGTH OF PROJECT	0.015	MILES
LENGTH OF EXCEPTIONS	0.000	MILES
GROSS LENGTH OF PROJECT	0.015	MILES

NOTE: EXCEPT AS MAY OTHERWISE BE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL CONFORM TO THE SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (2007 EDITION) AND THE STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN EFFECT AT THE TIME OF THE RELEASE OF THE FINAL RFP.

PLANS PREPARED BY:



110 MIDLANDS COURT
WEST COLUMBIA, SC 29169
Telephone: (803) 822-0333

ENGINEER OF RECORD

TECHNICAL PROPOSAL
PLANS


FOR CONSTRUCTION : _____
DATE

REVIEWED	WRS	WRS	09-22
DR.	JLJ	BY	CHK DATE

Z:\Projects\22-61Bridge Package 14\S-226 over Unnamed Stream\Structures\Tech Proposal\Plans\S-226_Unnamed Stream_TITLE_SHT.dgn
10/11/2022

Z:\Projects\22-61Bridge Package 14\S-226 over Unnamed Stream\Structures\Tech Proposal Plans\S-226_Unnamed Stream_PLAN_PROFILE.dgn
10/17/2022

BRIDGE PLANS ID	SHEET NO.
P041150-B01	2




NOTES:

BRIDGE END DRAINAGE NOT SHOWN. SEE ROADWAY PLANS.

(A) REMOVE AND DISPOSE OF EXISTING 56'-0" x 25'-6" 4-SPAN PRECAST CONCRETE BRIDGE AND APPURTENANCES IN ACCORDANCE WITH SECTION 202.4.2 OF THE STANDARD SPECIFICATIONS.

(*) INCLUDES 1'-0" MASH BARRIER AND 1" SLAB EXTENSION.

(M) DENOTES MTBBC2 GUARDRAIL ATTACHMENT




HYDROLOGY DATA


DA = 1 SQ. MI.
DESIGN FLOOD: 4% AEP (25-YR.)
Q (AEP-4%) = 684 CFS
V (AEP-4%) = 6.6 FT./SEC.
W.S. ELEV. (AEP-4%) = 544.38 FT.
DESIGN FLOOD: 1% AEP (100-YR.)
Q (AEP-1%) = 984 CFS
V (AEP-1%) = 7.0 FT./SEC.
W.S. ELEV. (AEP-1%) = 545.43 FT.

BACKWATER ELEVATION UPSTREAM OF BRIDGE:
4% AEP (25-YR.) H.W. ELEV. = 544.38 FT.
(INCLUDING 0.48 FT. BACKWATER)
1% AEP (100-YR.) H.W. ELEV. = 545.43 FT.
(INCLUDING 0.71 FT. BACKWATER)

STRUCTURE OVERTOPPING FLOOD:
0.2% AEP (500-YR.) FLOW = 1,350 CFS
OVERTOPPING FLOW = GREATER THAN 0.02% AEP (500-YR.) FLOW

LOW CHORD LESS THAN EXISTING BRIDGE LOW CHORD





TYPICAL SECTION
(LOOKING IN DIRECTION OF STATIONING)



South Carolina Department of Transportation



PROPOSED PLANS FOR

CHEROKEE COUNTY PROJECT ID P041152 STATE ROUTE S-11-86 (ROCK HOUSE ROAD) REPLACE BRIDGE OVER KINGS CREEK

INDEX OF SHEETS

1. TITLE SHEET
2. BRIDGE PLAN AND PROFILE
3. END BENT DETAILS (1)
4. END BENT DETAILS (2)
5. INTERIOR BENT DETAILS
6. SUPERSTRUCTURE TYPICAL SECTION


Design Reference for these plans is the:

LVB


Supplemental Design Criteria For
Low Volume Bridge Replacement Projects

Approximate Location of Bridge is

Latitude 35°08'44" N
Longitude 81°24'34" W



SITE LOCATION



3 DAYS BEFORE DIGGING IN
SOUTH CAROLINA

CALL 811

SOUTH CAROLINA 811 (SC811)
WWW.SC811.COM
ALL UTILITIES MAY NOT BE A MEMBER OF SC811

ASSET ID NOT ASSIGNED

TRAFFIC DATA

2020 ADT 200 V.P.D.
2040 ADT 256 V.P.D.
TRUCKS 5 %



LAYOUT

NET LENGTH OF ROADWAY	0.000	MILES
NET LENGTH OF BRIDGES	0.030	MILES
NET LENGTH OF PROJECT	0.030	MILES
LENGTH OF EXCEPTIONS	0.000	MILES
GROSS LENGTH OF PROJECT	0.030	MILES

NOTE: EXCEPT AS MAY OTHERWISE BE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL CONFORM TO THE SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (2007 EDITION) AND THE STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN EFFECT AT THE TIME OF THE RELEASE OF THE FINAL RFP.

PLANS PREPARED BY:



110 MIDLANDS COURT
WEST COLUMBIA, SC 29169
Telephone: (803) 822-0333

ENGINEER OF RECORD


TECHNICAL PROPOSAL PLANS

FOR CONSTRUCTION : _____
DATE _____

REVIEWED	WRS	09-22
DR.	JLJ	BY
	CHK	DATE




Z:\Projects\22-61Bridge Package 14\S-86 over Kings Creek\Structures\Tech ProposalPlans\S-86_Kings Cr_TITLE_SHT.dgn
10/17/2022

Z:\Projects\22-61Bridge Package\4\S-86 over Kings Creek\Structures\Tech Proposal\Plans\S-86_Kings Cr._PLAN_PROFILE.dgn 10/17/2022




Z:\Projects\22-61 Bridge Package 14\S-86 over Kings Creek\Structures\Tech Proposal\Plans\S-86_Kings Cr_END_BENT_DETAILS.dgn
10/17/2022

BRIDGE PLANS ID	SHEET NO.
P041152-B01	3






TECHNICAL
PROPOSAL PLANS

REV.			
REV.			
REV.			
REVIEWED			
QUAN.			
DR.			
DES.			
BY	CHK.	DATE	

lane 	
INFRASTRUCTURE CONSULTING & ENGINEERING	
SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION	
END BENT DETAILS (1) S-11-86 (ROCK HOUSE ROAD) BRIDGE REPLACEMENT OVER KINGS CREEK	
COUNTY CHEROKEE	ROUTE S-11-86

Z:\Projects\22-61 Bridge Package 14\S-86 over Kings Creek\Structures\Tech Proposal\Plans\S-86_Kings Cr_END_BENT_DETAILS (2).dgn
10/17/2022

BRIDGE PLANS ID	SHEET NO.
P041152-B01	4






TECHNICAL
PROPOSAL PLANS

REV.			
REV.			
REV.			
REVIEWED			
QUAN.			
DR.			
DES.			
BY	CHK.	DATE	

lane 	
INFRASTRUCTURE CONSULTING & ENGINEERING	
SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION	
END BENT DETAILS (2) S-11-86 (ROCK HOUSE ROAD) BRIDGE REPLACEMENT OVER KINGS CREEK	
COUNTY CHEROKEE	ROUTE S-11-86

Z:\Projects\22-61 Bridge Package 14\S-86 over Kings Creek\Structures\Tech Proposal\Plans\S-86_Kings Cr_INTERIOR_BENT_DETAILS.dgn
10/17/2022

BRIDGE PLANS ID	SHEET NO.
P041152-B01	5



TECHNICAL PROPOSAL PLANS

REV.			
REV.			
REV.			
REVIEWED			
QUAN.			
DR.			
DES.			
BY	CHK.	DATE	

lane 	
INFRASTRUCTURE CONSULTING & ENGINEERING	
SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION	
INTERIOR BENT DETAILS	
S-11-86 (ROCK HOUSE ROAD) BRIDGE REPLACEMENT OVER KINGS CREEK	
COUNTY CHEROKEE	ROUTE S-11-86



South Carolina Department of Transportation



PROPOSED PLANS
FOR

CHEROKEE COUNTY
PROJECT ID P041149

STATE ROUTE S-11-106 (ISLAND CREEK ROAD)
REPLACE BRIDGE OVER BRANCH OF SUCK CREEK

Design Reference for these plans is the:


LVB

Supplemental Design Criteria For
Low Volume Bridge Replacement Projects

INDEX OF SHEETS

1. TITLE SHEET
2. BRIDGE PLAN AND PROFILE
3. END BENT DETAILS
4. SUPERSTRUCTURE TYPICAL SECTION

Approximate Location of Bridge is
Latitude 35°07'22" N
Longitude 81°50'02" W



SITE LOCATION

3 DAYS BEFORE DIGGING IN
SOUTH CAROLINA

CALL 811

SOUTH CAROLINA 811 (SC811)
WWW.SC811.COM
ALL UTILITIES MAY NOT BE A MEMBER OF SC811

ASSET ID NOT ASSIGNED

TRAFFIC DATA

2020 ADT 225 V.P.D.

2040 ADT 329 V.P.D.

TRUCKS 8 %



LAYOUT

NET LENGTH OF ROADWAY	0.000	MILES
NET LENGTH OF BRIDGES	0.011	MILES
NET LENGTH OF PROJECT	0.011	MILES
LENGTH OF EXCEPTIONS	0.000	MILES
GROSS LENGTH OF PROJECT	0.011	MILES

NOTE: EXCEPT AS MAY OTHERWISE BE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL CONFORM TO THE SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (2007 EDITION) AND THE STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN EFFECT AT THE TIME OF THE RELEASE OF THE FINAL RFP.

PLANS PREPARED BY:



110 MIDLANDS COURT
WEST COLUMBIA, SC 29169
Telephone: (803) 822-0333

ENGINEER OF RECORD


TECHNICAL PROPOSAL
PLANS

FOR CONSTRUCTION : _____
DATE

REVIEWED	WRS	09-22
DR.	JLJ	BY
	CHK	DATE

Z:\Projects\22-61Bridge Package 14\S-106 over Suck Creek\Structures\Tech Proposal\Plans\S-106_Suck Cr _TITLE_SHT.dgn
10/17/2022



BRIDGE PLANS ID	SHEET NO.
P041149-B01	2




NOTES:

BRIDGE END DRAINAGE NOT SHOWN. SEE
ROADWAY PLANS.

- (A) REMOVE AND DISPOSE OF EXISTING 35'-0" x 25'-0" ± SINGLE SPAN STEEL BRIDGE AND APPURTENANCES IN ACCORDANCE WITH SECTION 202.4.2 OF THE STANDARD SPECIFICATIONS. REMOVE AND DISPOSE OF EXISTING ABUTMENT WALL DOWN TO NORMAL WATER ELEVATION LEAVING THE BOTTOM PORTION OF WALL IN PLACE DURING CONSTRUCTION, TO AVOID ENVIRONMENTAL IMPACTS TO THE CREEK.
- (B) 91°51'29.7" TO LOCAL TANGENT (TYP.)
- (*) INCLUDES 1'-0" MASH BARRIER AND 1" SLAB EXTENSION.
- (M) DENOTES MTBBC2 GUARDRAIL ATTACHMENT






**DESIGN EXCEPTION: BLOCK-OUT
IN PARAPET INSTEAD OF
4" DIA. DECK DRAIN SHOWN ON
SCDOT STD. DWG. 704-29a**

TYPICAL SECTION
(LOOKING IN DIRECTION OF STATIONING)

(A) DUE TO THE SAG VERTICAL CURVE AND BEAM CAMBER, THE
OVERLAY THICKNESS WILL VARY ALONG THE LENGTH OF
THE BRIDGE. THE MINIMUM OVERLAY THICKNESS SHALL BE 2".



INTERIOR CORED SLAB SECTION

TECHNICAL PROPOSAL PLANS

REV.			
REV.			
REV.			
REVIEWED			
QUAN.			
DR.			
DES.			
	BY	CHK.	DATE

lane 



INFRASTRUCTURE
CONSULTING & ENGINEERING


**SOUTH CAROLINA
DEPARTMENT OF TRANSPORTATION**

SUPERSTRUCTURE
TYPICAL SECTION


S-11-106 (ISLAND CREEK ROAD) BRIDGE
REPLACEMENT OVER BRANCH OF SUCK CREEK

COUNTY	CHEROKEE	ROUTE	S-11-106
--------	----------	-------	----------

Z:\Projects\22-6\Bridge Package 14\S-56 over Horse Creek\Structures\Tech Proposal Plans\S-56_Horse Cr_TITLE_SHT.dgn
10/17/2022






TYPICAL THROUGHOUT BRIDGE
SUPERELEVATION
SKETCH



Z:\Projects\22-6\Bridge Package 14\S-56 over Horse Creek\Structures\Tech Proposal Plans\S-56_Horse Cr_END_BENT_DETAIL S.dgn
10/17/2022


BRIDGE PLANS ID	SHEET NO.
P041148-B01	3



END BENT ELEVATION
(END BENT 2 SHOWN LOOKING IN DIRECTION OF STATIONING, END BENT 1 SIMILAR)

TECHNICAL
PROPOSAL PLANS


REV.			
REV.			
REV.			
REVIEWED			
QUAN.			
DR.			
DES.			
BY	CHK.	DATE	


INFRASTRUCTURE
CONSULTING & ENGINEERING

SOUTH CAROLINA
DEPARTMENT OF TRANSPORTATION


END BENT DETAILS
S-11-56 (MONTGOMERY ROAD)
BRIDGE REPLACEMENT OVER HORSE CREEK

COUNTY CHEROKEE ROUTE S-11-56



TYPICAL SECTION
(LOOKING IN DIRECTION OF STATIONING)

**DESIGN EXCEPTION: BLOCK-OUT
IN PARAPET INSTEAD OF
4" DIA. DECK DRAIN SHOWN ON
SCDOT STD. DWG. 704-29a**



INTERIOR CORED SLAB SECTION

TECHNICAL PROPOSAL PLANS

REV.			
REV.			
REV.			
REVIEWED			
QUAN.			
DR.			
DES.			
	BY	CHK.	DATE



INFRASTRUCTURE
CONSULTING & ENGINEERING

**SOUTH CAROLINA
DEPARTMENT OF TRANSPORTATION**

SUPERSTRUCTURE
TYPICAL SECTION

S-11-56 (MONTGOMERY ROAD)
BRIDGE REPLACEMENT OVER HORSE CREEK

COUNTY	CHEROKEE	ROUTE	S-11-56
--------	----------	-------	---------


CONCEPTUAL PLANS

A.3 – CPM Schedule

APPENDIX A



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County

[illegible]

 Remaining Level of Effort
 Remaining Work
 Milestone

 Actual Work
  Critical Remaining Work

Technical Proposal Schedule



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County

Activity ID		Activity Name	Original Duration	Start	Finish	Sep-23	Oct-23	Nov-23	Dec-23	Jan-24	Feb-24	Mar-24	Apr-24	May-24	Jun-24	Jul-24	Aug-24	Sep-24	Oct-24	Nov-24	Dec-24	Jan-25	Feb-25	Mar-25	Apr-25	May-25	Jun-25	Jul-25	Aug-25	Sep-25	Oct-25	Nov-25	Dec-25
SR S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)			136	09-Feb-23	22-Aug-23																												
ROW / Preliminary Plan Package			69	09-Feb-23	17-May-23																												
D1980		Prepare Right-of-Way Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	27	09-Feb-23	20-Mar-23																												
D1990		Prepare Preliminary Bridge Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	27	09-Feb-23	20-Mar-23																												
D2000		Submit ROW / Preliminary Plan Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	0		22-Mar-23																												
Review			40	23-Mar-23	17-May-23																												
D1480		Review Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	15	23-Mar-23	12-Apr-23																												
D1490		Respond to Comments - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	5	13-Apr-23	19-Apr-23																												
D1500		Status Comments - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	5	20-Apr-23	26-Apr-23																												
D1510		Submit Responses - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	5	27-Apr-23	03-May-23																												
D1520		Update Statuses / Closeout Comments - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	10	04-May-23	17-May-23																												
Final Package			65	18-May-23	18-Aug-23																												
D2130		Prepare Final Roadway Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	25	18-May-23	22-Jun-23																												
D2140		Prepare Final Bridge Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	25	18-May-23	22-Jun-23																												
D2150		Submit Final Roadway and Bridge Packages - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	0		22-Jun-23																												
Review			40	23-Jun-23	18-Aug-23																												
D1530		Review Final Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	15	23-Jun-23	14-Jul-23																												
D1540		Respond to Comments Final Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	5	17-Jul-23	21-Jul-23																												
D1550		Status Comments Final Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	5	24-Jul-23	28-Jul-23																												
D1560		Submit Responses Final Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	5	31-Jul-23	04-Aug-23																												
D1570		Update Statuses / Closeout Comments Final Submittal Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	10	07-Aug-23	18-Aug-23																												
RFC Plans			2	21-Aug-23	22-Aug-23																												
D2570		Sign and Submit RFC Roadway Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	2	21-Aug-23	22-Aug-23																												
D2580		Sign and Submit RFC Bridge Package - S-11-226 Unnamed Creek Bridge (Hammett Grove Rd)	2	21-Aug-23	22-Aug-23																												
SR S-11-86 Kings Creek Bridge (Rock House Rd)			131	21-Mar-23	22-Sep-23																												
ROW / Preliminary Plan Package			64	21-Mar-23	19-Jun-23																												
D2010		Prepare Right-of-Way Submittal Package - S-11-86 Kings Creek Bridge (Rock House Rd)	24	21-Mar-23	21-Apr-23																												
D2020		Prepare Preliminary Bridge Submittal Package - S-11-86 Kings Creek Bridge (Rock House Rd)	24	21-Mar-23	21-Apr-23																												
D2030		Submit ROW / Preliminary Plan Package - S-11-86 Kings Creek Bridge (Rock House Rd)	0		21-Apr-23																												

 Remaining Level of Effort
  Remaining Work
 ◆ ◆ Milestone
 Actual Work
 Critical Remaining Work

Technical Proposal

Schedule



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County

Activity ID		Activity Name		Original Duration	Start	Finish	2023												2024												2025											
							Sep-23	Oct-23	Nov-23	Dec-23	Jan-24	Feb-24	Mar-24	Apr-24	May-24	Jun-24	Jul-24	Aug-24	Sep-24	Oct-24	Nov-24	Dec-24	Jan-25	Feb-25	Mar-25	Apr-25	May-25	Jun-25	Jul-25	Aug-25	Sep-25	Oct-25	Nov-25	Dec-25								
Review				40	27-Sep-23	24-Nov-23																																				
D1680	Review Submittal Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			15	27-Sep-23	18-Oct-23																																				
D1690	Respond to Comments - S-11-106 Suck Creek Bridge (Island Creek Rd)			5	19-Oct-23	25-Oct-23																																				
D1700	Status Comments - S-11-106 Suck Creek Bridge (Island Creek Rd)			5	26-Oct-23	01-Nov-23																																				
D1710	Submit Responses - S-11-106 Suck Creek Bridge (Island Creek Rd)			5	02-Nov-23	08-Nov-23																																				
D1720	Update Statuses / Closeout Comments - S-11-106 Suck Creek Bridge (Island Creek Rd)			10	09-Nov-23	24-Nov-23																																				
Final Package				55	27-Nov-23	14-Feb-24																																				
D2190	Prepare Final Roadway Submittal Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			15	27-Nov-23	15-Dec-23																																				
D2200	Prepare Final Bridge Submittal Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			15	27-Nov-23	15-Dec-23																																				
D2210	Submit Final Roadway and Bridge Packages - S-11-106 Suck Creek Bridge (Island Creek Rd)			0		15-Dec-23																																				
Review				40	18-Dec-23	14-Feb-24																																				
D1730	Review Final Submittal Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			15	18-Dec-23	09-Jan-24																																				
D1740	Respond to Comments Final Submittal Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			5	10-Jan-24	17-Jan-24																																				
D1750	Status Comments Final Submittal Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			5	18-Jan-24	24-Jan-24																																				
D1760	Submit Responses Final Submittal Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			5	25-Jan-24	31-Jan-24																																				
D1770	Update Statuses / Closeout Comments Final Submittal Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			10	01-Feb-24	14-Feb-24																																				
RFC Plans				2	15-Feb-24	16-Feb-24																																				
D2610	Sign and Submit RFC Roadway Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			2	15-Feb-24	16-Feb-24																																				
D2620	Sign and Submit RFC Bridge Package - S-11-106 Suck Creek Bridge (Island Creek Rd)			2	15-Feb-24	16-Feb-24																																				
SR S-11-56 Horse Creek Bridge (Montgomery Dr)				117	13-Sep-23	04-Mar-24																																				
ROW / Preliminary Plan Package				60	13-Sep-23	08-Dec-23																																				
D2070	Prepare Right-of-Way Submittal Package - S-11-56 Horse Creek Bridge (Montgomery Dr)			20	13-Sep-23	10-Oct-23																																				
D2080	Prepare Preliminary Bridge Submittal Package - S-11-56 Horse Creek Bridge (Montgomery Dr)			20	13-Sep-23	10-Oct-23																																				
D2090	Submit ROW / Preliminary Plan Package - S-11-56 Horse Creek Bridge (Montgomery Dr)			0		10-Oct-23																																				
Review				40	12-Oct-23	08-Dec-23																																				
D1780	Review Submittal Package - S-11-56 Horse Creek Bridge (Montgomery Dr)			15	12-Oct-23	01-Nov-23																																				
D1790	Respond to Comments - S-11-56 Horse Creek Bridge (Montgomery Dr)			5	02-Nov-23	08-Nov-23																																				
D1800	Status Comments - S-11-56 Horse Creek Bridge (Montgomery Dr)			5	09-Nov-23	16-Nov-23																																				
D1810	Submit Responses - S-11-56 Horse Creek Bridge (Montgomery Dr)			5	17-Nov-23	24-Nov-23																			</																	

 Remaining Level of Effort
 Remaining Work
 ◆ ◆ Milestone
 Actual Work
 Critical Remaining Work

Technical Proposal Schedule



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County

[illegible]

 Remaining Level of Effort
 Remaining Work
 Milestone

 Actual Work
 Critical Remaining Work

Technical Proposal Schedule



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County

[illegible]

 Remaining Level of Effort
  Remaining Work
  Milestone

 Actual Work
 Critical Remaining Work

Technical Proposal Schedule



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County

Activity ID	Activity Name	Original Duration	Start	Finish	2023												2024												2025																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
					Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
SR S-11-106 Traffic Control along Island Creek Rd		437	11-Apr-23	20-Jun-24																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													

 Remaining Level of Effort
  Remaining Work
  Milestone

 Actual Work
 Critical Remaining Work

Technical Proposal Schedule



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County

[illegible]

 Remaining Level of Effort
  Remaining Work
 ◆ ◆ Milestone
 Actual Work
 Critical Remaining Work

Technical Proposal Schedule



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County

[illegible]

 Remaining Level of Effort
 Remaining Work
 Milestone

 Actual Work
  Critical Remaining Work

Technical Proposal

Schedule



SCDOT Bridge Package 14 DB Project Contract ID 1162220 - Cherokee County

Activity ID	Activity Name	Original Duration	Start	Finish	2023												2024												2025																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
					Sep-24	Oct-24	Nov-24	Dec-24	Jan-25	Feb-25	Mar-25	Apr-25	May-25	Jun-25	Jul-25	Aug-25	Sep-25	Oct-25	Nov-25	Dec-25	Jan-26	Feb-26	Mar-26	Apr-26	May-26	Jun-26	Jul-26	Aug-26	Sep-26	Oct-26																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
	SR S-11-106 - Roadway Improvements along Island Creek Rd	25	16-May-24	27-Jun-24																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			

 Remaining Level of Effort  Remaining Work   Milestone
 Actual Work  Critical Remaining Work

Technical Proposal
Schedule



REQUIRED FORMS



APPENDIX B

12. STIPEND ACKNOWLEDGEMENT FORM

Stipend Acknowledgement Form

Bridge Package 14 Cherokee County

Proposer: The Lane Construction Corporation

ADDRESS: 90 Fieldstone Court, Cheshire, CT 06410

The undersigned Proposer, hereby:



Waives the stipend for this Project.



Accepts the stipend for this Project.

By accepting the stipend for this Project, Proposer agrees:


- 1) to execute and include the Stipend Agreement in Article XIII of the RFP with its RFP response;
- 2) to submit an invoice with FEIN number for the stipend amount to the SCDOT POC after SCDOT's posting of the Notice of Award on SCDOT's Design-Build Website.;
- 3) to transfer all rights to its Work Product used to develop the Proposal as of the date of this acknowledgement. "Work Product" means all submittals, including ATCs, ideas, innovations, solutions, methods, processes, design concepts, materials, electronic files, marked up drawings, cross sections, quantity lists and intellectual property, made by Proposer during the RFP process, including the Proposal, exchange of information during the pre-Proposal and post-Proposal period.

SCDOT will pay the stipend to each eligible unsuccessful Proposer, who has signed a Stipend Agreement, within ninety (90) days after execution of the Contract or the decision to not award a contract.

Date

10/17/2022

Proposer



Ignacio Botella

Print Name

13. STIPEND AGREEMENT

STIPEND AGREEMENT

Project ID: 1162220

Bridge Package 14

Cherokee County

THIS STIPEND AGREEMENT (the "Agreement") is made and entered into as of the ____ day of October, 20__, by and between the SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION (hereinafter "SCDOT"), and The Lane Construction Corporation ("Proposer"), with reference to the following facts:

SCDOT issued a Request for Proposal ("RFP") for design and construction of the above-referenced Design-Build Project ("Project"), pursuant to procurement authority granted in Section 57-5-1625 of the S.C. Code of Laws, 1976, as amended. The RFP provided for payment of stipends as provided herein. Capitalized terms used, but not defined, have the meanings ascribed in the RFP.

NOW, THEREFORE, Proposer hereby agrees as follows:

1. Work Product.

1.1 Proposer shall prepare and submit a responsible and responsive Technical Proposal and Cost Proposal that conforms in all material respects to the requirements and provisions of the RFP, as determined by SCDOT, and are timely received by SCDOT in accordance with the RFP Milestone Schedule.

1.2 By signing this Stipend Agreement, Proposer agrees to transfer full and complete ownership to SCDOT of all Work Product. The Work Product (as defined below) shall become the property of SCDOT without restriction or limitation on its use, without further compensation or consideration, and can be used in connection with this Project or any future projects by SCDOT. Neither Proposer nor any of its team members shall copyright any of the material developed under this Agreement.

1.3 The term "Work Product" shall mean the Proposal and all material, electronic files, marked up drawings, cross sections, quantity lists, submittals, alternative technical concepts (ATC), ideas, innovations, solutions, methods, processes, design concepts, Trade Secrets or confidential information, and intellectual property, made by or produced for Proposer in the development and submission of the Technical and Cost Proposal, including exchanges of information during the pre-Proposal and post-Proposal period.

2. Compensation and Payment.

2.1 A stipend to Proposer for the Work Product described herein shall be \$25,000.00 and is payable to Proposer that was determined to be responsible and (1) submitted a responsive Technical Proposal and responsive Cost Proposal to the RFP which is not selected for award of this Project, or (2) was awarded the Contract but the Contract was terminated by SCDOT for convenience after the Submittal of Proposal Due Date (See Final RFP Milestone schedule) but prior to the Notice to Proceed #1. Responsibility of Proposers and responsiveness of the Technical Proposal and Cost Proposal will be determined by SCDOT as a condition of payment.

2.2 SCDOT will pay the stipend to Proposer as follows, subject (as applicable) to the following conditions:

- (a) Proposer has submitted this signed Stipend Agreement, unchanged with its response to the RFP.
- (b) After posting of the Notice of Award on SCDOT's Design-Build Website, Proposer has submitted to SCDOT an invoice, with FEIN Number, for the Stipend amount.
- (c) After execution of the Contract or the decision not to award a contract, SCDOT will pay the invoice for the stipend amount to the unsuccessful Proposer meeting the criteria of Section 2.1 within 90 calendar days of receipt of the invoice from Proposer.
- (d) If the procurement is suspended or cancelled prior to the Proposal Due Date (see FINAL RFP Milestone schedule), no stipend will be paid to Proposer.
- (e) After the submittal of Proposals, but prior to award, if the procurement is cancelled, all Proposers that provide a responsive Technical Proposal and Cost Proposal to the final RFP and submitted a signed Stipend Agreement with their RFP shall receive the stipend.
- (f) In the event of a Best and Final Offer, only one stipend will be paid to each Proposer that executed a Stipend Agreement and met the other criteria and conditions herein.
- (g) No stipends will be paid for submitting RFQ responses.
- (h) No stipends will be paid to a Proposer who withdraws at any time from this procurement.

2.3 Acceptance by the Proposer of payment of the stipend amount from SCDOT shall constitute a waiver by Proposer of any and all right, equitable or otherwise, to bring any claim in connection with this procurement, procurement process, award of the Contract, or cancellation of this procurement.

2.4 The Proposer awarded the contract shall be not eligible to receive a stipend.

2.5 If Proposer elects to waive payment of the stipend, SCDOT will not use the ideas or information contained in that Proposer's Proposal for this Project. However, the Proposer's Proposal will be subject to the South Carolina Freedom of Information Act.

3. Indemnities.

3.1 Subject to the limitations contained in Section 3.2, Proposer shall indemnify, protect and hold harmless SCDOT and its directors, officers, employees and contractors from, and Proposer shall defend at its own expense, all claims, costs, expenses, liabilities, demands, or suits at law or equity arising, in whole or in part, from the negligence or willful misconduct of Proposer or any of its agents, officers, employees, representatives or subcontractors or breach of any of Proposer's obligations under this Agreement.

3.2 This indemnity shall not apply with respect to any claims, demands or suits arising from use of the Work Product by SCDOT.

4. Compliance With Laws.

4.1 Proposer shall comply with all federal, state, and local laws, ordinances, rules, and regulations applicable to the work performed or paid for under this Agreement and covenants and agrees that it and its employees shall be bound by the standards of conduct provided in applicable laws, ordinances, rules, and regulations as they relate to work performed under this Agreement. Proposer agrees to incorporate the provisions of this paragraph in any subcontract into which it might enter with reference to the work performed pursuant to this Agreement.

4.2 The Proposer agrees (a) not to discriminate in any manner against an employee or applicant for employment because of race, color, religion, creed, age, sex, marital status, national origin, ancestry or disability of a qualified individual with a disability; (b) to include a provision similar to that contained in subsection (a) in any subcontract; and (c) to post and to cause subcontractors to post in conspicuous places available to employees and applicants for employment, notices setting forth the substance of this clause.

5. Assignment.

Proposer shall not assign this Agreement without SCDOT's prior written consent. Any assignment of this Agreement without such consent shall be null and void.

6. Miscellaneous.

6.1 Proposer and SCDOT agree that Proposer, its team members, and their respective employees are not agents of SCDOT as a result of this Agreement.

6.2 This Agreement, together with the RFP, as amended from time to time, the provisions of which are incorporated herein by reference, embodies the entire agreement of the parties. There are no promises, terms, conditions, or obligations other than those contained herein or in the RFP, and this Agreement shall supersede all previous communications, representation, or agreements, either oral or written, between the parties hereto.

6.3 It is understood and agreed by the parties hereto that if any part, term, or provision of this Agreement is by the courts held to be illegal or in conflict with any law of the State of South Carolina, the validity of the remaining portions or provisions shall not be affected, and the rights and obligations of the parties shall be construed and enforced as if the Agreement did not contain the particular part, term, or provisions to be invalid.

6.4 This Agreement shall be governed by and construed in accordance with the laws of the State of South Carolina.

IN WITNESS WHEREOF, the parties have executed this Agreement as of the date first written above.

Witness:

Recommended:

{INSERT NAME}
Alternative Delivery Program Manager

Witness:




SOUTH CAROLINA DEPARTMENT
OF TRANSPORTATION

By: _____
{INSERT NAME}
Alternative Delivery Engineer

Proposer

The Lane Construction Corporation

Name of Proposer
By: 
Its: President and CEO

11. EQUAL EMPLOYMENT OPPORTUNITY CERTIFICATION

(COMPLETE THIS SECTION FOR FEDERAL PROJECTS ONLY) EQUAL EMPLOYMENT OPPORTUNITY PERFORMANCE

Select the Certification that applies to the PROPOSER:

Certification (1) ☒ or Certification (2) ☐

Select the appropriate responses in the applicable Certification:

Certification (1): Pursuant to 41 C.F.R. §60-1.7(b)(1), Previous Equal Employment Opportunity Performance Certification, as the Prospective Prime Contractor, I HEREBY CERTIFY THAT I:

(a) **(HAVE / HAVE NOT)** developed and filed an Affirmative Action Program pursuant to 41 C.F.R. §60-2 and/or 60-4;

(b) **(HAVE / HAVE NOT)** participated in a previous contract or subcontract subject to the equal opportunity clause;

(c) **(HAVE / HAVE NOT)** filed with the Joint Reporting Committee, the Director of Office of Federal Contract Compliance, or the Equal Employment Opportunity Commission, all reports due under the applicable filing requirements,

OR

Certification (2): I, HEREBY CERTIFY that as the Prospective Prime Contractor submitting this Proposal, **(CLAIM / DO NOT CLAIM)** exemption from the submission of the Standard Form 100 (EEO-1) due to the fact that it employs a total of less than fifty (50) employees under C.F.R. §60-1.7, or qualifies for an exempted status under 41 C.F.R. §60-1.5.

I FURTHER CERTIFY that the above Certification will be made part of any Subcontract Agreement, or other agreement involved with this project.

Executed on 10/17, 2022.

Signed: 

(Officer/PROPOSER)

Title: President & Chief Executive Officer

Company: The Lane Construction Corporation

Address: 90 Fieldstone Court, Cheshire, CT 06410

Note: The above certification is required by the Equal Employment Opportunity Regulations of the Secretary of Labor (41 CFR 60-1.7(b)(1)), and must be submitted by PROPOSERS only in connection with contracts which are subject to the equal opportunity clause. Contracts that are exempt from the equal opportunity clause are set forth in 41 CFR 60-1.5. (Generally, only contracts of \$10,000 or under are exempt.)

Currently, Standard Form 100 (EEO-1) is the only report required by Executive Orders or their implementing regulations.

Proposers, Primary Members, or proposed Subcontractors (any tier) and Consultants who have participated in a previous contract subject to the Executive Orders and have not filed the required reports shall note that 41 CFR 60-1.7(b)(1) prevents the award of contracts and subcontracts unless such contractor submits a report covering the delinquent period or such other period specified by the Federal Highway Administration or by the Director, Office of Federal Contract Compliance, U.S. Department of Labor.

10. NON-COLLUSION CERTIFICATION

NON-COLLUSION CERTIFICATION

Project ID: 1162220

IN ACCORDANCE WITH THE PROVISIONS OF S.C. CODE ANN. §§ 39-3-10 ET.SEQ., 39-5-10 ET. SEQ., 15 U.S.C. §45; 23 C.F.R. §635.112(F); AND 28 U.S.C. §1746, I HEREBY ACKNOWLEDGE THAT I AM AN OFFICER OF THE PROPOSER FIRM AND, UNDER PENALTY OF PERJURY UNDER THE LAWS OF THE UNITED STATES AND SOUTH CAROLINA, DECLARE, BY MY CERTIFICATION BELOW, THAT THE FOLLOWING IS TRUE AND CORRECT, AND FURTHER, THAT THIS JOINT-VENTURE, FIRM, PARTNERSHIP, ASSOCIATION OR CORPORATION, OR ANY OTHER LEGAL ENTITY HAS NOT, EITHER DIRECTLY OR INDIRECTLY, ENTERED INTO ANY AGREEMENT, PARTICIPATED IN ANY COLLUSION, OR OTHERWISE TAKEN ANY ACTION IN RESTRAINT OF FREE COMPETITIVE BIDDING IN CONNECTION WITH THE SUBMISSION OF A BID PROPOSAL ON THE ABOVE REFERENCED PROJECT.

BY CHECKING THIS BOX ☒ , I CERTIFY THAT I HAVE READ, UNDERSTAND, ACCEPT, AND ACKNOWLEDGE ALL OF THE ABOVE STATEMENTS.

Executed on 10/17/2022
(Date)

Signed: 
(Officer/Proposer)

President & Chief Executive Officer
(Title)

90 Fieldstone Court Cheshire, CT 06410
(Address)



South Carolina
Department of Transportation

NOTICE TO PROPOSERS

Bridge Package 14
Design-Build – Contract ID 1162220
Cherokee County

September 15, 2022

NOTICE TO PROPOSERS - Enclosed is **Addendum 1** to the Request for Proposals (RFP) for the Bridge Package 14 design-build project. The information provided in this notice and the addendum shall be made part of the contract documents.

The **yellow** highlights identify the revisions associated with Addendum 1.

This addendum is being issued in order to provide clarification and additional information for the project. The following sections of the RFP contain revisions:

- Request for Proposals Instructions – Title Page
- Agreement – IV. Contract Time, Act 36 language, XVIII. DBE revision
- Exhibit 4a – Roadway Design Criteria – 2.15 Right-of-Way
- Exhibit 4e – Hydraulic Design Criteria – Section 2.2.1.8





South Carolina
Department of Transportation

NOTICE OF RECEIPT
Bridge Package 14
Design-Build – Contract ID 1162220
Cherokee County


Addendum 1

The information in this addendum shall be made part of the contract documents. PROPOSERS are instructed to incorporate the information into the previously provided RFP documents.

PROPOSERS are required to sign this document and enclose it with their Technical Proposal. Receipt of this signed document by The South Carolina Department of Transportation serves as confirmation that the PROPOSER has received and incorporated this Addendum into the contract documents.

Confirmation Statement:

I, the PROPOSER confirm that I have received this addendum package and have incorporated the information provided in the addendum into the contract documents.



PROPOSER's Signature

10/17/2022

Date

Ignacio Botella

Printed Name

For: The Lane Construction Corporation

Design-Build Team Name





South Carolina
Department of Transportation

NOTICE TO PROPOSERS

Bridge Package 14
Design-Build – Contract ID 1162220
Cherokee County

October 13, 2022

NOTICE TO PROPOSERS - Enclosed is **Addendum 2** to the Request for Proposals (RFP) for the Bridge Package 14 design-build project. The information provided in this notice and the addendum shall be made part of the contract documents.

The **yellow** highlights identify the revisions associated with Addendum 1. The **green** highlights identify the revisions associated with Addendum 1.

This addendum is being issued in order to provide clarification and additional information for the project. The following sections of the RFP contain revisions:

- Request for Proposals Instructions – Title Page, Section 4.1 Technical Proposal appendices
- Agreement – Section IV.A.1.c - Contract Time
- Project Information Package –
 - Roadway (3. S106 Present ROW 101122.dgn”
- Attachment B –
 - Hydro (R1_Minimum Bridge Length_Package14)





South Carolina
Department of Transportation

NOTICE OF RECEIPT
Bridge Package 14
Design-Build – Contract ID 1162220
Cherokee County

Addendum 2

The information in this addendum shall be made part of the contract documents. PROPOSERS are instructed to incorporate the information into the previously provided RFP documents.

PROPOSERS are required to sign this document and enclose it with their Technical Proposal. Receipt of this signed document by The South Carolina Department of Transportation serves as confirmation that the PROPOSER has received and incorporated this Addendum into the contract documents.

Confirmation Statement:

I, the PROPOSER confirm that I have received this addendum package and have incorporated the information provided in the addendum into the contract documents.



PROPOSER's Signature

10/17/2022

Date

Ignacio Botella

Printed Name

For: The Lane Construction Corporation

Design-Build Team Name





Executive Management
Lane & ICE

SCDOT RCE
(D4)

PROJECT MANAGER
Jeffrey Dean Nichols, Jr. ^{Lane}

Project, Subcontractor &
Supplier Administration
LANE

Safety
Lane

Quality Management /
Construction QC Team
ICE

Public Relations
ICE

ASSISTANT PROJECT MANAGER
Matthew Reed Miltner, PE ^{Lane}

PRE-CONSTRUCTION TEAM

CONSTRUCTION TEAM

LEAD DESIGN ENGINEER
Warren Ray Spence, Jr. PE ^{ICE}

CONSTRUCTION MANAGER
Donato Aguirre Mondragon ^{Lane}

Structural Engineering
ICE

Roadway Engineering
ICE

Hydraulic Engineering
ICE

Geotech Engineering
ICE & STE (drilling)

Utility Coordination
ICE

Pre-Design Surveys
ICE

ROW Acquisition
Services
COL

Environmental
Compliance / Permitting
ICE / Palustrine Group

Bridge & Demolition
Superintendents
Lane

Grading & Drainage
Superintendents
Lane

Construction Engineers / Surveyors
Lane

Major Subcontractors
Paving

Utility Coordination
ICE / Lane

Specialty Subcontractors
Traffic Control, Erosion Control, Signs,
Guardrail, Pavement Markings, Rebar,
Barrier, Grooving

Design Quality Review Team (DQRT)
ICE
(Structures, Geotech, Roadway, Hydrology/Hydraulic)

FIRM LEGEND

Construction
Lane – The Lane Construction Corporation
Design
ICE – Infrastructure Consulting & Engineering, PLLC
STE – SubTerra Exploration, LLC
COL – Collier Engineering & Design/Masur Consulting, Inc.
PG – Palustrine Group

Statement of Availability


On behalf of direct employer The Lane Construction Corporation, the undersigned states that the Key Individual, **Project Manager Jeffrey D. Nichols, Jr.**, identified in the Team Organizational Chart as Project Manager for the Bridge Package 14 Design-Build Project, will be available, barring any unforeseen circumstances, at the earliest of the times and durations identified in the RFQ and RFP until expiration of the Warranty Period, or such earlier date as the Contract is terminated or SCDOT releases, in writing, such Key Individual from this requirement.

Signed this 13th day of October 2022

A blue ink signature of David J. Rankin, written in a cursive style.

David J. Rankin, Vice President, Construction
The Lane Construction Corporation

Co-Signed

A blue ink signature of Jeffrey D. Nichols, Jr., written in a cursive style.

Jeffrey D. Nichols, Jr, Project Manager
The Lane Construction Corporation

Statement of Availability


On behalf of direct employer The Lane Construction Corporation, the undersigned states that the Key Individual, **Assistant Project Manager Matthew Reed Miltner, PE**, identified in the Team Organizational Chart as Assistant Project Manager for the Bridge Package 14 Design-Build Project, will be available, barring any unforeseen circumstances, at the earliest of the times and durations identified in the RFQ and RFP until expiration of the Warranty Period, or such earlier date as the Contract is terminated or SCDOT releases, in writing, such Key Individual from this requirement.

Signed this 13th day of October 2022

A blue ink signature of David J. Rankin, written in a cursive style.

David J. Rankin, Vice President, Construction
The Lane Construction Corporation

Co-Signed


A blue ink signature of Jeffrey D. Nichols, Jr., written in a cursive style.

Jeffrey D. Nichols, Jr, Project Manager
The Lane Construction Corporation

Statement of Availability


On behalf of direct employer Infrastructure Consulting & Engineering, PLLC the undersigned states that the Key Individual, **Lead Design Engineer, Ray Spence, PE** identified in the Team Organizational Chart as Lead Design Engineer for the Bridge Package 14 Design-Build Project, will be available, barring any unforeseen circumstances, at the earliest of the times and durations identified in the RFQ and RFP until expiration of the Warranty Period, or such earlier date as the Contract is terminated or SCDOT releases, in writing, such Key Individual from this requirement.

Signed this 13th day of October 2022



Elham Farzam, President & CEO
Infrastructure Consulting & Engineering, PLLC

Co-Signed



Jeffrey D. Nichols, Jr, Project Manager
The Lane Construction Corporation

Statement of Availability


On behalf of direct employer The Lane Construction Corporation, the undersigned states that the Key Individual, **Construction Manager Donato Aguirre Mondragon**, identified in the Team Organizational Chart as Construction Manager for the Bridge Package 14 Design-Build Project, will be available, barring any unforeseen circumstances, at the earliest of the times and durations identified in the RFQ and RFP until expiration of the Warranty Period, or such earlier date as the Contract is terminated or SCDOT releases, in writing, such Key Individual from this requirement.

Signed this 13th day of October 2022

A blue ink signature of David J. Rankin, written in a cursive style.

David J. Rankin, Vice President, Construction
The Lane Construction Corporation

Co-Signed

A blue ink signature of Jeffrey D. Nichols, Jr., written in a cursive style.

Jeffrey D. Nichols, Jr, Project Manager
The Lane Construction Corporation

Confidential and Proprietary Information Page List

There are no elements of this Technical Proposal that are considered confidential or proprietary.



Columbia, South Carolina

**SOUTH CAROLINA DEPARTMENT
OF
TRANSPORTATION**

PRIME CONTRACTOR

PREQUALIFICATION CERTIFICATE

This Certifies that your company has complied with the rules and regulations of the Department and the State of South Carolina, and subject to the rules and regulations for a prime contractor, is declared eligible to submit a bid and be awarded any construction contract issued by the Department, subject to obtaining proper bonds and insurance acceptable to the Department and complying with all other statutory and contract requirements.

ALL BIDS SUBMITTED TO THE DEPARTMENT MUST BE IN THE NAME AS SHOWN BELOW.

THE LANE CONSTRUCTION CORPORATION

Vendor ID: 1TH013

Issued : October 18, 2022

Expires: October 31, 2023

Approved By: *Maria A. Smith*
Prequalification Coordinator

Quality Credit Matrix

Number	Description	Added Value/Benefits	Cost/Schedule Impacts	Self-imposed Assurance
1	Reduced ROW compared to SCDOT Conceptual Design	Our Team's design requires 0.594 acres (20%) less ROW.	Estimated savings of \$10,000	It is in the Lane/ICE Team's best interest to maintain this reduction in ROW, as additional ROW would be the result of additional earthwork associated in final design.
2	Use of longer span at S-138 over Goucher Creek	a) Eliminates interior bent b) Improves hydraulic conveyance and reduces scour potential c) Reduces drift build up and the need for maintenance crews to clear accumulated drift debris d) Reduces the number of locations for potential joints, bearing assemblies, and overall elements considered as maintenance items for SCDOT	Accelerates schedule by 10 days Estimated savings of \$80,000	This approach enables our Team to submit the most cost-effective design. Our price proposal will include the savings associated with this design, so we consider this a contractual requirement that is part of the Agreement.
3	FATC 1 (eliminate skew) + Use of Longer Span at S-86 over Kings Creek	a) Eliminates interior bent b) Improves hydraulic conveyance and reduces scour potential c) Reduces drift build up and the need for maintenance crews to clear accumulated drift debris d) Reduces the number of locations for potential joints, bearing assemblies, and overall elements considered as maintenance items for SCDOT	Accelerates schedule by 10 days Estimated savings of \$80,000	This FATC allows our Team to submit the most cost-effective design. Our price proposal will include the savings associated with this FATC, so we consider this a contractual requirement that is part of the Agreement.
4	Asphalt on bridge decks will be saw cut transversely at each bent location, and joints will be sealed with cold applied joint filler	Controls joint cracking and spalling of asphalt, reducing the long-term maintenance costs to SCDOT-	Increased cost of \$5,000	Joint details will be included in the RFC bridge plans.
5	All cast-in-place concrete substructure components will be constructed with a 5000 psi concrete mix versus the required 4000 psi	Provides superior strength and long-term performance and reduces future maintenance costs	Increased cost of \$5,000	5000 psi concrete will be required by the RFC bridge plans.
6	Lowering the existing bridge low chord at sites S-138 over Goucher Creek, S-226 over Unnamed Stream, and S-86 over Kings Creek	Lowers fill height and negates the need for steep slopes and/or use of "sliver fill" for road widening on roadway approaches	Estimated savings of \$40,000	All changes to the bridge low chord will comply with the RFP criteria.
7	FATC 2 - S-226 over Unnamed Stream	Significant reduction in stream impacts and required ROW	\$200,000 cost reduction associated with reduction in stream mitigation credits required 20 days saved by not relocating stream	This FATC allows our Team to submit the most cost-effective design. Our price proposal will include the savings associated with this FATC, so we consider this a contractual requirement that is part of the Agreement.
8	FATC 2 - S-106 over Branch of Suck Creek	Significant reduction in stream impacts and required ROW	\$45,000 cost reduction associated with reduction in stream mitigation credits required 15 days saved by not relocating stream	This FATC allows our Team to submit the most cost-effective design. Our price proposal will include the savings associated with this FATC, so we consider this contractual requirement that is part of the Agreement.

Cost/Schedule Impacts – Describe the Cost in dollars and/or Schedule impacts in days associated with the feature (positive or negative).
Self-imposed Assurance – Discuss any penalties or liquidated damages that will apply in the event the CONTRACTOR cannot implement the feature as described.

APPROVED FORMAL ATCS



APPENDIX C

Formal ATCs Resubmittal

Date Received: 9/29/2022

Lane			SCDOT		Final?
ATC No.	Primary Discipline	Concept	Response	Justification	
1	Hydrology	S-86 two span with no skew	Approved		Yes
2	Geotechnical	Alternative detail to protect roadway fill slopes	Approved		Yes
3	Pavement	Additional pavement options for bridge approaches - CMRB	Approved		Yes





Formal Alternative Technical Concepts Submittal Form

Project: Bridge Package 14Project ID: 1162220

ATC No.: 1Priority: HighTeam: The Lane TeamDate: 9/23/22

Description (required):

This ATC proposes a two span layout for the S-86 bridge over Kings Creek where none of the bridge foundations are skewed.

Usage:

This ATC applies only to the S-86 bridge over Kings Creek.

Deviations (required):

Exhibit 4b section 2.1.6 - Provide the minimum channel span length, minimum bridge length, and minimum bent skew angle (measured from a line perpendicular to the alignment centerline) at each site as listed in Attachment B - Hydrology. At S-86 over Kings Creek, the minimum skew is 15 degrees.

Justification:

The conceptual bridge layout provided in the RFP is three spans (30'-100'-30'). Bent 2 is skewed to be parallel with the stream. The existing bridge also has a interior bent at this location (bent 2) that is not skewed and is experiencing significant erosion in front of the pilings (see Attachment 1). By using a two span bridge (115'-45'), we eliminate the need for a bent on this side of the stream which will mitigate any future issues if the channel continues to move in this direction. By not skewing the end bents, we maintain the current bridge opening. By hydraulic modeling we have confirmed the proposed bridge will not result in backwater greater than 1-foot compared to natural conditions. All other hydraulic criteria in Exhibit 4e will be achieved.

Schedule:

Approval of this ATC will eliminate one interior bent therefore accelerating bridge construction by 2.5 weeks.

Impacts:

There are no additional impacts associated with this ATC.

History:

The existing bridge was constructed as a five-span, 150-foot bridge in 1957 (30-foot precast double tee beam spans). Based on a review of construction plans for the existing bridge, interior bent 2 (Sta. 49+38) was originally located approximately 60 feet from the nearest bank along Kings Creek in 1957. Today, the channel has migrated significantly toward the western abutment, and high flows have eroded the overbank and caused the channel to shift to within approximately 5 feet of bent 2. The channel migration has likely been exacerbated by debris collection on the interior bents and deflection of flow toward the west abutment. The damage to the existing bridge in the vicinity of bent 2 is reflected in the most recent NBIS codes for the substructure (Item 60; Code 5; minor damage to bridge elements), channel protection (Item 61; Code 5; major damage and erosion of channel) and scour condition (Item 113; Code 3; scour critical; bridge foundations unstable).

Risks:

This ATC reduces the potential for debris accumulation and eliminates an interior bent on the outside bank of a meander bend that is currently experiencing erosion and damage along the channel bank. The potential for abutment scour is



Formal Alternative Technical Concepts Submittal Form

Project: Bridge Package 14Project ID: 1162220

ATC No.: 1Priority: HighTeam: The Lane TeamDate: 9/23/22

reduced since we are not placing fill inside the current bridge opening area, and the potential for local pier scour on the overbank is eliminated. Since the interior bent that is proposed to be eliminated is in a high flow conveyance zone with an increased potential for debris drift, removing the potential for debris accumulation on the substructure also eliminates the possibility of local damage to the overbank and abutment due to debris blockage. This reduces the risk of major repair work or even bridge replacement.

Costs (required):

The elimination of an interior bent will save approximately \$250,000.

Quality:


By eliminating the minimum skew angle requirement and removing an interior bent, we are providing a larger opening which reduces risk and future maintenance. Our proposed foundations have been arranged so that they do not conflict with the timber pilings of the current bridge.

Operations & Maintenance:

Our proposed bridge layout greatly reduces the potential for scour and debris build up, thus saving on maintenance and future repair costs. The conceptual bridge layout would likely result in new fill being placed in the overbank area on the upstream side of the western abutment as a result of the proposed skew. There is a large amount of flood discharge flowing into the bridge opening from the western floodplain (approximate 400 foot floodplain width on that side just upstream of Road S-86), and any new fill placed in this flow transition zone would be subject to higher velocities and scour. By removing the skew, this ATC would provide abutments that are aligned more parallel to the flow transition lines, and little or no new fill would be required along the western abutment. Compared to the conceptual bridge plan, the ATC would result in reduced flow transition velocities, a lower potential for abutment scour, and less probability of abutment maintenance and repairs in the future.



Attachment 1 - FATC #01



Bent 3



Bent 2 (ATC design avoids a Bent at this location)



Formal Alternative Technical Concepts Submittal Form

Project: Bridge Package 14 Project ID: 1162220

ATC No.: 2 Priority: High Team: The Lane Team Date: 9/23/22

Description (required):

This ATC proposes an alternate detail to protect roadway fill slopes adjacent to ditches/streams by armoring the slope with rip rap and geotextile fabric.

Usage:

This ATC applies to S-226 over Unnamed Stream and S-106 over Branch of Suck Creek.

Deviations (required):

RFP Attachment B contains the "Detail Of Ditch At Toe Of Fill". This detail shows a 5' wide berm sloped at 20:1 between a 2:1 fill slope and a 2:1 slope for a V-ditch.

Justification:

Bridge embankment fill slopes are commonly protected with rip rap (see SCDOT standard drawing 804-105-00). To further protect the slope we will take the rip rap up to the 100 year flood elevation. In cases where the embankment requires reinforcement (steeper than 2:1), rip rap will be installed on the entire face of slope.

Schedule:

Approval of this ATC will enable these sites to go to construction faster since impacts to WOUS are less.

Impacts:

This ATC will reduce stream impacts and if we are able to show no functional loss may eliminate the need to purchase mitigation credits. There will also be a reduction in the amount of new right of way required.

History:

SCDOT standard drawing 804-105-00 (Riprap - Bridge End) is used to protect bridge abutments from floods and scour all across the state.

Risks:

SCDOT standard drawing 804-105-00 will be followed to mitigate any risks to the Department. Rip rap will be buried 2' below the original ground line.

Costs (required):

We estimate savings in mitigation cost savings, roadway work and right of way to be \$500,000.

Quality:

This ATC will not have any negative effects on quality.

Operations & Maintenance:

Operations & Maintenance will be unaffected.




Formal Alternative Technical Concepts Submittal Form


Project: Bridge Package 14 Project ID: 1162220

ATC No.: 2 Priority: High Team: The Lane Team Date: 9/23/22







RFP Detail



S-226 OVER UNNAMED STREAM



S-106 OVER BRANCH OF SUCK CREEK





Formal Alternative Technical Concepts Submittal Form

Project: Bridge Package 14Project ID: 1162220

ATC No.: 3Priority: MedTeam: The Lane TeamDate: 9/23/22

Description (required):

The Lane Team proposes the use of additional pavement options for the construction of roadway approaches for Bridge Package 14 by incorporating Cement Modified Recycled Base (CMRB) in order to provide a more efficient pavement section.

Usage:

New option with CMRB layer would be used as prescribed within new pavement groups 1, 2, and 3. Pavement Option 3 is summarized in Attachment 1. The structural number (SN) calculations for the RFP and FATC options are shown in Attachments 2 through 7. The latest edition of the SCDOT CMRB Supplemental Technical Specification (SC-M-306) will be used. Curing method A will only be allowed if there is no damage prior to paving. If single treatment is damaged then method b with additional chip seal application is required.

Deviations (required):

Exhibit 4c Section 2.1 lists two options for the pavement design of each road. This FATC requests approval for a new option (Option 3) as summarized in Attachment 1 using either a 6-inch thick, 10-inch thick or a 12-inch thick layer of CMRB with 175 psy HMA Surface Type C or Type D. A paving fabric will be used between the CMRB and asphalt surface course to reduce the potential for reflection cracking.

Justification:

CMRB takes advantage of demolished material on site, and by adding cement and using on-site and off-site earth and aggregate in the reclamation process, results in a very efficient and reliable base for the pavement.

Schedule:

No schedule changes are anticipated.

Impacts:

There would be no adverse impact from the approval of this FATC.

History:

SCDOT has been using Cement-Modified CMRB as a base material for pavement since 1994, incorporating the recycling of existing aged asphalt material. SCDOT has recycled 4 million square yards of asphalt since 2016 and 8 million square yards since 2006.

Risks:

There are no increased risks.

Costs (required):

The net estimated savings is approximately \$100,000.



Formal Alternative Technical Concepts Submittal Form

Project: Bridge Package 14Project ID: 1162220

ATC No.: 3Priority: MedTeam: The Lane TeamDate: 9/23/22

Quality:

This ATC will increase the quality of the final product by eliminating the need to perform full depth patching of the roadway approaches since the CMRB operation will reconstruct the entire roadway section.

Operations & Maintenance:

Operations and Maintenance will be unaffected.



Attachment 1 - FATC #03



2. CRITERIA

2.1 New Pavement

For new pavement and replacement of mainline, use the following structure:

	Route	Option 1	Option 2
Group 1	Cherokee S-56	175 psy HMA Surface Type C or Type D 450 psy HMA Base Type A or Type B	175 psy HMA Surface Type C or Type D 8 inches GABC
Group 2	Cherokee S-86 Cherokee S-106 Cherokee S-226	150 psy HMA Surface Type C or Type D 175 psy HMA Surface Type C ¹⁾ 600 psy HMA Base Type A or Type B	150 psy HMA Surface Type C or Type D 175 psy HMA Surface Type C ¹⁾ 10 inches GABC
Group 3	Cherokee S-138	175 psy HMA Surface Type C or D 175 psy HMA Surface Type C ¹⁾ 600 psy HMA Base Type A or B	175 psy HMA Surface Type C or D 300 psy HMA Intermediate Type C 10 inches GABC

¹⁾ 200 psy HMA Intermediate Type B or C can be substituted

RFP Pavement Options

	Route	Option 3
Group 1	Cherokee S-56	175 psy HMA Surface Type C or Type D Non Woven Paving Fabric 6 inches CMRB
Group 2	Cherokee S-86 Cherokee S-106 Cherokee S-226	175 psy HMA Surface Type C or Type D Non Woven Paving Fabric 10 inches CMRB
Group 3	Cherokee S-138	175 psy HMA Surface Type C or Type D Non Woven Paving Fabric 12 inches CMRB

Proposed Option 3



Attachment 2 - FATC #03



RFP Pavement Options

Flexible Pavement Design



Road:	SCDOT Bridge Package 14	Date:	9/16/2022
County:	Cherokee	Analysis by:	Elham Farzam
Description:	Group 1 Pavement (option 1)	Checked by:	Andy Gillis

Conversion of Pavement Design to Thickness

1. Surface and Binder Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a1	Dep A1	SN Year (0-10)
AC Surface	175	105	1.67	0.44	0.26	0.73
AC Intermediate		105	0.00	0.44	0.26	0.00
Over 400 PSY Thickness		105	0.00	0.34	0.34	0.00
SUBTOTAL						0.73
2. Base Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a2	Dep A2	SN Year (0-10)
Asphalt Aggregate Base		450	4.29	0.34	0.34	1.46
Graded Aggregate Base				0.18	0.18	0.00
Cement-Modified Recycled Base				0.26	0.26	0.00
Cement Stabilized Earth Base				0.25	0.25	0.00
Cement Stabilized Agg. Base				0.34	0.34	0.00
SUBTOTAL						1.46
3. Subbase Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a3	Dep A3	SN Year (0-10)
Earth Subbase				0.08	0.08	0.00
Soil Agg. Subbase				0.10	0.10	0.00
Cement-Modified Subbase				0.15	0.15	0.00
SUBTOTAL						0.00
Total SN Provided						2.19

Flexible Pavement Design



Road:	SCDOT Bridge Package 14	Date:	9/16/2022
County:	Cherokee	Analysis by:	Elham Farzam
Description:	Group 1 Pavement (option 2)	Checked by:	Andy Gillis

Conversion of Pavement Design to Thickness

1. Surface and Binder Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a1	Dep A1	SN Year (0-10)
AC Surface	175	105	1.67	0.44	0.26	0.73
AC Intermediate		105	0.00	0.44	0.26	0.00
Over 400 PSY Thickness		105	0.00	0.34	0.34	0.00
SUBTOTAL						0.73
2. Base Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a2	Dep A2	SN Year (0-10)
Asphalt Aggregate Base			0.00	0.34	0.34	0.00
Graded Aggregate Base			8	0.18	0.18	1.44
Cement-Modified Recycled Base				0.26	0.26	0.00
Cement Stabilized Earth Base				0.25	0.25	0.00
Cement Stabilized Agg. Base				0.34	0.34	0.00
SUBTOTAL						1.44
3. Subbase Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a3	Dep A3	SN Year (0-10)
Earth Subbase				0.08	0.08	0.00
Soil Agg. Subbase				0.10	0.10	0.00
Cement-Modified Subbase				0.15	0.15	0.00
SUBTOTAL						0.00
Total SN Provided						2.17



Attachment 3 - FATC #03



Proposed Option 3

Flexible Pavement Design



Road:	SCDOT Bridge Package 14	Date:	9/16/2022
County:	Cherokee	Analysis by:	Elham Farzam
Description:	Group 1 Pavement (CMRB ATC)	Checked by:	Andy Gillis

This Option provides a SN > 2.19 (Group 1 - Option 1)

Conversion of Pavement Design to Thickness						
1. Surface and Binder Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a1	Dep A1	SN Year (0-10)
AC Surface	175	105	1.67	0.44	0.26	0.73
AC Intermediate		105	0.00	0.44	0.26	0.00
Over 400 PSY Thickness		105	0.00	0.34	0.34	0.00
SUBTOTAL						0.73
2. Base Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a2	Dep A2	SN Year (0-10)
Asphalt Aggregate Base			0.00	0.34	0.34	0.00
Graded Aggregate Base			0	0.18	0.18	0.00
Cement-Modified Recycled Base			6	0.26	0.26	1.56
Cement Stabilized Earth Base				0.25	0.25	0.00
Cement Stabilized Agg. Base				0.34	0.34	0.00
SUBTOTAL						1.56
3. Subbase Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a3	Dep A3	SN Year (0-10)
Earth Subbase				0.08	0.08	0.00
Soil Agg. Subbase				0.10	0.10	0.00
Cement-Modified Subbase				0.15	0.15	0.00
SUBTOTAL						0.00
Total SN Provided						2.29



Attachment 4 - FATC #03



RFP Pavement Options

Flexible Pavement Design



Road:	SCDOT Bridge Package 14	Date:	9/16/2022			
County:	Cherokee	Analysis by:	Elham Farzam			
Description:	Group 2 Pavement (option 1)	Checked by:	Andy Gillis			
Conversion of Pavement Design to Thickness						
1. Surface and Binder Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a1	Dep A1	SN Year (0-10)
AC Surface	150	105	1.43	0.44	0.26	0.63
AC Intermediate	175	105	1.67	0.44	0.26	0.73
Over 400 PSY Thickness		105	0.00	0.34	0.34	0.00
SUBTOTAL						1.36
2. Base Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a2	Dep A2	SN Year (0-10)
Asphalt Aggregate Base		600	5.71	0.34	0.34	1.94
Graded Aggregate Base				0.18	0.18	0.00
Cement-Modified Recycled Base				0.26	0.26	0.00
Cement Stabilized Earth Base				0.25	0.25	0.00
Cement Stabilized Agg. Base				0.34	0.34	0.00
SUBTOTAL						1.94
3. Subbase Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a3	Dep A3	SN Year (0-10)
Earth Subbase				0.08	0.08	0.00
Soil Agg. Subbase				0.10	0.10	0.00
Cement-Modified Subbase				0.15	0.15	0.00
SUBTOTAL						0.00
				Total SN Provided		3.30

Flexible Pavement Design



Road:	SCDOT Bridge Package 14	Date:	9/16/2022			
County:	Cherokee	Analysis by:	Elham Farzam			
Description:	Group 2 Pavement (Option 2)	Checked by:	Andy Gillis			
Conversion of Pavement Design to Thickness						
1. Surface and Binder Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a1	Dep A1	SN Year (0-10)
AC Surface	150	105	1.43	0.44	0.26	0.63
AC Intermediate	175	105	1.67	0.44	0.26	0.73
Over 400 PSY Thickness		105	0.00	0.34	0.34	0.00
SUBTOTAL						1.36
2. Base Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a2	Dep A2	SN Year (0-10)
Asphalt Aggregate Base			0.00	0.34	0.34	0.00
Graded Aggregate Base			10	0.18	0.18	1.80
Cement-Modified Recycled Base				0.26	0.26	0.00
Cement Stabilized Earth Base				0.25	0.25	0.00
Cement Stabilized Agg. Base				0.34	0.34	0.00
SUBTOTAL						1.80
3. Subbase Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a3	Dep A3	SN Year (0-10)
Earth Subbase				0.08	0.08	0.00
Soil Agg. Subbase				0.10	0.10	0.00
Cement-Modified Subbase				0.15	0.15	0.00
SUBTOTAL						0.00
				Total SN Provided		3.16



Attachment 5 - FATC #03



Proposed Option 3

Flexible Pavement Design



Road:	SCDOT Bridge Package 14	Date:	9/16/2022
County:	Cherokee	Analysis by:	Elham Farzam
Description:	Group 2 Pavement (CMRB ATC)	Checked by:	Andy Gillis

This Option provides a SN > 3.30 (Group 2 - Option 1)

Conversion of Pavement Design to Thickness						
1. Surface and Binder Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a1	Dep A1	SN Year (0-10)
AC Surface	175	105	1.67	0.44	0.26	0.73
AC Intermediate		105	0.00	0.44	0.26	0.00
Over 400 PSY Thickness		105	0.00	0.34	0.34	0.00
SUBTOTAL						0.73
2. Base Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a2	Dep A2	SN Year (0-10)
Asphalt Aggregate Base			0.00	0.34	0.34	0.00
Graded Aggregate Base				0.18	0.18	0.00
Cement-Modified Recycled Base			10	0.26	0.26	2.60
Cement Stabilized Earth Base				0.25	0.25	0.00
Cement Stabilized Agg. Base				0.34	0.34	0.00
SUBTOTAL						2.60
3. Subbase Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a3	Dep A3	SN Year (0-10)
Earth Subbase				0.08	0.08	0.00
Soil Agg. Subbase				0.10	0.10	0.00
Cement-Modified Subbase				0.15	0.15	0.00
SUBTOTAL						0.00
Total SN Provided						3.33



Attachment 6 - FATC #03



RFP Pavement Options

Flexible Pavement Design



Road:	SCDOT Bridge Package 14	Date:	9/16/2022
County:	Cherokee	Analysis by:	Elham Farzam
Description:	Group 3 Pavement (option 1)	Checked by:	Andy Gillis

Conversion of Pavement Design to Thickness						
1. Surface and Binder Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a1	Dep A1	SN Year (0-10)
AC Surface	175	105	1.67	0.44	0.26	0.73
AC Intermediate	175	105	1.67	0.44	0.26	0.73
Over 400 PSY Thickness		105	0.00	0.34	0.34	0.00
SUBTOTAL						1.47
2. Base Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a2	Dep A2	SN Year (0-10)
Asphalt Aggregate Base		600	5.71	0.34	0.34	1.94
Graded Aggregate Base				0.18	0.18	0.00
Cement-Modified Recycled Base				0.26	0.26	0.00
Cement Stabilized Earth Base				0.25	0.25	0.00
Cement Stabilized Agg. Base				0.34	0.34	0.00
SUBTOTAL						1.94
3. Subbase Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a3	Dep A3	SN Year (0-10)
Earth Subbase				0.08	0.08	0.00
Soil Agg. Subbase				0.10	0.10	0.00
Cement-Modified Subbase				0.15	0.15	0.00
SUBTOTAL						0.00
Total SN Provided						3.41

Flexible Pavement Design



Road:	SCDOT Bridge Package 14	Date:	9/16/2022
County:	Cherokee	Analysis by:	Elham Farzam
Description:	Group 3 Pavement (Option 2)	Checked by:	Andy Gillis

Conversion of Pavement Design to Thickness						
1. Surface and Binder Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a1	Dep A1	SN Year (0-10)
AC Surface	175	105	1.67	0.44	0.26	0.73
AC Intermediate	225	105	2.14	0.44	0.26	0.94
Over 400 PSY Thickness	75	105	0.71	0.34	0.34	0.24
SUBTOTAL						1.92
2. Base Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a2	Dep A2	SN Year (0-10)
Asphalt Aggregate Base			0.00	0.34	0.34	0.00
Graded Aggregate Base			10	0.18	0.18	1.80
Cement-Modified Recycled Base				0.26	0.26	0.00
Cement Stabilized Earth Base				0.25	0.25	0.00
Cement Stabilized Agg. Base				0.34	0.34	0.00
SUBTOTAL						1.80
3. Subbase Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a3	Dep A3	SN Year (0-10)
Earth Subbase				0.08	0.08	0.00
Soil Agg. Subbase				0.10	0.10	0.00
Cement-Modified Subbase				0.15	0.15	0.00
SUBTOTAL						0.00
Total SN Provided						3.72



Attachment 7 - FATC #03



Proposed Option 3

Flexible Pavement Design



Road:	SCDOT Bridge Package 14	Date:	9/16/2022
County:	Cherokee	Analysis by:	Elham Farzam
Description:	Group 3 Pavement (CMRB ATC)	Checked by:	Andy Gillis

Conversion of Pavement Design to Thickness

1. Surface and Binder Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a1	Dep A1	SN Year (0-10)
AC Surface	175	105	1.67	0.44	0.26	0.73
AC Intermediate		105	0.00	0.44	0.26	0.00
Over 400 PSY Thickness		105	0.00	0.34	0.34	0.00
SUBTOTAL						0.73
2. Base Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a2	Dep A2	SN Year (0-10)
Asphalt Aggregate Base			0.00	0.34	0.34	0.00
Graded Aggregate Base				0.18	0.18	0.00
Cement-Modified Recycled Base			12	0.26	0.26	3.12
Cement Stabilized Earth Base				0.25	0.25	0.00
Cement Stabilized Agg. Base				0.34	0.34	0.00
SUBTOTAL						3.12
3. Subbase Courses						
Material	Rate (psy)	Yield	Thick. (in)	New a3	Dep A3	SN Year (0-10)
Earth Subbase				0.08	0.08	0.00
Soil Agg. Subbase				0.10	0.10	0.00
Cement-Modified Subbase				0.15	0.15	0.00
SUBTOTAL						0.00
Total SN Provided						3.85

This Option provides a SN > 3.72 (Group 3 - Option 2)