
SUPPLEMENTAL SPECIFICATION

July 1, 2026

By: _____
FEDERAL HIGHWAY ADMINISTRATION

Section 209 - Shoulders and Slopes

Modify Section 209 with the following:

209.2 Materials - Paragraph 1

Replace the entire paragraph 1 with the following:

- 1 Obtain the materials used in the construction of shoulders and slopes from the following locations:
 - Stockpiles of material stripped from within the right-of-way in the grading operation,
 - Areas outside of the cut or fill slopes in the right-of-way,
 - Stockpiles of material stripped from borrow pits,
 - Select material pits,
 - Areas of watercourse and ditch excavation,
 - Aggregate Shoulder Borrow (ASB) from a source listed on QPL 2 that meets the following:

Sieve	Percent Passing
2"	100
1/2"	55-95
No. 4	50-75

209.2 Materials - Paragraph 8

Add the following new paragraph:

- 8 Aggregate Shoulder Borrow from a source listed on the current version of QPL 2 may be used in lieu of natural soil materials for shoulder material. Do not place aggregate shoulder borrow in areas adjacent to maintained lawns.

209.4 Measurement - Paragraph 5

Add the following new paragraph:

- 5 ASB shall be measured by the Ton. Furnish the RCE with certified weight tickets for material delivered to the project.

209.5 Payment - Paragraph 3

Add the following new paragraph 3 and revised paragraph 4 (was paragraph 3):

- 3 Payment for the accepted quantity of ASB at the unit price is full compensation for furnishing all materials, labor, equipment, tools, supplies, transportation and incidentals necessary to complete the work as specified.
- 4 Pay items under this Section include the following:

Item No.	Pay Item	Unit
2091000	Select Material for Shoulders and Slopes	CY
8990695	Aggregate Shoulder Borrow	TON